



Bruce

Precinct Master Plan

Final Scenarios Report

Final Issue
04/09/2026



Australian Government

HATCH

Title: Final Scenarios Report
 Prepared for: DITRDCSA
 Reference: H377218
 Status: Final
 Date: September 3, 2026 6:48 PM
 Prepared by: Marta Francisco, Fariz Hazmi and Jack Jeffries
 Approved by: Angela Koepp
 Report Inputs:
 Landscape Architecture: Brooke Ryan - Hatch
 Planning: Hope Watson - PlanIt
 Designing With Country: Yerrabingin
 Economic Development: Leigh Holford - Hatch
 WSUD: Tommy Plahcinski - Stantec
 Sustainability: Rebecca Dracup- Stantec
 Active Travel: Chris Coath - Stantec
 Cost Estimates: Sephton Wolmarans - RLB

DISCLAIMER & COPYRIGHT

This document was prepared for the exclusive use of Department of Infrastructure, Transport, Regional Development, Communications, Sports and the Arts (DITRDCSA). Hatch acts in all professional matters as a faithful advisor to its clients and exercises all reasonable skill and care in the provision of its professional services. The information presented herein has been compiled from a number of sources using a variety of methods. Hatch does not attempt to verify the accuracy, validity or comprehensiveness of any information supplied to Hatch by third parties. The development parameters (dwelling yields, stages etc) referred to in this report are based on the information provided by the client and are not intended to be used for any other purposes of this report. Hatch makes no warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, validity or comprehensiveness of this document, or the misapplication or misinterpretation by third parties of its contents. Reference to any product, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favouring by Hatch.

This document cannot be copied or reproduced in whole or part for any purpose without the prior written consent of Hatch.

© Hatch Pty Ltd, 2026

Hatch
 Level 3, 50 Carrington Street, Sydney NSW 2000
 T: +612 8202 8000 www.hatch.com

HATCH

 **Stantec**

 **YERRABINGIN**



PLANIT
Strategic & Transport
Town Planning

 **Rider
Levett
Bucknall**

Table of Contents

Executive Summary	06
-------------------	----

1

Introduction	08
Project Overview	10
Purpose of this report	12

2

The Foundations	14
Precinct Ambition	16
Engagement Summary	18
Design Brief	20
Strategic Maps	24
Urban Design Recommendations	26

3

Context	28
Context Overview	30
A Country First & Place Led Approach	32

4

Bruce Precinct	34
----------------	----

4.1	
Stitched together by waterways & green corridors	
<u>Starting with Country</u>	38
<u>Designing with Country</u>	40
<u>Connecting with Country</u>	42

4.2	
Connected through public places & active connections	
<u>Community & Cultural Spaces</u>	46
<u>Movement Network & Access</u>	48
4.3	
Fostering innovation & anchor synergy	
<u>Economic Development</u>	72
<u>Health, Education & Sports Integration</u>	76
4.4	
Creating a new entertainment & stadium-led community	
<u>Land Use, Built Form & Density</u>	82
<u>Strategic & Statutory Planning</u>	92

4.5	
Integrated with Belconnen & beyond	
<u>Infrastructure & Servicing</u>	104
4.6	
Delivering a legacy of resilience for generations to come	
<u>Environmental Sustainability & Resilience</u>	122
<u>Indicative Costing</u>	132

5

Conclusion	134
Next Steps	136

Appendix A

Transport


Appendix B

Designing with Country

Acknowledgment of Country

We acknowledge the Traditional Custodians of Country throughout Australia and their continuing connection to culture, community, land, water, and sky.

Ê Ø æ ã Ø Ö Ü Ö Ô ß Ì Ô Ö Þ á â ê ß Ø × Ú Ø ç Û Ø Á Ú è á á Ô ê Ô ß Ô á × Á Ú Ô à Õ ã who have long cared for this Country. We pay our respects to Elders and Knowledge Holders, past and present, and express our gratitude for their continued sharing of knowledge and culture.









Executive Summary

Project Overview

Hatch and Stantec have been engaged by the Department of Infrastructure, Transport, Regional Development, Communications, Sports and the Arts (DITRDCA) to lead and coordinate the preparation of a master plan for the Bruce Precinct, a section of the suburb of Bruce in the ACT.

The report was commissioned by Commonwealth to provide advice for future decisions on the precinct. It contains investigations using scenarios to explore future outcomes and inform government decisions at all levels. The document does not represent current ACT or Australian Government policy decisions.

The master plan builds on existing strategic work and aligns with the Australian Government and ACT Government's vision for a vibrant, inclusive, and sustainable Precinct, by identifying optimal land uses within the Precinct and integrating the various existing anchors into a cohesive scheme.

This report

This report synthesises nine months of collaborative planning, analysis and design to establish a clear vision for the precinct and to provide existing and future opportunities and constraints associated with a future development capacity of the Bruce Precinct in order to guide decision-making and facilitate the highest and best use.

The process has been grounded in iterative engagement, including workshops with the project Working Group and meaningful consultation with Ngannawal and Ngambri stakeholders, alongside comprehensive background, place and site analysis to frame opportunities and constraints.

The report sets out a set of guiding principles and tests two spatial scenarios against the eight core elements of the design brief, translating these into integrated urban design responses.

The development potential of Bruce Precinct is described within this document through a multidisciplinary lens—including transport, landscape, infrastructure, sustainability, planning and economic development—to understand performance, trade-offs and delivery considerations.

This approach ensures the direction is both strategically aligned and practically achievable, balancing place outcomes with technical and commercial realities in the trajectory to the ultimate realisation of the long-term vision for Bruce Innovation Precinct.

01

INTRODUCTION

Project Overview

The Bruce Precinct comprises several distinct

Ü á æ ç Ü ç è ç Ü â á æ Ô á × Û è Õ æ ÿ Ô ß ß â Ù ê Û Ü Ö Û â ã Ø å Ô ç Ø Ü á è á Ü ä è Ø ß × æ ê Ü ç Û ß â Õ Õ ß ç Û å â è Ú Û ç â Û Õ å å Ø Õ Õ Û Ü á Ú æ Ü Ü á Ü Õ Õ á Õ Ø

The Final Scenarios Report will deliver options for the integration of these various existing developments

into a cohesive place, delivering optimal land uses

Ü á Õ ß è × Ü á Ú â ã ã â å ç è á Ü ç Ü Ø æ Û â å è å Õ Õ á å Ø á Ø ê Õ ß ÿ Ô á × Ø á Û Õ á Õ Ü á Ú æ ì á Ø å Ú Ü Ø æ Õ Ø ç ê Ø Ø á ç Ü Ø ã å Ø Õ Ü á Õ ç Ô á Õ Û â å æ ÿ

The Project

The project has been overseen by both levels of government, including through a working group, with the overall ambition of seeking information for future government decision making.

The Working Group, together with Client, endorsed at ç Û Ø å æ ç å Þ æ Ü Ü Ø å å Ý Ø Õ Ü é Ø å æ

- achieving highest and best land use including urban renewal
- delivering integration of existing sites into a cohesive place
- enhancing synergies between anchors


At that session a series of critical inputs were mapped out and curated to help establish the design brief.

Those inputs were then tested at the March workshop, ã å â é Ü × Ü Ø å × Ü á Õ æ × Õ ã ã Ü ç Û Õ ç å å à Ø Ø Ø scenarios in the Scenarios Report, later expanded into the Strategic Map report. This report subsequently added eight Urban Design Recommendations, inspired by learnings from the scenarios, that have informed the spatial advice included in the Final Scenarios report.


In parallel, the Precinct Ambition Report has set out the Place Principles that enable the delivery of the Place Vision. This Vision was initially set out by the project team and workshopped with the Working Group.

In this report, the scenarios are now critically assessed through a multidisciplinary lens—including transport, landscape, infrastructure, built form, sustainability, planning and economic development—to understand performance, trade-offs and delivery considerations.

Project team structure




Project Milestones




Purpose of this report

constraints shaping the development capacity of the Bruce
planning and economic development.


PLACE PRINCIPLES



URBAN DESIGN RECOMMENDATIONS



REPORT CHAPTERS




Document Structure

The report is structured into four key sections:

- 1. Introduction** - Provides an overview of the project and the purpose of this report.
- 2. The Foundations** - Summarises the scope of work undertaken over the past nine months highlighting design brief, the key reference documents and engagement and their respective insights and takeaways.

- 3. Context** - Establishes the site context and outlines the methodology.
- 4. Bruce Precinct** - Organised around the place principles, this section outlines the opportunities and constraints informing the future development capacity of the Bruce Precinct, providing a basis for decision-making and enabling its highest and best use through a multidisciplinary lens.




02

THE FOUNDATIONS

Precinct Ambition

Recommendations includes a constant review against identity.



The Precinct Ambition was developed through a multi-layered process:

- establishing context (alignment with broader policy, investment directions, and governance frameworks as well as building an understanding of physical setting, assets, opportunities and constraints, users, etc),
- a range of perspectives and aspirations into design moves),
- and benchmarking (ensure its forward-looking, competitive, and grounded in proven models).

Synthesised into a clear overarching Place Vision: 'The Bruce Innovation Precinct anchors are stitched together by a whole of Government ambition towards wellbeing, learning and legacy built on the strong foundations of Country, public life and long-term viability' that articulates the future identity of the Precinct and a set of supporting **PLACE PRINCIPLES** that translate the vision into actionable and strategic directions.

PLACE PRINCIPLES



STITCHED TOGETHER BY WATERWAYS AND GREEN CORRIDORS

A network of green spaces and water systems stitches the precinct together, supporting amenity, ecology, and movement.



FOSTERING INNOVATION AND ANCHOR SYNERGY

Key institutions and assets collaborate to drive research, learning, and high-performance outcomes.




CONNECTED THROUGH PUBLIC PLACES AND ACTIVE CONNECTIONS

Strong public spaces and social connections enable easy movement and vibrant, active places that community wants to visit and linger.



INTEGRATED WITH BELCONNEN AND BEYOND

The precinct is embedded within the broader urban context. It celebrates its national reputation while meeting local needs.



DELIVERING A LEGACY OF RESILIENCE FOR GENERATIONS TO COME

Urban development is designed for long-term adaptability, environmental resilience, and




CREATING A NEW ENTERTAINMENT AND STADIUM- LED COMMUNITY

Sporting and entertainment assets act as catalysts for community and public life, visitation, and economic activity.

Engagement Summary

Despite the transformations that have occurred
European settlement, the deep systems of
Country remain intact. This truth must guide
development.



Community Engagement Outcomes



Country as our Teacher

We listen deeply to the needs of Country and walk together with our peers to foster connection. Drawing on Cultural knowledge, we observe the cues Country offers to understand how to maintain balance. This outcome recognises country as a source of knowledge, guidance and Cultural truth, inviting visitors and the local community to slow down, observe, and learn.



Country as our Healer

Health and wellbeing at the centre of Bruce, means a healthy Community, and healthy Country. Promote physical, mental and Cultural wellbeing through nature, sport, recreation, and shared healing spaces. This theme requires us to heal Country so that Country can heal and bind community and kin.



Country as our Legacy

Legacy is established through practices of caring for Country and Non-human Kin, which allows for preservation of traditions, landscapes and ecological systems. This theme is all about building a resilient Country that will span across generations and thrive with time, leaving a lasting legacy of Place deep in time.

As part of the Stakeholder and Engagement Plan a series of workshops were undertaken in the March workshop. Two scenarios were developed, based on the eight established Design Brief elements.

An 'Opportunities and Trade-offs' activity was undertaken in the March workshop. Two scenarios were developed, based on the eight established Design Brief elements.



- Rapid Transit** - Central route via Bruce Ridge Reserve existing track
- Stadium** - Retain existing site for redevelopment
- GDE** - Off ramp adjacent to hospital/ICT
- Hospital** - Site remains, increase precinct connectivity
- CIT Future** - Campus remains in current location
- Housing Needs** - New housing to be located on site, investigate opportunity on CIT site, existing stadium site, and south-west AIS site.
- Bruce Ridge Remnant Reserve Area** - Assume preservation of natural area.
- AIS Master Plan** - Potential for community areas to be allocated to the south of the campus. Consideration of divestment and land swaps.

Design Brief



Figure 01. Bruce Precinct Summary Plan from the 'Background Review and Place Analysis' Report

Existing commitments and strategic priorities include:

Sports

A Fit for Purpose Australian Institute of Sport Independent Review recommends renewal as a catalyst for a broader sport, health and education precinct via a coordinated master plan rather than solely on elite outcomes.

Access

Address challenges on game day, and explore improvements along Gungahlin Drive.

Stadium

Australian Government agrees in principle with Recommendation 14 of A Capital for all Australians, in which the Committee recommends that the Commonwealth Government work with the ACT Government to upgrade Canberra's stadium infrastructure.

Housing

Under the National Housing Accord, the ACT is required to deliver approximately 21,000 new well-located dwellings by 2029. Precincts, such as Bruce, with strong access to health, education, employment and public transport, are well-placed to deliver this.

Health

ACT Government's largest single investment in a health infrastructure - the new North Canberra Hospital will be built on the existing hospital campus in Bruce, early works scheduled for late April 2026. It will remain open and fully operational during the delivery, which Canberra Health Services will manage it after delivery.

Canberra's light rail network is not yet funded, strategic planning is ongoing, with Bruce expected to be a key station.

LEGEND

- Bruce Study Area
- AIS
- CIT
- Hospital
- Box-Gum Woodland
- Urban Ponds and Lakes
- Mature Native Tree Canopy

Scale
1:15,000 @ A4



0m 150 300 450 600 750m

Design Brief (continued)

commitments, and strategic priorities that inform the development of future scenarios for the Bruce. Infrastructure investments and known constraints into a clear framework to guide scenario testing and option development.

well as components requiring critical decisions for their advancement, hence requiring a focus of investigation and testing. These elements are the core building blocks of infrastructure investments, protected assets, statutory requirements and operational commitments that establish the fundamental parameters to commence strategic thinking on the Bruce Master Plan.

assumptions aligned with initial appreciation and further investigation was required before any of these elements could be conclusively answered, the assumptions provided a starting point to test possible outcomes with Stakeholders and led to the development of the Scenario Maps, critical in the process of delivering this report.

scenario development. These matters include the location, mix and intensity of uses, the staging of development, the integration of movement, open space and built form, and the funding of major infrastructure works such as multi-storey parking or new sporting infrastructure.

building blocks with the brief's breadth of open strategic questions provided the balance needed for this precinct's investigation. This approach ensures that future scenarios are grounded in reality while remaining to uncertainty and align with broader government objectives for growth, infrastructure delivery and long - term place quality.

The **Eight Elements** of the Precinct are
 and key decisions for their advancement

Conditions and considerations that were
 tested in Scenarios at the March Workshop



HOSPITAL

Master Plan connectivity



» Æ ¼ · Ç Å ´ Å Æ ¼ Ç

» Æ × Æ á · Æ Ü é Ø É Æ µ Æ Ç ç ì Ø Æ Ç å Ø Ø Ç
 rapid transit alignment



STADIUM

Retain or relocate stadium



ACCESS

° è á Ú Æ Ü Æ Ü á · Æ Ü é Ø Ø á Ç à ì Æ Æ Æ Æ Ç Ü Æ á É Æ Ç
 Ø á Ç à ì Æ Æ Ü á Ç Æ Ü Æ Æ Ç Æ Æ Ü Æ Æ Ü á Ç Æ Ç Ü Ø Æ Æ
 parking arrangements and infrastructure



CIT

Ç Æ á Ú Ç Ø Æ à é Æ Æ è Ø Æ Æ Æ Æ Æ Æ Ü Ç Ü Æ á Æ á ×
 Æ Æ Æ Æ Ü Æ Æ Ø Æ Æ Æ Æ Æ Æ Æ Ç Ü Æ á



» Æ È Æ ¼ Á °

Quantity commensurate with
 investment



Æ , Æ , Æ É ,

Æ Æ Æ Æ Æ Æ é Æ Ç Ü Æ á É Æ Æ Ç Ø é Æ Æ × Æ Ü Æ Æ



AIS

Master Plan land use synergies
 and athletics track location

Strategic Maps

Scenario 1

the site's central east-west core, as a branch from a deeply innovation-focused rapid transit alignment.

The plan assumes the relocation of the CIT campus and consideration of land swap arrangements. This clean slate allows the desired stadium renewal to be delivered more centrally within the precinct and proximate to the rapid transit, with space for housing, mixed-use development and public amenity surrounding all sides.

The rapid transit alignment focuses access toward the civic destinations, including the hospital, education precincts to the north, and the new stadium and transit-oriented development.

The Strategic Maps were initially developed in the March Stakeholder workshop, from different assumptions on the eight elements of the Design Brief (listed on the previous page). They form an important spatial tool to explore and investigate outcomes and map their implications in order to for future decision making.



Scenario 2

This scenario considers the introduction of a central spine whereby movement and place come together to support people, investment, activity, access and community life. This spine would be located and designed to support the existing precinct legacy anchor corridor for place- based outcomes including but not limited to high-density mixed-use frontages, active travel, event crowd movement, rapid transit, road closure destination events (sport, community, events by Traditional Custodians, etc). This corridor stitches together a renewed stadium precinct, CIT campus and æ è å å è á × 0 æ 0 ß å å à 0 æ å è ù × 0 æ 0 ß æ å 0 heart of the AIS campus, via a common central green open space.

- LEGEND
- Stadium

Mixed-use Development

Education

Sports

Health

Green Open Space

Active Sport Field

Protected Woodland/ Grassland

Potential Multi-Storey Parking

Rapid Transit Corridor

Access


Epicentre

Land Swap & Divestment

Pedestrian Corridor

Indicative New Access Road

Slip Lane Road Extension




Urban Design Recommendations

The urban design recommendations were developed directly from insights from the March Workshop. During the workshop, two scenarios were developed that tested a series of assumptions across the eight elements that make up the design brief.

Comparative testing of these two scenarios revealed a strong convergence around several preferred structural moves that have been summarised into

URBAN DESIGN RECOMMENDATIONS

The urban design recommendations were developed directly from insights from the March Workshop. During the workshop, two scenarios were developed that tested a series of assumptions across the eight elements that make up the design brief. Comparative testing of these two scenarios revealed a strong convergence around several preferred structural moves that have been summarised into



The urban design recommendations were developed directly from insights from the March Workshop. During the workshop, two scenarios were developed that tested a series of assumptions across the eight elements that make up the design brief.


Comparative testing of these two scenarios revealed a strong convergence around several preferred structural moves that have been summarised into

URBAN DESIGN RECOMMENDATIONS


The urban design recommendations were developed directly from insights from the March Workshop. During the workshop, two scenarios were developed that tested a series of assumptions across the eight elements that make up the design brief. Comparative testing of these two scenarios revealed a strong convergence around several preferred structural moves that have been summarised into




Á' Ñ¼. Ç Á' ÁÆ¼Ç μÄÈ¿,É'




°Á,,Á'Á· μ¿È, ÀÄÉ,À,ÁÇ °Á¼·




,ÄÈ¼Ç'μ¿, 'Á· '¶Ç¼É, Á,Ç




Á,Á,Ê,· 'Á· ¼ÁÇ,ÁÆ¼¹¼,·ÆÇ'




Á,Á,Ê,· 'Á· ·¼É,ÁÆ¼¹¼,·¶



¶ÄÁÁ,¶Ç,·'Á·.Á»'Á¶,·ÁÄÁÇ»
¶'Äμ,ÄÄ'HOSPITAL



AIS SEAMLESS
ÄÈμ¿¼¶ ÄÄ¼É'Ç, Ç Á' ÁÆ¼



Á,Ê Á,¼°»μÄÈÄ»ÄÄ·

03

CONTEXT

Context Overview

μ å è Ö Ø ÿ Ü á ¶ Ô á Õ Ø å å Ô à æ μ Ø ß Ö â á á Ø á × Ü æ ç å Ü Ö ç ÿ Ü æ Ô é Ü Õ å Ô á Þ á â ê á Û â å Ü ç æ Ø × è Ö Ô ç Ü â á Ô ß ÿ Û Ø Ô ß ç Ü Ô á × æ ã â å ç Ü á Ú Û è Ö æ ç â ç Ü Ø È á Ü é Ø å æ Ü ç ì â Û ¶ Ô á Õ Ø å å Ô ÿ ´ è æ ç å Ô ß Ü Ô á ¼ á æ ç Ü ç è ç Ø å ¶ Ô á Õ Ø å å Ô ¼ á æ ç Ü ç è ç Ø â Û Ç Ø Ö Ü á â ß â Ú ì ÿ Á â å ç Ü ¶ Ô á Õ Ø å å Ô » â æ Ô á × ¶ Ô á Õ Ø å å Ô Æ ç Ô × Ü è à ç Ü Ø μ Ø ß Ö â á á Ø á , × è Ö Ô ç Ü â á Ô á × Æ ã â å Innovation Precinct, where research, education and sports practice come together, has a national reputation for Ø ë Ö Ø ß ß Ø á Ö Ô á × à Ô Ú á Ü Ø æ ç Ü Ø æ ç å â á Ú × Ü æ ç å Ü Ö ç Ø Ö â á â à ì ;


The Site

The subject area (approx. 214 ha) is located in the Australian Canberra Territory, 7km northwest of Canberra's city centre, in Belconnen District. Bruce sits on gently undulating terrain between Black Mountain and Lake Ginninderra, the site is bordered by the Bruce Ridge Nature Reserve along Gungahlin Drive, Belconnen Way to the south, Haydon Drive to the west, and Battye and Braybrooke Road and Ginninderra Drive to the north, providing key access routes.

Key social infrastructure within the site include the Australian Institute of Sport and Canberra Stadium, the Bruce campus of the Canberra Institute of Technology, and the new North Canberra Hospital.

Belconnen's large town centre, Radford College, Fern Hill Park suburb, and the adjacent University of Canberra campus are very accessible to the site - a 5 to 10 minute drive away.

This precinct is part of a broader national Canberra innovation corridor linking the cluster of institutions around the ANU, the City Centre, ADFA and Fyshwick. Initiatives to support this potential role could include using future light rail stops to catalyse and support the diversity of land uses already in this area, particularly with a sport, education and health focus.



Á Ô ç Ü â á Ô ß ß ì Æ Ü Ú á Ü Ö Ô á ç Landscape Character

Surrounded by nature, Canberra is cultivating a reputation as Australia's 'Bush Capital' with 'gorges, forests and snow-capped mountains only 45-minutes' drive from the city'. The Australian Botanic Gardens, National Arboretum and Lake Mead are assets easily accessible. Walter Burley and Marion Mahony's various vistas, landscapes, roads, and institutions around the Capital.

Regionally Belconnen encompasses Lake Ginninderra, Ginninderra Creek Riparian corridor, Halls Creek, Gooromon Ponds and key grassland and woodland habitat corridors.

Figure 02. Bruce ACT Wide Context plan


 N
 Not to Scale

A Country First & Place Led Approach

Wind, soil, plants, animals, and people that sustains life and Culture. Designing with Country means recognising these interconnections and working with them to create places that endure.

and ephemeral waterways, connected to Ginninderra Creek and adjacent to Bruce Ridge Nature Reserve in an ecological corridor linking Black Mountain, O'Connor Ridge and the Molonglo River.

These connections are not incidental, they are vital pathways for species and stories. They invite us to see the precinct as part of a continuum of this important Cultural landscape of Country.

Yerrabingin's 'Connecting with Country' report

- Consideration of seasonal cycles, water management and plant use offers a guide for sustainable design.
- Strengthen links, regenerate landscapes and foster custodianship.
- Restore ecological health and Cultural connections.
- Community planting days with local custodians.
- Consider water management across the precinct through permeable surfaces, vegetated swales and wetlands.
- Acknowledge and follow natural patterns, creating paths that follow natural contours and connect people to reserves and Cultural sites.

Understanding Country



Figure 03. Deep Country - Ngunnawal Country landscape



Figure 04. Move with Country - Tidbinbilla Nature Reserve




Figure 05. Sky Country - Mist

Beginning with Country

'Country is our mother, our teacher, our library and our kin; it sustains us, inspires us and surrounds us. The experience of Country is both individual and collective, both new and familiar.

Continuing to care for Country is central to our being and our identity.'

Christian Hampson, Yerrabingin

Country reaches into and across the earth and into the sky. The unique and distinctive elements of Country are connected, and open to everyone. They are the Water, Earth, Sky, our Non-Human Kin, and ourselves. In this way, we are part of the system of Country and have a responsibility to future generations. Our actions must always be Country positive.




Figure 09. Yerrabingin. 2026. We inhabit and are inhabited by Country (source: Yerrabingin Designing with Country Report March 2026)

¶ â è á ç â ì Ö Ø á ç â Ü Ö

We inhabit and are inhabited by Country. To inhabit Country and connect with Country is to be grounded in the landscape and to practice the cultural knowledge stored within it. This encourages physical and emotional wellbeing for people and Country.

The innate symbiosis of being connected to Country moves us into being Eco or Country centric, rather than being Human centric. This connection and position in relation to Country is a central component of Aboriginal people's ideology. It is a cultural value that places humans within the ecological and landscape system, not as dominators but as caretakers and custodians. This function requires constant interaction and observation, being tuned in to reactive requirements and response.



Figure 06. Water Country - Ginninderra Creek



Figure 07. Wind Country - Grassland



Figure 08. Non-Human Kin Country - Eastern grey kangaroos

04

BRUCE INNOVATION PRECINCT

4.1

**STITCHED TOGETHER
BY WATERWAYS AND
GREEN CORRIDORS**

Starting with Country

Regional Scale: Setting the Scene

Blue, green, and Country are inherently interconnected, with through learning from Country, supporting ecological healing, and sustaining an enduring legacy of Connection to Country.

Bruce Precinct sits on Ngunnawal and Ngambri Country, to the north of Canberra. It is surrounded by mountain ranges to the east and south, with a ridgeline connecting O'Connor Ridge Reserve and Bruce Ridge Reserve to the high point of Black Mountain, forming the edge of Lake Ginninderra's water catchment, within which the precinct lies. This establishes the precinct's connection to Sky and Water Country. This landscape also supports a diverse ecological system rich in biodiversity, where patches of potentially threatened woodland and ACT's Urban Habitat Connectivity Project, a functional habitat connectivity corridor that allows non-human kin to move between habitats. Therefore, future development of the Bruce Precinct should respond to the Country system by protecting and enhancing the ecosystem, while strengthening the ongoing Connection to Country.

Connecting with Country Strategies

The three Designing with Country opportunities Yerrabingin Designing with Country Report, have been central infrastructure and open space strategies:

- a source of knowledge, guidance, and cultural truth.
- importance of healing Country so that Country can in turn heal and bind community and kin.
- and preservation of caring for Country and non-human kin across generations, enabling both to thrive over time.

Protecting and enhancing the ecosystem, as well as

facilitating and improving human-nature connections to strengthen community's ecological stewardship, is at the core of designing the Bruce Precinct. The following key principles of Biodiversity Sensitive Urban Design (BSUD) have been adopted across multi-scale strategies in the Bruce Precinct, from the precinct to

block-scale, ensuring that ecological connectivity is woven throughout the broader landscape:

- maintain and enhance nature
- connect and extend nature
- minimise threats and protect nature
- connect people to nature

Landscape Strategies

- celebrate ACT 'bush-capital' legacy to foster inter-generational pride and empowerment.
- Ensure tree canopy planning, embedding key principles to achieve a 30% urban tree canopy cover by 2045 (ACT Urban Forest Strategy)
- 30% target for permeable surfaces (ACT WSUD Guidelines, Urban Forest Act)
- Ensure a minimum of 50% of the whole site area include one or a combination of heat reducing strategies (permeable surfaces, vegetation, shading structures or water bodies)

Blue Strategies

The Bruce Precinct adopts a layered Water Sensitive Urban Design (WSUD) strategy, where water management is embedded throughout the development, from regional systems through to individual development lots. Rather than relying on a single intervention, the approach integrates precinct-scale infrastructure, street-scale systems and lot-scale controls to deliver a resilient and adaptable water cycle. This framework supports reduced potable water demand, improved stormwater performance, and

At its core, the strategy responds to four key drivers:

- reducing mains water demand through harvesting and reuse
- maintaining or reducing post-development runoff
- improving stormwater quality through distributed treatment
- supporting climate resilience, urban cooling and canopy outcomes





Figure 10. Country System



LEGEND

	Bruce Precinct		Functional Habitat Connectivity Patch (>10ha)		Non-human Kin Habitat
	Nature Reserve/Urban Open Space		Ridgeline		
	Lake Ginninderra Catchment		Water Country - Water Body		
	Potential Threatened Woodland		Water Country - Water Line		
	Urban Habitat Connectivity Project (UHCP)		High Point		

Designing with Country

Precinct Scale: Blue-Green Infrastructure

Bruce Precinct protects and enhances its woodland, grassland and wetland systems through connected ecological corridors, expanded management and a stronger Connection to Country.

It is essential for Bruce precinct to protect the ecological community, White Box–Yellow Box–Blakely's Red Gum Grassy Woodland and Derived Native Grassland, that exist on site. Future development occurring in proximity to this ecosystem should avoid or minimise ecological degradation by preventing key threats, including changes to soil nutrient levels, land clearing and fragmentation, inappropriate grazing, weed invasion, altered hydrology, inappropriate

Accordingly, future development should follow the ACT BSUD Guide and Implementation Advice.

Protect and Expand The Wetland System

Several wetland and pond systems already exist within the precinct and are to be protected. There is an opportunity to expand the northernmost wetland system, including a transient bog linked to it, to operate as multifunctional assets that manage and store water. This wetland supports rich biodiversity and hence expanding the wetland system will therefore support ecological habitat and amenity, fostering a stronger sense of connection and stewardship of Country.

Bruce Precinct should avoid or minimise impacts from future development on existing intact groups of mature native trees with dense canopy located within the precinct, as they function as critical habitat connectivity corridors across the broader landscape, particularly between Gossan Hill Nature Reserve and Bruce Ridge Nature Reserve. Wildlife crossings or tunnel infrastructure connecting the precinct to these nature reserves should be considered to reduce habitat fragmentation, especially for ground-dependent species. Moreover, future main boulevards and streets, particularly those linking the woodland to the northern wetlands, should incorporate a minimum structural soil volumes) to support large canopy trees and contribute to pollination processes.

custodians, multiple medicinal and bush tucker gardens should be located near North Canberra Hospital and Yurauna Education Centre. These gardens provide food sources and habitat for pollinators while enabling direct engagement between the community and non-human kin, strengthening connections to Country.

The Bruce Precinct proposes a strategic approach to achieve at least 30% tree canopy cover through the early integration of large-canopy trees (ASV Class 4+)

Canopy coverage will be maximised through the selection of large, climate-resilient, and predominantly indigenous species, supported by coordinated design measures such as asymmetrical verges, staggered planting, integrated civil layouts, permeable surfaces, and structural soils to enhance tree health and provide shading along key movement corridors. The plan also prioritises the retention and in line with the Urban Forest Act 2023, while preserving at least 50% of the site as nature reserve to strengthen biodiversity, maintain cultural heritage values, and exceed canopy and ecological connectivity targets.

WSUD Strategies

At the precinct scale, WSUD is anchored by centralised and reused across the site. The expanded and enhanced wetland system can provide water quality treatment, detention and storage. This may be in the form of converting ponds to wetlands or creating standalone wetland systems.

Water captured within these systems is then reused across the precinct, supporting a range of demands such as irrigation, cooling and public realm watering, of these water bodies also plays an important role in placemaking, reinforcing a strong identity centred around water and landscape.

Complementing this is a connected blue-green grid, which integrates bushland, open space and key movement corridors into a coherent framework. In this way, water is not treated as isolated infrastructure,




Figure 11. Precinct Scale Green-Blue Infrastructure

Scale 1:15,000 @ A4
N
0m 150 300 450 600 750m

LEGEND

- Endangered Ecological Communities (Woodland/Grassland)
- Protected and Enhanced Existing Wetland/Ponds
- Constructed Wetland and/or Sedimentation Basin (Indicative)
- Indicative WSUD features (e.g., vegetated swale)
- Areas of Intact Mature Nature Trees
- Connected and Expanded Ecological Corridor
- Main Green Boulevards with Prominent Shade Canopy and Cooling
- Wildlife Crossing (Tunnel/Bridge/Passage) for future investigation
- Medicinal and Bush Tucker Garden

linking hydrology, ecology and urban form.

Typical WSUD features at this scale include:

- Constructed wetlands and expanded or new stormwater ponds
- Below ground stormwater harvesting infrastructure
- Sedimentation basins for sediment/pollutant control
- Open space

Block and Street Scale: Integrated Solutions

¼ á ç Ø Ú å Ô ç Ø × . Ö â ß â Ú ì Ô á × È å Õ Ô á Æ â ß è ç Ü V I S U D Strategies Cap Street Scale Ø

- **Open spaces:** Create and maintain open spaces (with deep soil), connected via secondary green links that tie into the precinct's natural habitats (e.g. woodland and wetlands). These biodiverse open spaces could incorporate native garden beds, dense shrubs, and layered vegetation to provide food sources and habitat for pollinators, while WSUD solutions such as raingardens and vegetated swales can also be integrated to support water management and enhance habitat value.
- **Community engagement:** Develop and implement community engagement programs in collaboration with Traditional custodian communities, providing opportunities to learn from and heal with Country. This will require further engagement.
- **Active frontages:** Support and encourage active frontages, particularly in blocks with an entertainment or commercial focus. Integrating both within a single block and across precinct boundaries will further reinforce this relationship. Orienting active frontages and public spaces towards ecological areas will further reinforce this relationship.

In constrained or higher-density areas, surface systems are supported by subsurface infrastructure, without compromising valuable public realm space.

At the lot scale, WSUD focuses on capturing, reusing, and attenuating runoff at its source, reducing pressure on downstream systems and improving overall performance. Buildings and development parcels incorporate rainwater harvesting systems to capture roof runoff for reuse, reducing demand on

Where reuse is not feasible, tanks can function as leaky ecosystems, capturing runoff and releasing it gradually



Semi-natural biodiverse communal open space as stepping stone habitat for non-human kin. Integrated with WSUD such as raingardens to capture lot-scale catchment, and potentially complemented with social spaces such as community garden, nature based playground, and interpretative ecological knowledge can strengthen positive human-nature connection in everyday life.



Multi layered Vegetation Canopy of native planting and integration with WSUD features such as vegetated swale on the secondary green link, street, communal open space to provide suitable resources and allow on-site natural processes including pollination and seed dispersal.




Ecological Block Permeability with Secondary Green Link that connects to primary cross-precinct blue-green corridor and/or directly connect to natural landscape (woodland/wetland), providing movement spaces for both human and non-human kins.



Balanced use of space for ecology, social, entertainment, commercial and other human activities, with active frontage orienting towards semi-natural social spaces to foster daily human-nature interaction.

On-site water management, such as rainwater tank, for internal water re-use



Green rooftop and permeable pavement on car parks and driveways to increase on-site



The threatened woodland is protected and celebrated by enhancing its connection to surrounding landscape.

Main blue-green corridor as habitat system and passively irrigated trees that stitch together the woodland, wetland, and precinct's block, integrating the movement of people, water and non-human kin in one spine.



Existing wetland is protected and enhanced through the constructed wetlands with water capture, storage, attenuation/detention and management while providing habitat for wildlife.



Figure 12. Blue Green Infrastructure at Block and Street Scale, integrated to precinct scale system.

4.2

CONNECTED THROUGH PUBLIC PLACES AND ACTIVE CONNECTIONS

Community and Cultural Spaces and Trails

Culturally responsive environments, where learning, healing
 and connection to Country are fostered through
 community and cultural spaces and trails.

District Play Space opportunity

District play spaces serve a large portion of the community, catering to children and families through diverse play experiences and a wide range of amenities. They typically include multiple play areas for different age groups, combining structured play equipment, nature play, open space, barbecues, picnic shelters, toilets, car parking, and landscaped areas to support longer visits and large gatherings. These are destination play spaces, facilities that families may travel to on weekends. The strategy aims to provide at least one district play space per district as populations grow, recognising that community infrastructure is delivered progressively. They are often located within district parks and co-located with features such as sporting facilities, lakes, rivers, or nature reserves.

John Knight Memorial Park is currently the nearest district-level play space to Bruce. There is an opportunity to introduce a new sporting-themed destination play space near AIS Stadium, celebrating Indigenous athletes across Australia and incorporating Indigenous themes and games. District play spaces are intended to cater to all age groups, including

and are intended to cater to all age groups, including

Public space is where public life happens, they include public open spaces like parks and playgrounds, public facilities such as libraries and museums as well as streets. Local public spaces are located close to homes and support frequent, everyday use, particularly for young families. There is an opportunity to enhance the site existing ones and introduce new through diverse, engaging, and nature-based country-led design.

Opportunities to strengthen local amenity include nature play, outdoor classrooms, community gardens. In Bruce, there is a strong desire for culturally expressive play spaces that connect to Country, supported through a network of informal healing, gathering and learning space connected via nature based active travel trails. This became spaces that celebrate the anchors and the local stories.

These uses require stricter measures due to vulnerable occupants and evacuation constraints, including larger Asset Protection Zones and emergency planning, and adequate access to the site. These uses require stricter measures due to vulnerable occupants and evacuation constraints, including larger Asset Protection Zones and emergency planning, and adequate access to the site. These uses require stricter measures due to vulnerable occupants and evacuation constraints, including larger Asset Protection Zones and emergency planning, and adequate access to the site.

forward, drawing on Indigenous knowledge systems that use “cool burning” to reduce fuel loads, maintain ecological balance, and care for Country through reciprocal practices. There is an opportunity to support initiatives, such as CIT’s cultural ranger programs to actively manage landscapes like Gossan Hill Nature Reserve, although this will require stronger policy support and investment. Moreover, land-use planning and urban development must become more adaptive and ecologically grounded, responding to changing



Figure 13. Art & interpretative design element through



Figure 14. Acknowledgement of Country and

Movement Network and Access

The Bruce Precinct Strategic Maps Report provides design recommendations. Based on this, the following design and delivery of the Bruce precinct.

Strategic Alignment

Movement and Place is universally acknowledged as a multi-disciplinary, place-based approach to integrated planning, design, delivery and operation of transport networks. It recognises the dual function of roads and streets and balances the place-making expectations related to their role in the transport network.




Figure 17. Movement and Place diagram - ACT Planning Strategy (2018)

Movement Network and Access

Road Network

ç â Ô Ö Û Ü Ø é Ø ç Û Ø ã å Ø é Û â è æ ß ì Û × Ø á ç Û Ø × ç å Ô á æ ã å å ç ã å Û á Ô Û å å å Ô × á Ø ç è å å Þ æ Û â è ß × Ô Û à ç â Ô Ø æ ç å è Ô ç è å Ø × ç â Ô Ö Ö å à à å × Ô ç Û è ç è å Ø × Ø é Ø ß å ã à Ø á ç è Û Û ß Ø æ è ã å å å ç Û á Û Ô Ø æ ç ã å Ô Ö ç Û Ö Ø ç å planning practices of mode shift and reducing reliance on private vehicles for internal and event related trips.

´ Ö ß Ø Ô å à å é Ø à Ø á ç Û Û Ø å Ô å Ö Û ì è Û ß ß Ö å á Ö Ø á ç å Ô ç Ø Û Û Û Û Ø å ç å volumes on peripheral routes and limit through movements Û á Ö å å Ø Ô å Ø Ô æ ÿ Ø á æ è å Û á Û Ø Û Ö Û Ø á ç Ö Û å Ö è ß Ô ç Û å á è Û Û ß Ø × è á á Ø Ö Ø æ æ Ô å ì Ö Ô å ç å Ô é Ø ß ; Å å Ô × æ è Û ß ß Ô Ø è Ø ß ß Û á ç Ø Û å Ô ç Ø æ è å å å è á × Û á Û è å Ô Ô á Ø á é Û å å á à Ø á ç ÿ è Û ç Û Ö ß Ø Ô å ß Ô ì å è ç æ ÿ Ô å æ å Ø Ø × Ø á é Û å å á à Ø á ç æ Ô á × å Ø × è Ö Ø × Ö å á Û Ö ç ã å Û á ç æ ç â æ è ã å all users. The network will perform effectively during peak and event conditions through managed access, clear routing, and × Û å Ø Ö ç Û á Û ç å Ô Û Ö ç â ç Û Ø ã Ø å Û å Û Ø å ì ;

ç Û Û æ Ô å å å å Ô Ö Û è Û ß ß à Ô Û á ç Ô Û á å Ø ß Û Ô Ö ß Ø ÿ æ ç å Ô ç Ø Û Û Ö Ô Ö destinations and parking facilities while reinforcing a road network that prioritises essential vehicle trips. In doing so, it è Û ß ß æ è ã å å å ç æ è æ ç Ô Û á Ô Ö Û Û ç ì å è ç Ô å à Ø æ ÿ Ø Û Ö Û Ø á ç á Ø ç è å Ô á × ã å å è Û × Ø Û å å ß å á Û ç Ø å à Û å å è ç Û Ô á × Û á ç Ø á æ Û Ö Ö ç Û å á ÿ è å Ø æ è ß ç Û á Û Û á è á á Ø Ö Ø æ æ Ô å ì Ø è ã Ô á æ Û å á å å å é Ø å ã å å è Û æ Û å å infrastructure.

Existing Road Network

The Bruce precinct is located approximately 7 kilometres northwest of Canberra's city centre and is bounded by major arterial roads, including Belconnen Way to the south, Ginninderra Drive to the north, Haydon Drive to the west and Gungahlin Drive to the east.

Battye Street and Braybrooke Street form collector roads that provide the major access into the precinct connecting to the arterial network with signalised intersections. No vehicular access to the precinct is available directly from Gungahlin Drive.

The internal road network connects the major destinations to their associated at-grade car parking and to the surrounding arterial roads at the perimeter of the precinct. Individual institutions are serviced by smaller internal access roads which primarily support movement within their own areas. The movement within the site is characterised by vehicle travel needs Û å å Ô å ç Ø å Ô Ö æ å Ø Ö Û Ø æ ç Û á Ô ç Û å å Ô × network connectivity exists between the AIS, Canberra

Stadium and CIT. The North Canberra Hospital is however isolated from the remaining precinct network not having any local road network connections between itself and the other precinct land uses. Its access is solely to and from Haydon Drive.

Generating diverse travel demands and patterns, the precinct accommodates daily commuter, student, visitor and event based demand associated with major sporting and entertainment uses. As such, the precinct requires a well-coordinated and multimodal transport æ ì æ ç Ø æ è å å å Û Ö Û å æ Ø à Ø å ÿ å å å é Ø connectivity and enable future growth opportunities.

, è Û æ ç Û á Û ç å Ô Û Ö É å ß è à Ø æ

´ á Ô æ æ Ø æ æ Û å ç Û è ß è à Ø æ å å ç Û å Ø Ô Û å ç å å å è Û × Ø æ å Ø á × Û æ ; æ ß æ ç Û å è à Ø æ æ ; ç Û Û æ Ô ß è Ø æ æ Û × Ø æ Û å å å × Ø Û ç Û Ô Û è å ß è à Ø æ ç Û Ø á è Ø å Û è Ø æ Û Ô Û ;

´ ß Û á ç Ø å æ Ø æ ç Û å ç Û è à Ø increases on game days as expected, with the most notable increases at the Haydon Drive/Battye Street and Haydon Drive/Jaeger Circuit intersections.

Movement Network and Access

Road Network

Proposed rapid transit boulevard

The transport networks presented for each scenario explore alternative alignments of the Rapid Transit framework across the precinct. While the alignments vary between scenarios, a representative cross section is proposed to illustrate the intended corridor design and functionality.

The rapid transit boulevard integrates capacity for future light rail (or dedicated bus lanes), with a single on-street parking, indented bus bays and an 8.0m wide promenade designed for community use. This indicative cross section, shown in Figure below illustrates the intent of the transit boulevard for shared transport and public realm outcomes. Priority is given to public transport, while accommodating limited vehicle

Movement and Place

The Rapid Transit Boulevard in Scenario 2 creates an opportunity for a 'Vibrant Street' function through the centre of the precinct aligning with both a high movement and a high place function under Movement

The dual function of this corridor highlights its strategic



Figure 18. Example Transit Boulevard Section

In contrast, the core of the precinct accommodates vehicles along Battye Street while prioritising pedestrian movement along north-south internal connections via Leverrier Street and an active travel link between the stadium, CIT and North Canberra »

Geometric and physical spacing constraints may affect the feasibility of an additional Gungahlin Drive interchange, particularly in respect to providing adequate ramp tapers and storage length. Weaving at the intersection would also occur if a third access point was provided between the existing two interchanges. While this additional access point could be anticipated to be predominantly used for providing additional event capacity, it is more suitable to provide a permanent new interchange. Further investigation of such an access point would need to be explored through modelling, geometric design and government engagement.

Haydon Drive Impacts

Haydon Drive Impacts

Transitway report indicates a reduction in Haydon Drive operation will require improvements, in particular, recommending corridor widening near Belconnen Way and Haydon Drive to support interim operations and the potential longer term transition to light rail. Further be required along Haydon Drive to understand its Bruce Precinct. However based on the Belconnen to City Transitway modelling it would be expected that a would need to be accepted as an inherent consequence of any upgrade to Transitway proposals.

Opportunity exists to for private vehicle movements to be combined with the Rapid Transit Boulevard providing an eastern precinct connection across (under) Gungahlin Drive through the Bruce Ridge Nature Reserve to Dryandra Street and Fairfax Street.

North-south movement within the precinct is provided via the pedestrianised Leverrier Street and the extended Masterman Street along the eastern edge, which functions as an important internal link. This corridor supports access between major destinations, including North Canberra Hospital, the CIT campus and off Gungahlin Drive. The extension of Masterman Street seeks to provide opportunity for greater access across the precinct.

Overall, under this scenario, the network emphasises internal connectivity through high quality public transport and pedestrian links, while maintaining broader accessibility via the peripheral road network.

Movement Network and Access

Parking Provisions

The desired outcome for parking provision should support

the precinct to accommodate peak demand associated with major sporting events. The precinct will adopt a parking management approach that encourages alternative travel choices.

The precinct will adopt a parking management approach that encourages alternative travel choices. The precinct will adopt a parking management approach that encourages alternative travel choices.

Existing Conditions

Parking across the precinct is predominantly provided through a combination of large at-grade car parks and select parking buildings associated with individual institutions. Provision and management vary with a mix of free and controlled parking supporting staff, students, visitors and event based demand.

While this approach accommodates existing needs, it results in a dispersed and land-intensive parking pattern, with limited coordination across the precinct. The following outlines the current parking arrangements for key institutions.

Mary Potter Circuit

The hospital campus has a free 24/hr multi-storey car park on the Mary Potter Circuit approximately 100m from the main hospital entrance. Across the campus, enforced parking conditions and time limits apply to the at grade uncovered car park opposite the main hospital entrance, and short term parking outside the Marian Building and Emergency Department.

Accessible parking is available around the campus and within the multi storey car park.

CIT Bruce Campus

A large at grade uncovered car park is available at the Bruce campus, free for all students. Accessible parking is provided outside various buildings.

Canberra Stadium

Designated car parks are available on the east and west sides of the stadium catering to visitors for \$10 per vehicle. VIP, corporate and disabled parking is also provided. Additionally, Canberra stadium directs visitors to additional parking at CIT and the University of Canberra about 10 or 20 minutes' walk respectively.

AIS

Three parking areas are provided for visitors, with two areas accommodating buses. Separate staff and athlete parking is also available. Accessible parking is available close to the main entrances.

Proposed Parking Generation

An estimate of the future parking needs of the contemplated master plan uses has been undertaken in the following.

Residential

Adopting a rate of 1 car parking space per dwelling would result in a demand in the order of 4,000 to 5,800 resident spaces.

Commercial

A range of parking generation rates are applicable for a range of commercial use types that could be expected to make up an overall commercial offering across the precinct.

In this regard car parking expectations have been referenced from the ACT Government Technical

- Retail (Shop): 5 spaces per 100 sqm
- ...

These would be expected to form the key range limits to be tested.

Rate Range (Peak Hour)	30,000	43,000
2 spaces / 100sqm (Shop)	600	860
5 spaces / 100sqm (Shop)	1500	2150
Average	1,278 spaces	

Table above (Commercial Parking Generation) indicates an average commercial parking expectation of 1,278 spaces. Combined with future resident parking a total additional parking requirement in the order of ... currently provided within the precinct.

of demand is likely to be accommodated through shared and walk-up trips between future residential development and adjacent retail/commercial uses. This internalisation of trips is expected to reduce the overall parking demand compared to a conventional, stand-alone land use approach. It is important to put in place a forward looking parking strategy at the outset which balances travel and parking needs now, however of a mixed use activity centre occurs. Parking controls and future planning provisions and ownership of ... for change.

Notwithstanding this, the provision and distribution of parking will require careful consideration in future development stages, particularly in response to the ... Parking supply should be aligned with network capacity constraints to avoid exacerbating peak period pressures on the surrounding road network.

It is important to recognise that parking provision is a key determinant of private vehicle travel behaviour. As such, parking supply may need to be deliberately moderated to discourage unnecessary car use, mitigate congestion impacts, and support a shift toward more sustainable transport modes. An oversupply of parking can induce additional vehicle trips, undermining broader transport and land use objectives.

and utilisation of parking should be actively pursued. This includes, but is not limited to, shared parking arrangements across complementary land uses with ... strategies, and potential integration with demand management measures. These approaches will help to optimise parking provision across the precinct and avoid unnecessary capital investment in underutilised parking infrastructure, while still maintaining appropriate levels of accessibility for residents, workers, and visitors.

Movement Network and Access
Parking Provisions
(continued)



Proposed Parking Generation (cont.)

SCENARIO 1

A second multi-storey parking structure is proposed adjacent to the relocated stadium and is accessed from Haydon Drive. It supports both hospital staff and stadium demand while keeping vehicles out of the precinct core and utilising existing parking land. The second parking structure is located on mixed-use development land and is proximate to the proposed access to Gungahlin Drive.

Together, these multi-storey parking structures respond to event-related congestion and reduce the need for vehicles to enter the core of the precinct. They provide the ability to supplement and provide shared parking for hospital staff and stadium demand. This peripheral parking approach reduces the need for vehicles to enter the core of the precinct, enabling the epicentre to be prioritised for active travel.

Across the wider precinct and a range of stakeholders, noting that considerations of investment, ownership and ongoing operation and maintenance of these structures have not been addressed at this stage.

SCENARIO 2

A second multi-storey parking structure is proposed upgrading existing parking land adjacent to the CIT campus to a multi-storey facility, accessed from Haydon Drive.

The second parking structure is located adjacent to the rapid transit boulevard near AIS. It is accessed from the extension of Masterman Street and the proposed connection under Gungahlin Drive. This utilises existing parking land. This peripheral parking approach reduces the need for vehicles to enter the core of the precinct, enabling the epicentre to be prioritised for active travel.

Collectively, these multi-storey parking structures support the precinct's evolving access and parking demands by accommodating the need for vehicles to enter the precinct core, enabling the epicentre to be prioritised for active travel.

Movement Network and Access

Active Travel Connections

stress environments with appropriate levels of separation, low speed conditions and safe crossings.

and intuitive choice for everyday and recreational trips. A fully prioritises active travel within the precinct core and maintains strategic access to key destinations such as the hospital, stadium, and AIS.

Existing Conditions

A series of active travel routes exist through the precinct comprising both Principal Routes and Main Routes.

The Main Route provides connection along the northern side of Battye Street from Haydon Drive to Canberra Stadium travelling onwards under Gungahlin Drive continuing through the Bruce Ridge Nature Reserve to Fairfax Street. This route facilitates a number of crossing points of local roads through the use of raised pedestrian zebra crossing treatments.

the route will experience heightened interaction management. This existing route network will become increasingly valuable, offering users an attractive alternative to private vehicle use which enables a shift toward more active travel modes while maintaining the continuous connection between Belconnen Town Centre and the Canberra CBD.

A further main route is provided from Ginninderra Drive providing connections from the north to the Canberra Stadium linking with the path network that continues south under Gungahlin Drive.

The Main Route through the site provides a connection to the Centenary Trail, a 138 km shared use trail which runs through urban and rural Canberra and passes through the Bruce precinct. This provides an important corridor for walking, running and cycling. Connection of this trail is provided under Gungahlin Drive to the Bruce Ridge Nature Reserve. To the west the path crosses Haydon Drive in an uncontrolled manner linking with the Gossan Hill Nature Reserve. Kerb ramps are provided however formal crossing control is not.

These routes are shown in Figure 19.

Several local streets support cycling in lower-speed environments such as Braybrooke Street and Leverrier Street which function as bicycle friendly streets, these include:

- signage to encourage slower vehicle speeds particularly through the AIS area
- Raised zebra crossings e.g. on Braybrooke near Battye Street intersection that further support pedestrian safety




Figure 19. Existing Active Travel Routes, Source: ACT Active Travel Planning Tool

Battye Street includes sections of shared path infrastructure known as the Belconnen Bikeway, supporting both pedestrians and cyclists and connecting to the main entrance of the Canberra stadium.

Bike and Ride

Transport Canberra provides a network of Bike and Ride facilities that support multimodal travel by enabling seamless connections between cycling and bus or light rail services. One such facility is located within the precinct at the CIT Bruce campus, with several additional sites in the surrounding area. These facilities

allow cyclists to securely park their bikes before transferring to other modes, supporting convenient access into and through the precinct.

Pedestrian Access

Around Mary Potter Circuit, footpaths and crossings are provided to support access to bus services, improving connections to public transport, however footpath provision across the precinct is inconsistent, for example Braybrooke Street has a footpath on one side only which many local roads have limited or no formal footpath provision.

Recreational Routes

The precinct does contain an extensive network of informal trails and mountain bike tracks through surrounding green open space areas, which provide strong recreational opportunities, however they are not well integrated with key destinations for everyday transport use.

À Ö Ü å ä à ã Ö Ü ß Ü ç ì

Canberra Stadium promotes an e-scooter share scheme run by Transport Canberra and ACT Government. The scheme allows visitors to the stadium to ride e-scooters directly from Belconnen to Civic and back, with drop off points provided on Leverrier Street in front of the AIS arena.




Figure 20. Transport Canberra Bike and Ride Services, Source: Transport Canberra

 Alinga Streetcar
100m ←

 Bus
100m ←

Active Travel Network and Access

Active Travel Connections

(continued)



Proposed Active Travel

SCENARIO 1

movement change by transforming Haydon Drive into an active mixed-use rapid transit corridor along the precinct. This corridor utilises the socialised space along Haydon Drive to connect major anchors, including the hospital, Fern Hill residential neighbourhoods, and Radford College. It strengthens connectivity by facilitating links to Jaeger Circuit and Purdie Street, as well as pedestrian connections into Aranda to the southwest. While access to the AIS and the precinct core would rely on the internal local movement network, the boulevard enhances broader connectivity by linking into the existing Centenary Trail, improving access to surrounding nature reserves. The scenario prioritises active movement along the precinct core, supporting a framework for a more integrated and walkable movement network across the precinct.

While links to regional and recreational routes are provided, connectivity at a local level is more limited, necessitating a more comprehensive internal movement network. Scenario 1 has a clearer separation between commuter movement along the rapid transit boulevard and connections to the broader precinct, which results in weaker direct integration, particularly in relation to the pedestrianised Leverrier Street.

Enhancements such as the development of Battye Street are required to establish continuous and legible active travel infrastructure, ensuring both effective connections between key destinations and also improving overall network permeability.

SCENARIO 2

The proposed scenario builds on the existing Centenary Trail, strengthening connections to recreation and surrounding open space. Permeability is enhanced through new, upgraded and extended connections, including Leverrier Street and additional thoroughfares—particularly in the northern section—at intervals of up to 100 metres, supporting a highly walkable urban form. A transit boulevard through activated frontages, with movement and land use focused around the precinct epicentre and integrated with key recreational connections.

transit and from the CIT parking centre, strong active travel connections—particularly between Battye Street and the CIT—are critical to ensure the hospital is closely tied to station placement, which must be optimised to maintain walkable distances. Similarly, access to other key destinations may require complementary measures such as bicycle depots or a loop bus to support last-mile connectivity.

In this scenario, the direct stadium link to the light rail station is used to manage additional active travel measures to manage game day surges.

Movement Network and Access

Public Transport

One of the key planning practices is to create a clear movement hierarchy that while accommodating vehicles at the periphery and maintaining access to strategic destinations, including the hospital, stadium and AIS.

It will effectively respond to peak and event demand through a secondary and local access network.

to destinations, manage congestion during peak and event timing and will reinforce a connected, resilient and future focused

Existing Conditions

The existing public transport network comprises a mix of regular, event and school bus services, each serving a distinct function in providing coverage, managing commuter and event related demand and supporting access to destinations across the precinct and wider network.

Bus

- Regular Services

Overall, the public transport network exhibits a strong radial structure centred on Belconnen Interchange, connections City Interchange and supporting regional travel demand. Rapid routes R2, R3, R4, R5, and R6 form the primary public transport spine, operating at a high frequency between Belconnen Interchange and City Interchange.



Figure 21. Rapid routes R2, R3, R4, R5, and R6

Route 9 supplements this network by linking Belconnen Interchange to Dickson Interchange, supporting cross-town movement and improving connectivity to the inner north.



Figure 23. Route 9

Local routes such as the 901 complement this structure by servicing key destinations within the Bruce precinct and enabling accessibility.




Figure 22. Route 901

Game day Services

Canberra Stadium provides free game day bus services for ACT Brumbies and Canberra Raiders matches. These services depart from major interchanges across Canberra and drop off and pick up passengers at the East Gate of Canberra Stadium, adjacent to the East car park.

School Services

School services further reinforce the importance of key corridors such as Haydon Drive and Belconnen Way, highlighting concentrated peak-period movements associated with education facilities.

Additional Services

Additional transport services are available to support conventional public transport. These include community bus services operating Monday to Friday, supporting passenger needs.

While the existing network provides a solid foundation of coverage and connectivity, it is primarily oriented towards connecting outer suburbs and passing through Bruce. This suggests opportunities to enhance cross-precinct and local connectivity, as well as to better integrate key institutions and activity centres within the broader transport network.

A summary of the available bus routes is in Table below along with maps showing the routes as they relate to the Bruce precinct.

Route	Route	Roads through Precinct
R2	Belconnen to Fyshwick Via City and Railway Station	Belconnen Way, Haydon Drive
R3	Belconnen to Airport Via City and Russell	Belconnen Way, Haydon Drive
R4	Tuggeranong to Belconnen Via Woden and City	Belconnen Way, Haydon Drive
R5	Belconnen to Lanyon Via ANU, City, Woden and Erindale	Belconnen Way, Haydon Drive
R6	Belconnen to Woden Via ANU, City and Kingston	Belconnen Way, Haydon Drive
R9	Belconnen to Watson Via Bruce and Dickson	Braybrooke Street, Battye Street
901	Belconnen to North Canberra Hospital Via UC Hospital and CIT Bruce	Mary Potter Circuit, Haydon Drive, Purdie Street, Vowels Crescent
1055	Aranda Primary School, Canberra High School	Braybrooke Street, Battye Street
2012	St Clare's/St Edmund's College	Belconnen Way, Haydon Drive

Figure 24. Table Bus Routes Passing through Precinct

Movement Network and Access

Public Transport

(continued)

Light Rail

The existing light rail network comprises the north-south Route R1, which connects Alinga Street in the City to Gungahlin Place. Operated by Canberra Metro Operations, the line provides a high-frequency rapid transit service, with services running approximately every 5 to 15 minutes across weekdays, weekends, and public holidays. All stops along the corridor are fully accessible.

While the current light rail alignment does not directly service Bruce, indirect access is available via connecting bus service Route 9 from Dickson Interchange.

Transport Canberra has planned network expansion which will extend light rail to additional destinations, following a hub-and-spoke model centred on the City, with new corridors radiating outward to serve surrounding areas.

A feasibility study undertaken by WSP in March 2026 investigated opportunities to enhance transit performance along Haydon Drive and eastern portion of Belconnen Way through targeted interventions that address the short to medium term needs. The existing connections of this corridor are currently constrained, and the study developed two tactical kerbside treatment options.




Figure 25. Moving Canberra 2019-2045 Integrated Transport Strategy: Current Planned Network

Proposed Public Transport

Figure 26. Scenario 1 - Public Transport Catchment 400m



SCENARIO 1

the focus is on enabling infrastructure, including the provision of new bus stops and an upgraded bus corridor integrated within the proposed rapid transit boulevard. This approach is intended to support direct and convenient public transport access to the future mixed-use development, as well as key destinations such as the stadium and hospital.

With the stadium centrally located and new mixed-use development, housing and public amenity surrounding the precinct, these key destinations will be anchored by the rapid transit corridor along Haydon Drive.

The overall strategy maintains a strong emphasis on the future delivery of high-capacity light rail as the primary mode, with bus services playing a complementary role in providing local access and network coverage.

Under Scenario 1, the rapid transit alignment is oriented to serve key civic destinations, including the hospital, northern education precincts, and the proposed stadium location (noting the relocation of the stadium is required to place it within a reasonable walking catchment of the Transit Corridor). The corridor follows Haydon Drive and Belconnen Way, providing strong regional connectivity and direct access to these high-demand uses. This aligns with the short and medium term transitway alignments contained within the recent feasibility study prepared by the ACT Government. While this alignment provides direct access to key destinations, the perimeter alignment limits coverage over the core of the precinct. In particular, it introduces a degree of separation from the AIS campus, reducing the directness of connections and potentially constraining accessibility within this area. As a result, while the alignment performs well at a strategic level, additional measures may be required to strengthen internal connectivity and ensure equitable access across the precinct.

Figure 27. Scenario 2 - Public Transport Catchment 400m



SCENARIO 2

bus routes proposed at this time, with the public light rail corridor along Battye Street, supported by active travel, to address future transport demand. In this context, bus services are not the dominant mode. The concept design only subject to patronage and demand analysis, to support the light rail corridor by providing local circulation and informing stop placement and coverage. Overall, bus services are envisaged as a secondary, adaptable layer, complementing the light rail network rather than driving network structure.

The rapid transit alignment along Battye Street, extending to Gungahlin Drive, establishes a strong public transport spine that integrates with the wider network. With the stadium retained in its existing location, the corridor is well positioned to support event-related demand, and also enhances connectivity to key destinations within the precinct, including the heart of the AIS campus, the CIT campus, and other education facilities to the north. Overall, the alignment supports both daily and peak demand, reinforcing the role of rapid transit as the primary mode while improving accessibility across major activity centres. This alignment is however at the expense of the North Canberra Hospital which would fall outside of a 400m walking catchment of the Rapid Transit route.

Movement Network and Access

Loading and Servicing

particular within high activity areas. The design and operation of these functions will also protect the visual and

The strategy should aim to respond to the anticipated Stadium, ensuring event related servicing is accommodated practice transport planning practices it will align with the operation without driving unnecessary road expansion or over delivery technologies and evolving servicing models.

Existing and planned routes

The strategy will respond to the existing and planned transport network, including key orbital links and freight

The precincts bordering arterial roads all currently allow B-Double access as part of the National Heavy Vehicle Register. The future orbital network is shown in Figure 42

Land Use

A diverse mix of residential, health, education and event uses generates varied servicing and waste management needs. Future residential growth will increase demand, requiring solutions that protect amenity, while major destinations such as the hospital, stadium and CIT campus will require tailored servicing

Vehicle types and servicing

The precinct must accommodate a range of vehicle types, including waste trucks, delivery vans, removalists, trades, emergency services and event related loading vehicles. Increasing small vehicle parcel deliveries residential areas and local centres, with servicing

Access and Circulation

Servicing access will be designed to support safe and

- Accommodating MRV and where required HRV and Semi Trailer turning paths
- Minimising reversing in public streets
- Maintaining clear sightlines and pedestrian priority
- Calming measures




Figure 28. Freight Current and Planned Network, Source: ACT Transport Strategy 2020

Movement Network and Access

Future Transport and next steps

The precinct as envisioned, will generate diverse travel demands, including commuter, student, visitor and major events. The precinct is well positioned to leverage a future rapid transit corridor as the primary spine for movement and connectivity.

Future Transport

Future transport in the precinct should integrate land use and movement to support a mixed-use environment, prioritising active and public transport. A forward looking approach will enable the adoption of emerging technologies and innovative mobility solutions, ensuring the network remains accessible, resilient, and aligned with broader ACT objectives.

The infrastructure should be designed to support long-term development timing. The precinct is well positioned to leverage a future rapid transit corridor as the primary spine for movement and connectivity.

Road Network and Operation

Supply-side measures would be required to support the precinct's growth. Master Plan Option Case results in a deterioration and breakdown of network performance compared to the Bruce Master Plan.

Increasing mode shift to public and active transport, along with stronger internal trip capture, will therefore be critical to reducing reliance on private vehicles. However, targeted upgrades to intersections, site access arrangements, and local circulation will also be required. This will place additional pressure on the road network, reinforcing the need for dedicated event management strategies.

All mitigation measures remain indicative and require further investigation. Overall, an integrated approach combining travel demand management, land use optimisation, and targeted infrastructure improvements will be required to support the precinct's growth.

Scenarios Assessment

Both Master Plan Scenario 1 and Scenario 2 align strongly with the desired transport outcomes by establishing a clear movement hierarchy and integrating land use with transport. High-capacity rapid transit forms the backbone of the public transport network, supported by active travel connections and a road network that accommodates vehicles primarily at the periphery. This approach supports mode shift, improves access to key destinations, and limits unnecessary vehicle movement within central business district environment.

Next Planning and Design Stages

Further work is required to resolve gaps in connectivity and strengthen integration between rapid transit and local roads. Ensuring equitable access to key destinations including AIS and the North Canberra Hospital, and developing effective event management strategies will be critical. This approach should also support emerging technologies, integrated multimodal networks and staged delivery to ensure adaptability as the precinct grows.

Loading, servicing and future transport strategies should be further developed through the next stages of planning. This approach should also support emerging technologies, integrated multimodal networks and staged delivery to ensure adaptability as the precinct grows.

Overall, the master plan provides a strong foundation for a coordinated, multimodal transport system that supports growth, enhances accessibility, and promotes sustainable travel, positioning Bruce as a high value and integrated mixed-use precinct.



EMERGING TECHNOLOGIES AND MULTIMODAL INTEGRATION

Future transport in the precinct will integrate land use and movement to support a mixed-use environment, prioritising active and public transport. A forward looking approach will enable the adoption of emerging technologies and innovative mobility solutions, ensuring the network remains accessible, resilient, and aligned with broader ACT objectives.

The infrastructure will be designed to support long-term delivery aligned to development timing. The approach will allow for adaptation to evolving technologies and travel behaviours while maintaining a focus on sustainable travel patterns.

MONITORING AND ADAPTABILITY

The infrastructure will be designed to be responsive to changing conditions. This will include ongoing monitoring of travel patterns and mode share and periodic review of infrastructure performance and capacity. The approach will allow for adaptation to evolving technologies, user behaviours, and policy settings, including the use of pilot programs and temporary interventions.

SUSTAINABILITY AND BEHAVIOUR CHANGE

Encouraging sustainable travel behaviour will be central to the precinct vision, particularly given its role as a major destination for events, education, and health services. Travel demand management will be critical to reducing reliance on private vehicles, with measures tailored to these uses, such as event travel planning, and incentives for staff, students, patients and visitors to choose active and public transport.

Flexible working and study arrangements, personalised travel planning, and targeted initiatives during major events will further support mode shift. Community engagement and education can further reinforce sustainable travel choices and support a transition to less car dependent travel patterns.

4.3

FOSTERING INNOVATION AND ANCHOR SYNERGY

Economic Development

Benchmarking Success in Innovation Precincts

Comparable innovation precincts demonstrate consistent performance benchmarks. These precincts have achieved critical mass, density and ecosystem integration. Bruce must target a minimum threshold of 25,000+ jobs to operate as a credible innovation precinct. The presence and integration of health, education and sport anchors is essential, alongside a deliberate focus on building a translational research ecosystem that drives clinical trials, innovation and economic uplift. Equally important is governance and coordination, with successful precincts supported by strong partnership models and long-term investment to grow from emerging clusters into mature innovation ecosystems. Without this level of scale and integration, precincts risk underperforming and functioning as conventional centres rather than globally competitive innovation hubs.

Comparable innovation precincts demonstrate consistent performance benchmarks. These precincts have achieved critical mass, density and ecosystem integration. Bruce must target a minimum threshold of 25,000+ jobs to operate as a credible innovation precinct. The presence and integration of health, education and sport anchors is essential, alongside a deliberate focus on building a translational research ecosystem that drives clinical trials, innovation and economic uplift. Equally important is governance and coordination, with successful precincts supported by strong partnership models and long-term investment to grow from emerging clusters into mature innovation ecosystems. Without this level of scale and integration, precincts risk underperforming and functioning as conventional centres rather than globally competitive innovation hubs.

The benchmarking highlights that success is not just about development, but achieving critical mass, density and ecosystem integration. Bruce must target a minimum threshold of 25,000+ jobs to operate as a credible innovation precinct. The presence and integration of health, education and sport anchors is essential, alongside a deliberate focus on building a translational research ecosystem that drives clinical trials, innovation and economic uplift. Equally important is governance and coordination, with successful precincts supported by strong partnership models and long-term investment to grow from emerging clusters into mature innovation ecosystems. Without this level of scale and integration, precincts risk underperforming and functioning as conventional centres rather than globally competitive innovation hubs.




Figure 29. Maturity pathway for health and knowledge precincts - "Agglomeration" on a Continuum- increase productivity or output that is achieved through improvements in processes, technology or skills.

KEY TAKEAWAYS

STRUCTURED PARTNERSHIPS AT IPS UNLOCK ~30%+ PRODUCTIVITY GAINS

*FASTER COMMERCIALISATION AND TALENT ATTRACTION

PARTNERSHIPS, NOT JUST CO-LOCATION, DRIVE OUTCOMES

Successful precincts typically have strong and integrated institutional relationships are the primary driver of productivity gains. The integration of two universities, and Parkville's integration of a university and a research centre showcase this.

CROSS-SECTOR IPS GROW 2-3× FASTER* THAN TYPICAL METRO EMPLOYMENT GROWTH

*~150-180% TOTAL GROWTH OVER ~20 YEAR PERIOD

PRECINCTS EVOLVE FROM SINGLE-SECTOR CLUSTERS TO DIVERSE ECOSYSTEMS

Successful precincts typically evolve from single-sector clusters to diverse ecosystems. The Coast precinct is exemplary of how a cross-sector nexus is often the logical point of growth.

300-800+ PEOPLE & 25,000-80,000 JOBS /HA REQUIRED FOR CRITICAL MASS

SUSTAIN TALENT, SERVICES, AND DAILY INTERACTION

DENSITY, CRITICAL MASS AND OPPORTUNITY FOR INTERACTION UNDERPIN AGGLOMERATION BENEFITS

High density and concentration of activity is essential to unlock agglomeration benefits. Westmead is an example of how enhanced attractiveness for further capital investment. Westmead is an example of how a precinct can become a hub for the precinct.

BALANCED MIXED-USE* DRIVES PEAK INNOVATION PERFORMANCE

*35% EMPLOYMENT, 25% KNOWLEDGE, 25% RESIDENTIAL AND 15% AMENITY

TRANSITION FROM INSTITUTIONAL CORE TO MIXED-USE INNOVATION DISTRICT MUST BE PLANNED

The coming transition of Sydney Olympic Precinct will see a mix of uses translates into density of economic opportunity. The coming transition of Sydney Olympic Precinct will see a mix of uses translates into density of economic opportunity.

\$1 - 5B AVERAGE AUSTRALIAN GOVERNMENT INVESTMENT IN IPS

UP TO \$10B LONG-TERM

PUBLIC INVESTMENT ENABLES AND ACCELERATES, BUT DOES NOT ALWAYS LEAD

Funding models are not always the primary catalyst. Parkville developed organically from one of Australia's oldest universities, with government infrastructure and support recognizing this and facilitating further growth, rather than initiating the precinct.

AUSTRALIAN SPORTS-TECH CONVERGENCE SECTOR GENERATED \$5.65B*

*ANNUAL REVENUE IN 2025

CONNECTION TO SPORTS SECTOR IS A NEW FRONTIER FOR INNOVATION IN PRECINCTS, BEYOND PLACE ACTIVATION

Sport is increasingly relevant to innovation precincts through its role in the emerging wellness economy, where it intersects with health, human performance, and technology. Beyond its traditional role, sport can act as an additional driver of innovation in preventative health, commercialisation. In the context of Bruce, sport can act as an additional driver of innovation in preventative health, research and consumer markets.

Economic Development (continued)

Westmead Innovation Precinct



Figure 30. Westmead Innovation Precinct services health needs, and includes multiple ancillary health developments and is surrounded by dense housing, universities, schools and green space

SERVES WESTERN SYDNEY, 10% OF AUSTRALIA’S POPULATION

- Strong institutional anchors with complementary roles
- Attracts one in every four dollars of biomedical research and education
- Co-locates Western Sydney University and Epping Hospital and Health Centre and within major facilities
- Precinct models how multiple education tiers complement each other and coexist with health assets
- Achieved scale and critical mass (density), one of the largest clusters of its kind
- Formalised partnerships across institutions, collaboration supports strongly connected system
- Located within a high-growth population catchment with demand for services
- Sustained and coordinated government investment
- Attracting substantial private capital investment to strengthen the precinct and diversify employment
- Transitioning to mixed-use innovation district

Parkville Medical Precinct



Figure 31. Parkville Medical Precinct - government investment reinforces an already successful ecosystem, image of partnership with Transport to ensure patients have a safe arrival experience

- Clustered around historic institutions (eg Melbourne University), now includes over 40 education, research and medical institutions
- Early establishment and co-location of major anchor institutions
- Exceptional density of complementary research, clinical and education institutions
- Attracts one in every four dollars of biomedical research funding in the nation
- Long-term accumulation and compounding of institutional relationships and collaboration
- Sustained government investment reinforcing and scaling an already successful ecosystem
- Mature, self-reinforcing cluster dynamics driven by global reputation, talent attraction and research funding
- Sub-precincts within Parkville provide opportunities for specialised focus within a dynamic mixed-use environment
- Precinct can bid for Commonwealth grants, coordinate place delivery and ensure awareness across institutions and activities

EVERY DOLLAR INVESTED BY GOV GENERATES \$3.66 IN GROSS STATE PRODUCT



Figure 32. Gold Coast Health and Knowledge Precinct - research hubs around hospitals delivered approx. 3.4B to QLD economy

SURPLUS LAND INTO KEY WORKER HOUSING DELIVERS MIXED-USE VITALITY

- Anchor-led development enabled through proactive government planning
- Institution-led governance with formal partnerships driving outcomes
- Research focus on sports technology, biotechnology and assistive technologies, the latter relating to the more mature population in the Gold Coast region but not wholly serving a local population catchment
- Public investment catalysing private sector integration
- Planned private sector entry through land release and enabling infrastructure
- Sequenced development from anchors to commercial growth Emerging sports innovation focus (human performance, health, technology)
- Converted surplus land into key worker housing to minimise commute, and appeal through mixed-use vitality
- Leveraged major event infrastructure for the




Figure 33. Sydney Olympic Park - green corridor delivering a diversity of public open spaces that support both community as well as sporting infrastructure

- 10M+ visitors per year to between 5,500 to 6,000 events per year
- Unique catalytic investment delivering world-class infrastructure and site transformation
- Required “top down” planning to ensure
- Staged private sector activation following upfront public investment
- Creation of a strong destination identity anchored in events, sport and entertainment
- Economic activity dominated by events, sport, entertainment and government, rather than knowledge-based industries
- Ongoing transition from event-based precinct to mixed-use urban district requires active planning and long-term coordination (2050 Master Plan)
- Existing precinct structure supports active
- Transition will overcome the “monoculture” of an event-only precinct, structurally isolated and not truly “owned” by a local community by providing consistent daily working and residential population.

\$16.3M IN REVENUE FROM LEASES AND LICENSES ACROSS 190 PROPERTIES

Health, Education and Sports Integration

Potential Precinct Governance Models



This page outlines four typical innovation precinct governance models, distinguished by how structure, governance and funding responsibilities are distributed across government, anchor institutions and the private sector.

ANCHOR: institution-led governance & precinct identity  GOVERNMENT: funds health & education via bilateral agreements PRIVATE: commercial relationships for precinct development	Anchor-Led Distributed Model AKA campus Structure - Precinct grows around one or two dominant anchors - Governance is institution-led, not place-led Governance - Bilateral or multilateral agreements » funding and operations Funding - health capital programs - Research grants + education / university investment - Surrounding development funded privately
ANCHOR: Statutory entity GOVERNMENT: policy and funding PRIVATE: delivery capital	Development Corporation Model A stadium led/event catalyst urban renewal Structure - Statutory or quasi - government entity with: - planning powers - land assembly - delivery oversight Governance - Board appointed by government - Multi-agency coordination mandate - Ability to override fragmented planning controls Funding - Commercial event revenue and Development partnerships - Government capital (seed infrastructure) - Land value uplift capture and Long-term leasing

Health, Education and Sports Integration (continued)

a formal MoU or partnership agreement to align vision and
 formalise funding, infrastructure and programming protocols.

Recommendation approach for Bruce

Drawing on economic development insights from comparable innovation precincts, and informed by the four typical governance models reviewed, a model that changes over time is recommended for the Bruce Precinct. The governance structures will evolve over time in response to market conditions and institutional maturity. Establishing a clear and enduring precinct identity is critical to aligning stakeholders, attracting investment and guiding long-term decision-making.

° â é ø å á Ô á Ö ø

A Urban Renewal / Development Corporation model, led by the ACT Government, is recommended to provide the leadership, statutory authority and delivery capability required to overcome fragmentation and coordinate precinct-wide outcomes. This entity would be supported by a formalised partnership framework with key anchor institutions, including the Commonwealth (through the Australian Institute of Sport), and ACT including the University of Canberra, CIT and the North Canberra Hospital.

Delivery

A staged delivery approach is critical to sequencing investment, managing risk and building momentum:

- Stage 1: Establish governance structure, secure funding agreements, and deliver enabling infrastructure (transport, utilities, public domain) to unlock development capacity.
- Stage 2: Anchor Projects
Deliver catalytic anchor investments, including the stadium, hospital and education expansions, to establish critical mass, attract talent and signal long-term commitment.
- Stage 3: Mixed-Use + Innovation Ecosystem
that facilitates broader mixed-use development (residential, commercial, retail) alongside the growth of innovation clusters, partnerships and supporting ecosystem programs.

public and institutional investment de-risks the precinct and creates the conditions for sustained private sector participation.

Funding

A blended funding model is required to support both infrastructure delivery and long-term ecosystem development:

- Public investment from the ACT Government and Commonwealth should be considered, to facilitate major infrastructure and anchor projects including the stadium and hospital.
- Institutional capital from the University of Canberra and CIT will support campus expansion, research facilities and education infrastructure.
- Private sector investment will drive residential and commercial development, enabled by improved infrastructure and place value uplift.
- Targeted innovation funding streams, particularly in sports technology will be critical to supporting research, commercialisation and industry growth

precinct priorities.

Precinct Positioning

The Bruce Precinct has the potential to establish a globally unique positioning as a “SPORTS, HEALTH AND EDUCATION INNOVATION DISTRICT.” This integrated identity builds on existing strengths and differentiates the precinct in a competitive global market. The positioning aligns with the ACT Government’s BSHEP planning work on the wider integration of the area’s diverse anchors, with the Bruce Precinct differentiating itself as a distinct and integrated precinct. By co-locating elite sports infrastructure, health services and education/research institutions, the precinct can foster cross-sector collaboration, support applied research and create new pathways for innovation, talent development and industry engagement. A clear and consistent positioning will be essential to attract investment, partnerships and global recognition.

Governance model principles for IPs

PURPOSE

empowered and
coordinated
governance
entity

PEOPLE

actively curate
collaboration
and innovation

PLACE

shared
infrastructure,
funding and data



4.4

CREATING A NEW ENTERTAINMENT AND STADIUM-LED COMMUNITY

Land Use, Built Form and Density

A Vision for Innovative Urban Development

The precinct's anchors.

Bruce is located between the strategic centers of Canberra City and Belconnen, and along the innovation corridor. The ACT Government has committed to 30,000 dwellings by 2030 and Bruce is well positioned to contribute.

This precinct will deliver Urbanity (rather than only housing density) in the form of a neighbourhood structure centred around a vibrant green public heart and dominated by mixed-use development that integrates residential, commercial and community uses with the existing and planned anchors, and rapid transit corridor.

Leveraged off planned public transit and green amenity, the development should be moderately dense, with typical 4-6 storey blocks topped with appropriately located towers that minimise visual impacts. Built form should be integrated with the precinct's anchors.

This integration with anchors should drive the typologies and character areas. Dense development should be focused around the revitalised stadium, driving a complementary mixed-use precinct boosting retail and urban activity both on and outside game days. Proximity to several universities and education campuses supports well located student housing that in turn generates activity and innovation. Adjacent the redeveloped North Canberra Hospital, diverse retirement and aging in place typologies, as well as key worker housing, would be attractive offerings.

Delivering successful innovation precincts relies on the attraction of people, not just as an ideal place to work, but a place to stay, live, and invest into a shared identity. People are the difference between bustling places and all-too-common, sparse, 'ghost-town' campus environments, and this activity is what provides the friction for innovation and the energy that attracts businesses and institutions. The Bruce Precinct should meet this need through mixed-use development that integrates the density and walkability to stimulate attractive, populated public realm.

The Bruce Precinct will exist within its regional context and the traditional town center hierarchy of surrounding areas. While it is a district center, however its commercial space will be more focused on district and city-scale employment and attraction as opposed to a center delivering at a suburban scale.



Figure 34. University Canberra 'UCLodge' Student Accommodation houses over 350 units on an medium-density 8 storey, half-hectare site.



Figure 42. A mixture of apartments and student accommodation along Scholars Greenway offers attractive living on the edge of Vancouver's UBC campus.



Figure 35. Woollooware Shores - an attractive medium-density retirement campus including standalone units and RACF in Taren Point, Sydney, designed by Jackson Teece Architects



Figure 36. Westmead Innovation Precinct Master Plan, incorporates a new stadium, city center, and regional health district, and mixed-use development along a green corridor.



Figure 37. Billion dollar mixed-use development under construction adjacent to CPKC, the largest rail yard in North America, offering a mix of affordable housing and integrates with a streetcar extension.



Figure 38. Sydney Olympic Park Master Plan - Mixed-use, activated housing blocks leveraged off a successful sports and commercial precinct.



Figure 41. Macquarie Park Innovation District with public transit and dense housing



Figure 40. Scape Sydney - modern, compact student housing within the city fabric



Figure 39. Industry Lanes, Richmond VIC - mixed-use, campus style precinct combining retail, community amenity and modern, creative commercial uses.

Land Use, Built Form and Density

Achieving Urbanity: Character Area Based Densities

The ambition of these areas is to realise a form and feel to new development in the Bruce Master Plan, and allocate densities that aligned with expected yield outcomes from previous investigations. The two areas differentiate between and acknowledge the unique characteristics of the future stadium-associated development versus the traditional urban precincts.

The ambition of these areas is to realise a form and feel to new development in the Bruce Master Plan, and allocate densities that aligned with expected yield outcomes from previous investigations. The two areas differentiate between and acknowledge the unique characteristics of the future stadium-associated development versus the traditional urban precincts.

In then next stage of the master planning process, a further detailed character area breakdown will be required to go beyond density and capacity and include identity, land use and anchoring features.

Stadium Precinct

of mixed-use entertainment precincts for civic outcomes, the precinct's densest development is allocated in proximity to the renewed stadium.

This density can accommodate medium-high-density development including increased

Bruce Village

More traditional urban precincts away from the stadium will be suited to medium-density typologies, providing a density capable of active, walkable, amenable neighbourhoods while maintaining an urban village feel.

These areas will interface with existing campuses, including the AIS and CIT, and this density allows for a considered transition including the opportunity for development by these anchor institutions.



Figure 43. Scenario 1



Figure 44. Scenario 2

Determining an Indicative Yield Baseline

Ç Ü Ö å Ø Õ æ Ø á ç ù ù ç Ü Ü å Æ Ö ã æ æ 'urban development' have guided our spatial understanding of the potential development capacity of the site in terms of a reasonable lower and upper limit.

Based on preliminary development capacity investigations, using the assumptions opposite, a viable yield range applicable to both scenarios is established as 4,000-5,800.

For the purposes of establishing a yield range as the Ö Ö æ Ü å á Ü Ü á Ø Æ Ü å Ö å á á à Ü æ Ø æ ç Ü Ü Ö ç Ü å á æ ® the yield has been developable as all residential and mixed-use medium to high-density. The yield range does not include any of the other accommodation typologies at this stage.

However, the table opposite provides the inputs necessary to reevaluate the yields/ beds to generate a more tailored yield, development and accommodation typology mix once market demand is further understood.


Pro Rata Yield for a 1Ha plot

Public	40%	0.4Ha
Open Space & Non-developed Land	50%	0.2Ha
Roads	50%	0.2Ha
Private	60%	0.6Ha
Commercial/Institution	10%	0.06Ha
Residential	90%	0.54Ha

Typical Residential	dw/ha	yield
¥ © Æ ç â å Ø ì æ	150	81
§ ¢ £ Æ ç â å Ø ì æ	250	135
§ ¢ ¨ Æ ç â å Ø ì æ	350	189
Student Housing		
§ « Æ ç â å Ø ì æ	1 £ £ © £ £ ¢ 1 ¨ ¥ ¢ £	
Aged Living		
Æ ç Ö á × Ö ß â á Ø Å ´ ¶ 1 ¨ ¨ \$ © ¨ £ © ¢ ¢ ¢ ¥ Storey		
Å Ø ç Ü å Ø à Ø á ç É Ü ß ß Ö £ Ø ¥ £ § © § ¨ ¨ £ Storey		
É Ø å ç Ü Ö Ö ß Å é Ø å ¨ ¢ £ £ 1 £ £ ¨ £ ¢ 1 ¨ ¨ ¨ å à à è á Ü ç ì Ý § « Æ ç â å Ø ì æ		
Specialty Accom.		
Athlete ´ Ö Ö å à à â × Ö ç Ü å á Ý Storey	¥ £ £ § £ £ ¨ £ ¢ «	¨ £ ¢ « £
BTR Key Worker » â è æ Ü á Ü Ý § « Æ ç â å Ø ì æ	¥ ¨ £ 1 ¨ £ ¢ ¢ ¥ ¢ ¨ ¢	
´ Ü Ü å á × Ö Ö ß Ø » â è æ Ü á Ü Ý £ \$ « ¢ ¥ ¢ ¨ ¢ Storey	¥ ¨ £ 1 ¨ £ ¢ ¢ ¥ ¢ ¨ ¢	

Land Use, Built Form and Density

Character Area Exemplars



Stadium Precinct:

¼ á Ö å Ø Õ æ × Ö å à à Ø å Ö Ü Ö å å å æ å Ö Ö
 compared to village character area,
 Ü á Ö Ö è × Ü á Ü à å æ ç Ü á å è á × å å å æ Ö á ×
 podium levels

Larger podiums with increased levels dedicated to green-walled parking, adaptable in future to alternative uses

Podium parking to be located on upper
commercial frontage along outer edges of
parking where possible

Podiums between 4-6 Storeys, and towers up to 20 storeys, with greater variation between typical buildings and standalone anchor tower developments

Ambition of >25% of communal open space including >7% of deep soil

Through block links integrated with green-blue network ambitions



Figure 45. Perkins and King, Newcastle East End, NSW - SJB



Figure 46. Nishi, Canberra, ACT - Fender Katsalidis




Figure 47. Kent Road, Mascot, NSW - SJB

The Character Area Exemplars seek to provide an **indicative application of the densities planned for the Bruce Precinct on a generic 1ha block**. These blocks are not drawn from any spatial location on the site and should serve only as a guide for potential height, form and typology that will be determined at the detailed master planning stage.

-  Mixed-use - Residential
-  Mixed-use - Commercial
-  Parking
-  Open Space
-  Civic Promenade

Bruce Village:



Towers up to 10 storeys, offering a range of medium-density typologies

Integrated medium-density housing typologies with internalised parking and maximised frontages

Ambition of >25% of communal open space including >7% of deep soil

Consistent perimeter block frontage still includes through-block connectivity at both green corridor through to arcade scale

Introduction of typologies with less or no integrated parking to support modal shift ambitions

Consistent active commercial edges with zero setback to pedestrian active streets

Standalone towers with adaptable ground
green walls



Figure 48. Nightingale 1, Melbourne, VIC
- Breathe Architecture



Figure 49. Parklife, Melbourne, VIC - Austin Maynard Architects



Figure 50. Yukeembruk - ANU, Canberra, ACT - Bates Smart

Land Use, Built Form and Density

Evolution & Delivery


of density, activity, movement trends and commercial needs over time.

The subject area, in it's current form, is largely a low density, campus-style special purpose precinct, well aligned with Canberra's prevalent car dependence and sprawling low density urban development typologies. Transition towards positive urban design outcomes, including transit mode shift, a high intensity of mixed-uses and a pedestrianized ground plane will require a stepped approach that stretches beyond, yet relies on, the initial outcome of this master plan.

The precinct's initial outcome based on current best practice delivers full sized vehicular roads and increased parking amenity that focuses on meeting current needs while delivering a moderate push and prepare for such catalysts as new rapid transit networks, roads should be designed to facilitate future


dieting, including lane reductions, verge increase and buildings should be designed with appropriate heights and servicing for future conversion to retail, residential, community or commercial use. These changes may be unlocked through the needs of population density in the project's later stages, increased pedestrian activity, and the delivery of rapid transit.

Podium parking is a desirable outcome not just for its adaptive reuse capability, but also for environmental sustainability (reduced excavation) and residential may be delivered sustainably through planned adaptive re-use and tactical landbanking.



An expectation for the uplift of campuses in the subject area, such as CIT (pending relocation) or AIS, creates a collaborative governance models. This may include charters or formal partnerships, or statutory recognition as a special precinct with it's own distinct controls, or taller and more open internal spaces to facilitate such changes as converting residential to commercial space, or larger apartments to student accommodation.

Delivering on some of these long-term ambitions for collaborative governance models. This may include charters or formal partnerships, or statutory recognition as a special precinct with it's own distinct controls, or taller and more open internal spaces to facilitate such changes as converting residential to commercial space, or larger apartments to student accommodation.



Land Use, Built Form and Density

Land Use Zoning Map

Land use zone changes within the Territory land can be facilitated through amendments to the District Strategy and Major Territory Plan Amendment process. This would consider and identify the proposed land use zones and planning controls to facilitate the redevelopment of the precinct.

Through this process more detailed consideration would be given to the most appropriate zones and controls to achieve the intended outcome. Potential consideration could also be made to using a Future Urban Area (FUA) overlay.

This process could also consider the introduction of an **Entertainment precinct** to support a lively mixed-use precinct associated with the stadium.

entertainment precincts within the District Policies. These are areas where the focus is on existing and future nightlife activities.

1. The City Centre Entertainment Precinct (CCEP) is located in the City Centre. It comprises a Core and a Frame area. The CCEP supports the strategic planning direction of the Inner North and City District Strategy and the City Plan.
2. The Gungahlin Town Centre is located in the Gungahlin Town Centre. This supports the direction provided in Gungahlin District Strategy.

Both District Policies identify mandatory assessment requirements for development in entertainment precincts, which include:

- Developments should help make the area more vibrant, including supporting entertainment and
- Entertainment venues must consider how they manage loud music, especially bass sounds,
- and
- reduce incoming noise, including bass sounds.

The following table includes the following permissible uses that are intended for the precinct including:

- Indoor Recreation facility or outdoor recreation facility (e.g. stadium)
- Educational Establishment (CIT)
- Multi-unit housing
- Commercial accommodation use
- Cafe
- Restaurant
- Supermarket
- Light rail

Some of the uses within the precinct can be facilitated within the current land uses zones. For example, the existing CIT site is zoned Community Facility and permissible uses include Indoor Recreation facility and outdoor recreation facility (stadium).

While mixed-use commercial and residential development can't currently be proposed in the community facility zone, a new stadium could be.

Within the Bruce - Commercial Mixed Area to the west, there are currently a number of assessment controls that apply to development, for land uses, GFA for shop, building heights and setbacks within that mixed-use area. Interface with this area would need to be considered as part of the planning amendments.




Figure 51. Scenario 1 Proposed Land Use





Figure 52. Scenario 2 Proposed Land Use



LEGEND

- | | |
|---------------------------|---------------------------------------|
| Bruce Precinct Boundary | NUZ3 - Hills, Ridges and Buffer Areas |
| CF - Community Facilities | PR21 - Urban Open Space |
| G25 - Mixed Use | TSZ1 - Transport |
| DES - Designated | TSZ2 - Services |

Strategic and Statutory Planning Overview

The current District Strategy sets the scene for a future innovation precinct with ambitions for a scale innovation precinct at Bruce integrating strong stakeholder leadership, alignment across dual planning jurisdictions, land divestment, and a series of Commonwealth and Territory planning and land transfer processes between the ASC and ACT Government.

The current District Strategy sets the scene for a future innovation precinct with ambitions for a scale innovation precinct at Bruce integrating strong stakeholder leadership, alignment across dual planning jurisdictions, land divestment, and a series of Commonwealth and Territory planning and land transfer processes between the ASC and ACT Government.

- support a knowledge-based, innovation-driven economy.

To realise either of the strategic scenarios there are several processes and changes that would be required. In addition, there would need to be demonstrated leadership from key stakeholders to implement the changes and work together to support the vision for an integrated precinct.

The Bruce precinct will continue to be subject to two planning jurisdictions (the boundaries of which may be changed if desired).

1. The AIS/ASC land which is subject to the National Capital Plan (NCP).
2. Territory land which is subject to the Territory Plan.

Co-ordination would need to come through alignment of the AIS Master Plan with the Bruce Precinct Master Plan, so that the planning and vision for both the AIS and the broader precinct is co-ordinated.

The National Capital Authority (NCA) has advised that the precinct is not considered to be nationally significant (the key responsibility for the planning and implementation of the precinct outside the nationally significant area is the responsibility of the ACT Government or through a co-ordinated governance structure as described in Section 4.4 Health, Education and Sports Integration below.

The process to implement the chosen scenario for the Bruce Precinct Master Plan would commence with land transfer processes between the ASC and ACT Government.

There are various processes that could then follow to support delivery of the scenarios, these include:

Commonwealth processes:

- Declaration of National land.
- Amendments to NCP.

Environmental Assessment processes:

- EPBC Act (Cth).
- Planning Act (Territory).

Territory Processes:

- Amendments to the Belconnen District Strategy.
- Major Territory Plan Amendments.
- Subdivision Design Proposal.
- Development Applications.

These are described in further detail below.



Strategic and Statutory Planning

Land Transfer Paths

ÇÛØ åæç æçøã Üá ÙÔÖÛßÜçÔçÜáÚ çÛØ àÔæçøå ãßÔá êâèß× Õ
ãâææÛÕßø ßÔá× æÕßø âå ×Ûéøæçàøáçæ Õøçèøøá çÛØ ´Æ¶ Õ
çÛØ ´¶Ç °âéøåáàøáç; ÇÛØåø Ôåø çêâ ãÔçÛêÔìæ àÔããø×
Üá Üèåø Õøßâê; ÇÛØåø àÔì Õø âçÛøå êÔìæ çâ ÙÔÖÛßÜçÔçø
çÛÛæ ååâÕøææÝ Õèç çÛøæø Û×øáçÛÙì Ô åâçøáçÛÕß åâçÛâá;

TRANSFER MECHANISM 1

Transfer to ACT Government

market value Territory Crown Leases which comprise the ASC site. Block 26 Section 8 Bruce includes most of the AIS including the stadium and athletics track in the south. This process describes the divestment to the ACT Government. The typical steps outlined in the diagram are as follows:

1. Initial discussions and Due Diligence

ACT Government to undertake due diligence work on the land to understand constraints. This would include more detailed investigations such as hazardous materials, servicing, contamination, ecology, trees, heritage etc.

2. Æ è å é Ø ì ç Û Ø ã å â ã â æ Ø × ã Ô å ç Õ ß â Ö

Agreement on the appropriate boundary for subdivision and valuation purposes.

3. Á Ø Ú â ç Ü Ô ç Ø ç Ø å à æ ¢ ã å Ø ã Ô å Ø Ô à Ø à å å Ô å × è à å Ù
understanding (MOU) Through either subdivisi


Based on the due diligence and land area, a general agreement could be reached to set out the terms and process going forward.

4. $\mathbb{A}^1 \times \mathbb{A}^1 \cong \mathbb{A}^2$ $\mathbb{A}^1 \times \mathbb{A}^1 \cong \mathbb{A}^2$ $\mathbb{A}^1 \times \mathbb{A}^1 \cong \mathbb{A}^2$

The ASC could surrender part of their block to the ACT (without compensation) subject to any condition. This would then become unleased Territory land and the ASC block boundary could be redrawn. Part of this step would be to undertake a valuation of the land to inform negotiations.

Alternatively, the part block would be valued to inform a subdivision and lease variation so that the new block could be sold to the ACT Government. (Note that the Crown Lease and land subdivision may require both a development application under the Planning Act (for the Crown Lease variation) and a works approval under the NCP if physical works are required).

Through either sublease or surrender, the outcome would be a new separate lease to the Australian Capital Territory for part of the block. A lease would be required so that subleases can be registered for operations and activities at the Stadium.



TRANSFER MECHANISM 2

Transfer of Contiguous Land / blocks to ASC

The Territory can only grant a lease by auction, tender, ballot or direct sale. The typical Steps for a Direct Sale Application are as follows:

1. Initial Discussions

This is a relatively informal process that typically involves meetings or writing to the Direct Sales Team within the ACT Government to identify the block(s) and proposal, and they will undertake initial enquiries within the Territory to identify any barriers to a Direct Sale of the land. Typically parcels subject to direct sale cannot be separately saleable and so this would need to be tested with Direct Sales and the Territory more broadly.

2. Concept Planning

A Direct Sale application needs to be supported by a concept to justify the need for the sale. This would include the overall AIS master plan and the Bruce Precinct Master Plan to demonstrate how the land would be used by the AIS and to help facilitate development across the precinct.

3. Formal Application

A formal application for the parcel(s) needs to be submitted which includes

- Site details (block/section) and applicant details
- Proposal description (suitability and consistency with operations) inc. development concept/sketch plans in this case it might be supported by the AIS master plan and the Bruce Precinct Master Plan
- Financial Capacity to develop the land (Indicative project costs (construction, design, site grants), land cost assumptions etc.

4. Assessment

The proposal will be assessed by relevant ACT Government entities and agencies against the criteria. Direct sales of contiguous land must:


- facilitate the achievement of a good planning outcome
- be compatible with Territory or Commonwealth government policies applicable to the proposed lease
- the lease is not viable to grant as a separate parcel
- the proposed lease will a) not detract from the AIS master plan and b) not restrict public access to other land.

5. Executive Decision

Direct sales to Commonwealth or Territory Entities require Executive approval. If supported, the government may agree to negotiate the sale.

The ACT Government then grants the Crown lease to the applicant based on the agreed value and upon any relevant conditions of sale or development.

Note: This process could potentially be bypassed by a direct transition from Territory land to declaration of National land subject to negotiations with the Territory. This is provided that the ASC could demonstrate the need for the declaration in the context of their overall site master plan and how the parcels would be developed.



Strategic and Statutory Planning

Land Ç å Ô á æ Ù Ø å ã Ô ç Û æ
(continued)






Strategic and Statutory Planning

Planning approaches

Following divestment decisions and actions, the implementation of precinct development could commence. There are many potential approaches and ways this could be achieved. This document outlines the following approaches:



Planning changes process

Territory Planning Changes

In parallel more detailed precinct planning on Territory land could be developed to support either scenario as follows.

Amend District Strategy

There is an opportunity to develop the Bruce Precinct Master Plan, as a 'planning and response report' that supports an amendment to the Belconnen District Strategy.

This process is set out in Part 2 of the Planning (General) Regulation 2023. A planning and response report can be prepared at a precinct scale and must include a concept planning document. Examples include a place and character plan, master planning and design framework, environmental and site study, staging and feasibility plan.

A planning and response report can either be prepared by the Territory Planning Authority (TPA) or if it is at a precinct scale it can be prepared by a prescribed entity such as the Suburban Land Agency (SLA).

Following the preparation of a planning and response report, the Minister may amend the district strategy and it is consistent with the Planning Strategy.

In accordance with the Planning Act, 2023 (s41) the Executive at least once every 5 years after making the planning strategy or a district strategy, consider whether the strategy should be reviewed. The District Strategies will also potentially be up for review in September 2028, and this could also be an opportunity to review the Bruce Precinct Master Plan.

Strategic and Statutory Planning

Process per scenario

(continued)

Territory Plan Amendments

There are two types of amendments that can be made to the Territory Plan under the Planning Act, 2023. A minor plan amendment or a major plan amendment.

A minor plan amendment is a change to the Territory Plan that does not require a referendum. It can be used to provide minor relocation of boundaries and would not be relevant in this case. A minor amendment can be made to remove an inconsistency between the Territory Plan and the National Capital Plan, which would arise if the designated land boundaries are amended in the NCP without the Territory Plan also being amended, however as the precinct master plan also relies upon other Territory Plan amendments, this should not be necessary.

Major plan amendments represent larger changes in policy and are prepared by the TPA, but can be proposed by a proponent, government or the minister. Irrespective of the proponent for the amendment, they typically follow the same process and usually require the preparation of a supporting report which outlines the need for the amendment, the impacts of the amendment and how it would give effect to the Planning Strategy and District strategy. The process for a major amendment to the Territory Plan is set out under part 5.2 of the Planning Act, 2023.

In the case of a precinct-wide major amendment, this would be undertaken by the TPA. There are different options that could be considered for a major plan amendment subject to the agreement of the TPA. This amendment would be subject to requirements in the District Policy that apply to the land. Changes could also be made to the Technical Requirements of the Territory Plan (refer to Proposed Land Use on pages 88 to 89).

Consideration could be made to the possibility for introducing a future urban area (FUA) over part of the precinct. This would be subject to ongoing planning conditions for this area as part of the subdivision design development.

Within an FUA, minor plan amendments can be undertaken, which could support master planning or changes if development does not proceed for some time. A FUA also increases the amount of native vegetation clearing that can be contemplated before it is required to be cleared.

Under s157 of the Planning Act, once the TPA has prepared a MPA and given the major plan amendment to the Minister for approval, a proponent can apply for development approval. A Subdivision Design Proposal (SDP) or DA can be prepared concurrently with a Major Plan Amendment.

In locations where land is to cease being National Land or within Designated Areas, and hence will become subject to the requirements of the Territory Plan, the Territory Plan is amended in anticipation of the change, so that the appropriate planning controls are in place.

Development Applications process

Development Options

There are many possible ways development could be progressed within the precinct which will be subject to future decisions.

Development Applications

Following a Major Plan Amendment, development that the MPA facilitates can be proposed. Various options could be considered, such as:

- Subdivision Design Proposal(s) (SDPs) that identify the proposed blocks, roads, services and block consolidation.
- Alternatively in areas of unleased Territory land new blocks can be created without the need for subdivision, but where new roads and service connections are required, an SDP would be required.
- Development of buildings, services, demolition, roads etc.

Other usual considerations for development assessment and approval would be required under the Planning Act, 2023.

Environmental Assessment process

Environmental Assessments

Concept planning and understanding constraints and environmental impacts will be a key factor for planning components of future development.

Environment Protection and Biodiversity Conservation Act, 1999

Across the whole precinct, potential for development to impact on matters of national environmental significance must be considered. This is relevant to areas subject to both the NCP and to the Territory Plan. Where possible protected values should be avoided, but where matters cannot be avoided a self-assessment process is available under the EPBC Act which should be used. If a self-assessment indicates that a proposed action is likely to have a significant impact on matters of national environmental significance, a referral can be made to DCCEEW for a decision on whether the action is a controlled action and requires assessment under the EPBC Act.

ACT Environmental Assessment

Under the EPBC Act for any proposal, the Territory would also require an Environmental Impact Assessment (EIS) under the Planning Act on Territory land and the bilateral process (if established) may be relevant.

Bilateral Environmental Impact Assessment Process

A new bilateral agreement between the Australian Government and the ACT Government for a combined environmental assessment process to streamline approvals is currently being prepared. Subject to its implementation, if a controlled action decision is made by the Australian Government under the EPBC Act, one EIS can be prepared to provide an assessment for both MNES and for the matters and considerations under the ACT legislation (Planning Act, 2023).

ACT EIS or ESO Process

Following consideration of EPBC Act matters on Territory land, other matters that could trigger the need for environmental impact assessment also need to be considered under the Planning (General) Regulation 2023. There are 25 items as waste facilities, infrastructure projects, airports and the like. Items 16-25 are for areas and processes which have the potential to have an adverse environmental impact to species and communities listed under the Nature Conservation Act.

An Environmental Statement of Opinion (ESO) can be sought. But an ESO will only be required if a proposed action is likely to have an adverse environmental impact in relation to the matter for which an ESO is sought. An ESO is typically provided for proposals that are smaller in scale and impact, where impacts have in the majority been avoided. An ESO is valid for 18 months so multiple ESO's may be required for long-term or staged projects.

If a proposed action is likely to have an adverse environmental impact, an EIS process would be required, this could potentially be a bilateral process if it relates to MNES. An EIS process typically takes 2 years.

Territory Priority Project process

Territory Priority Projects (TPP) process

A proposed action is likely to have an adverse environmental impact if it is a TPP. A TPP is a proposed action that is declared to be a TPP by the Chief Minister and Planning Minister if they meet certain criteria. If a declaration is required, it must be made prior to a development application being lodged.

A DA for a TPP must be decided by the Planning Minister (or their delegate) supported by advice from the TPA. A proposed action is likely to have an adverse environmental impact if it is a TPP. The North Canberra Canberra Hospital project has already been declared a TPP. A new stadium for the ACT would be expected to meet the TPP criteria.

4.5

**INTEGRATED WITH
BELCONNEN AND
BEYOND**

Infrastructure and Servicing

This section presents an assessment of infrastructure and servicing across the precinct. It includes a review of the existing infrastructure networks and servicing evaluation of the infrastructure upgrades and development.

The assessment adopts a strategic approach, considering the upper range of potential demand associated with the two development scenarios to inform indicative servicing requirements. This ensures that the analysis captures potential peak infrastructure demand and provides an appropriate basis for future detailed investigations.

It is noted that the North Canberra Hospital upgrade is currently progressing through the Design and Construct phase. As its servicing catchment is functionally separate from the remainder of the project precinct and being designed by others for ACT Government, an infrastructure and servicing assessment of this area has been excluded from this report.

Demand inputs for the assessment have been derived from the residential and commercial yields outlined in the Land Use, Built Form and Density section of this report. The upper bounds of these yields have been applied to ensure that the assessment appropriately captures potential peak servicing demands and informs the scale of infrastructure provisioning required.



Infrastructure and Servicing

WATER

Existing Infrastructure

Water Supply

A 900 mm diameter mild steel cement-lined (MSCL) trunk main traverses the site, conveying water from the Aranda Reservoir under the management of ICON Water. This critical asset supplies the Canberra Institute of Technology via a network of branching domestic water mains.

Along the Haydon Drive boundary, a 500 mm cement-lined cast iron (CICL) water main provides supply to the North Canberra Hospital via a 100 mm diameter ductile iron (DI) connection. This 500 mm CICL main connects to a 375 mm CICL main that runs along the Battye Street boundary.

The 375 mm CICL main along Battye Street, together with a 300 mm ductile iron cement-lined (DICL) main along Podium Way, forms the primary distribution system supplying the Australian Institute of Sport (AIS) and Canberra Stadium. Both the 375 mm CICL and 300 mm DICL mains feed into a connecting DICL main along Leverrier Street, which in turn supplies the AIS and Canberra Stadium precinct.

For more information on the existing water supply network, see the following page.

Easements

An existing easement is associated with the 900 mm MSCL trunk main within the block bounded by Battye Street, Braybrooke Street, and Podium Way. This easement must be maintained and protected to ensure access for operation, maintenance, and asset protection.

In addition, the 300 mm DICL main along Podium Way is subject to easements. Works must account for these easements, with appropriate setbacks and access provisions incorporated into the design.

Proposed Development

As part of this project, an assessment has been undertaken of the additional demand generated by the proposed development across the site. This high-level assessment considers the upper range of potential demand across the two development scenarios to inform servicing requirements. It excludes the North Canberra Hospital upgrade as this work is currently in the detailed design phase and its servicing catchment is distinct from the remainder of the project precinct.

Three primary sources of water demand have been identified:

- Residential (Super High-density)
- Commercial space
- Public open space

The water demand for the proposed development is assessed against the Icon Water Standard STD-SPE-G-012, Supplement to WSA 03-2011-3.3 Water Supply Code of Australia. These are shown in the Table 1.

As outlined previously in the Land Use, Built Form and Density section of the report, a maximum of 5,800 people has been estimated based on the scenario layouts. These values represent the maximum across the two considered scenarios.

Table 2 summarises the additional water demand required for the proposed development.

The additional water demand required for the proposed development is summarised in Table 2. The values represent the maximum across the two considered scenarios. The additional water demand required for the proposed development is summarised in Table 2. The values represent the maximum across the two considered scenarios.

ICON Water Response

Regarding the water supply assessment, ICON Water advised:

- The additional water demand required for the proposed development is summarised in Table 2. The values represent the maximum across the two considered scenarios.
- Based on a preliminary review, the proposed development is likely to trigger water network pressure zoning arrangements.
- » The extent of the required network upgrades and rezoning will be subject to further hydraulic assessment.
- ICON Water recommended the preparation of a comprehensive water supply Master Plan to support future servicing investigations.
- » The Master Plan should consider detailed development demand information, ultimate development yields, and distribution.
- » The Master Plan should consider detailed development demand information, ultimate development yields, and distribution.
- ICON Water requested the preparation of a development staging plan to coordinate future infrastructure delivery.
- » The staging plan will assist in aligning network upgrades with development timing and identifying the sequencing of required augmentation works.
- Further detailed assessment will be required to determine the full extent of water supply infrastructure upgrades necessary to service the proposed redevelopment while maintaining compliance with ICON Water service level requirements.




Figure 53. Existing water infrastructure

Figure 55. Table 1

Development type	Units	Peak Day Demand	Peak Hour Demand	95th Percentile Demand
Residential Super High-density	tenement / day	550	2200	1452
Commercial	L / Ha / s	0.432	1.08	0.7128
Playing Fields: Automatic Night Watering	L / Ha (irrigated area)	1.2	3.5	2.31

Figure 54. Table 2

Land Use Type	Service Area (ha)	Total Dwellings	Peak Day Demand (L/s)	Peak Hour Demand (L/s)	95th Percentile (L/s)
Urban Apartments	37.27	5800	36.92	147.69	97.47
Commercial	4.14	0	1.79	4.47	2.95
Urban Open Space	9.00	0	10.80	31.50	20.79
Total		5800	49.51	183.66	121.21


Infrastructure and Servicing

STORMWATER

Existing Infrastructure

The existing stormwater network comprises a combination of underground pipe systems. Based on the topography of the site, the runoff generally drains from south to north through minor systems before connecting to larger trunk infrastructure.

The existing stormwater infrastructure is shown in the .

The existing ponds/wetland at the north of the Precinct is part of the existing stormwater system functioning in a  the blue-green infrastructure in Figure 11.


Proposed Development

No detailed stormwater modelling or design has been undertaken at this stage. Further investigation will be  requirements.

Future stormwater design will be undertaken in accordance with the requirements of ACT Municipal  Revision 2). This includes, but is not limited to:


-  below pre-development conditions for relevant design events
- providing adequate major and minor drainage systems (including 1% AEP major event conveyance)
- incorporating water quality treatment to achieve required pollutant reduction targets applying Water Sensitive Urban Design (WSUD) principles and a treatment train approach

 precinct-scale WSUD strategy.



The stormwater approach for the Bruce Precinct will be informed by the layered WSUD strategy outlined earlier in this report, with drainage design to be developed through an integrated, multi-scale framework.

At the precinct scale, centralised assets such as ponds and wetlands are expected to play a key role in stormwater management, potentially providing detention, treatment and opportunities for harvesting and reuse. These systems are anticipated to contribute to the overall structure of the major drainage network and management of larger storm events.

At the street and lot scales, distributed WSUD measures may be adopted to reduce runoff at source through  surfaces, tree pits and rainwater harvesting, providing pre-treatment prior to discharge to downstream systems.

In combination, a treatment train approach is intended to:

-  post-development hydrology
- improve stormwater quality through staged treatment
- provide opportunities for reuse and reduce reliance on potable water
- 

Further investigation, modelling and detailed design  management approach and demonstrate compliance with relevant standards, including MIS  conveyance and water quality requirements.

As noted previously in the report in covering the blue-green infrastructure, a precinct scale consideration of water quality through the expanded and enhanced wetland system can provide both water quality treatment as well as stormwater detention and storage. Refer Figure 11 to show proposed increase in the wetland system to the north of the Precinct.

The North Canberra Hospital stormwater catchment drains to the southwest and functionally separate from the remainder of the project precinct. Drainage upgrades for the North Canberra Hospital project are being assessed as part of the current Design and Construct stage by ACT Government.




Figure 56. Existing stormwater infrastructure

Infrastructure and Servicing

SEWER

Existing Infrastructure

The site has been divided into three indicative drainage catchments based on existing topography. Catchment 1, located in the south, services North Canberra via 150 mm and 225 mm VCP pipes (VCP).

Catchment 2 (approximately 15.2 ha), bounded by Mary Potter Circuit, Haydon Drive, Battye Street, and Purdie Street, services the Canberra Institute of Technology via 150 mm and 225 mm VCP pipes.

Catchment 3, the northern-most catchment, services Canberra Stadium, the Australian Institute of Sport (AIS), and the Evoenergy Bruce Switching Station via a network of pipes ranging from 150 mm to 375 mm in diameter. These pipes are constructed from polyvinyl chloride (PVC) and reinforced concrete pipe (RCP), in addition to VCP.

Easements

An existing easement is associated with the 900 There is one sewer easement within the development site, located along Battye Street, containing a 225 mm VCP that services Catchment 2.

The existing sewer infrastructure and catchment details are shown in the table below. For more information, see the table on page 111.

Proposed Development

As part of this project, an assessment has been undertaken of the additional demand generated by the proposed development across the site. This high-level assessment considers the upper range of potential demand across the two development scenarios to inform servicing requirements. It excludes the North Canberra Hospital upgrade as this work is currently in the detailed design phase and its servicing catchment is distinct from the remainder of the project precinct.

Three primary sources of sewer demand have been identified:

- High-density Residential
- Commercial space

Total Equivalent Population for these demand sources have been determined using the parameters set out in the table below. These are shown in the table below.

Development Type		Equivalent Population per Unit
High-density Residential	Per dwelling	2
Commercial	Gross Lettable Floor Space (10,000 sqm)	300




Figure 57. Existing sewer infrastructure



Infrastructure and Servicing

Table 58. Additional Sewer Demand for Proposed Development

As previously noted, a maximum of 5,800 dwellings adopted for the assessment as outlined in the Land Use, Built Form and Density section of the report. These demands have been distributed across Catchments 2 and 3 based on upper-bound assumptions to

This results in 2,900 dwellings allocated to Catchment 2 and 3,500 dwellings to Catchment 3. An additional 200 dwellings associated with the AIS upgrade have been assigned to Catchment 3, increasing its total to

The North Canberra Hospital upgrade is the only proposed development within sewer Catchment 1, and consequently, its servicing catchment is functionally separate from the remainder of the project precinct. therefore not directly connected with the balance of the precinct. Servicing requirements for the North Canberra Hospital upgrade are being assessed as part of the current Design and Construct stage by ACT Government.

with the method outlined in IW.3.4 of Icon Water Standard STD-SPE-G-011, Supplement to WSA 02-2014-3.3 Gravity Sewerage Code of Australia

The table below summarises the additional sewer demand required for the proposed development.

ICON Water Response

- Regarding the sewer servicing assessment, ICON Water advised:
- There is concern that the existing sewer network may proposed redevelopment, in conjunction with other known growth within the surrounding catchment.
 - The proposed development assumptions for the Canberra Institute of Technology (CIT), Australian Institute of Sport (AIS) and North Canberra Hospital represent an increase of approximately 3,000 Equivalent Persons (EP) compared to the development information currently held by ICON Water.
 - ICON Water noted that the majority of this increase appears to be associated with the proposed redevelopment of the CIT site
 - Lawson and University of Canberra catchments, major sewer network augmentations are likely to be required.
 - The extent of these augmentations will need to be network assessment.
 - Local sewer augmentations are also expected to be triggered by the proposed redevelopment.
 - information becomes available.
 - need for sewer augmentation works.
 - Given the increased Equivalent Population adopted for the current assessment, additional local sewer augmentation works may be required beyond those
 - ICON Water requested an indicative development staging program to assist with future network planning and scheduling of capital works and existing infrastructure augmentation.

Figure 58. Additional Sewer Demand for Proposed Development

	Á Á' (ha)	EP	TEP	Aeff (ha)	ADWF (L/s)	PDWF (L/s)	° É ¼ > ¸ ¢ (L/s)
1	North Canberra Hospital upgrade						
2	15.22	2	6340	16.30	13.21	32.09	0.24 20.07
3	21.79	2	8089	23.18	16.85	39.95	0.35 27.36



Infrastructure and Servicing

 $0' \text{ } \mathcal{AE}$

Existing Infrastructure

There is existing gas infrastructure within the site which services the North Canberra Hospital, Canberra Institute of Technology, Canberra Stadium and the AIS.

Ç Ü Ø ë Û æ þ Ů Ő Á À Å Ô æ ç Ä å Ö Ç Ü Ø Ú è å Ů á
the following page.

Proposed Development

Existing gas infrastructure within the Bruce Precinct is expected to be retained in the short to medium term to service established uses, with its future role dependent on redevelopment staging and the extent of works.

The approach to gas will be guided by the ACT legislative framework, including the Climate Change and Greenhouse Gas Reduction Act 2010, which supports emissions reduction and restricts new natural gas connections in prescribed areas.

Consistent with this direction, new development is expected to minimise reliance on natural gas, with a preference for all-electric systems where feasible.

Opportunities to rationalise or progressively decommission existing gas infrastructure may arise to a fully gas-free precinct will be subject to further investigation, including feasibility, staging and cost considerations.

¶ Â Ã Ä È Á ¼ ¶ ´ Ç ¼ Â Á Æ

Existing Infrastructure

There is existing communications infrastructure within the site which services the North Canberra Hospital, Canberra Institute of Technology, Canberra Stadium and the AIS.

The existing communications infrastructure is shown in

Proposed Development

Based on the current assessment, there are no infrastructure that would restrict the delivery of the proposed development outlined in this report.

As part of subsequent project stages, communications servicing will be further developed through design development and ongoing engagement with relevant authorities and service providers. This process will ensure that the proposed works are consistent with applicable standards and regulatory obligations.

Any required upgrades should prioritise the delivery of infrastructure, consistent with the precinct's education and innovation aspirations.




Figure 59. Gas Infrastructure servicing the Precinct





Figure 60. Communications infrastructure servicing the Precinct



Infrastructure and Servicing

ELECTRICAL

Existing Evo Energy Network


The proposed development area is centrally located between two zone substations on Evo Energy's 132 kV network, namely the Belconnen and Civic substations. The area and its surroundings are currently supplied by an 11 kV feeder from these two zone substations.

11kv Feeder Á â ã	1 Ø Ø × Ø å Á Ô à Ø	Zone Æ è Ñ æ ç Ô
1	Belcon 8VB SWNDNLAMP	Belconnen
2	Belcon 8XB BATTYE	Belconnen
3	Belcon 8+FB EARDLEY	Belconnen
4	Belcon 8UB SHANNON	Belconnen
5	Belcon 8WB HAYDON	Belconnen
6	Civic 8YB DRYANDRA	Civic
7	Civic 8+QB BELCWAYNT	Civic

The map in the following page shows the feeder layout from Evo Energy's annual planning data portal. Most of the existing loads in the proposed area and its surroundings are supplied by feeders 1, 2, 3, 5, and 6, while feeders 4 and 7 are in the vicinity of the proposed site.

Electrical Infrastructure Assessment:

1. The existing 11kV network allows extensions and connection points to supply the rising demand from the proposed development via the existing 11kV feeder network.
2. The existing 11kV network is a semi-mesh distribution network designed to ensure increased redundancy and load-transfer capability.
3. The ability to transfer loads depends on the existing feeder wires and cables, as well as the capacity and availability of the zone substation. According to Evo Energy's Distribution Annual Planning Report 2025, the estimated load transfer to the Belconnen zone substation from other zone substations is 36MW in summer and 33.8MW in winter. Civic zone substation expects to receive 45.1MW in summer and 49.7MW in winter.
4. The forecast capacity transfers as above allow Evo Energy to manage the increased demand during peaking periods of the year.
5. Some large existing demands are situated near the proposed development area. These load centres are supplied by multiple feeders for enhanced reliability. The Next Gen Data Centre is an example and is reported to have an ICT load of 4.4MW.
6. The feeders supplying this area have less PV solar and battery integration, which increases peak demand on the zone substation and feeder infrastructure.
7. According to the Evo Energy Distribution Annual Planning Report 2025, a transformer is to be added in the Belconnen zone substation to cater for the increasing demand in the catchment area, including the proposed development area. This project has been tentatively marked for the 2029-2034 regulatory period.
8. If the forecast maximum demand over the decade increases by approximately 10MVA Evo Energy will need to consider the installation of a third transformer. This project will provide new 11kV feeders and is to be installed from the zone substation towards the load centre via Ginninderra Drive.



Infrastructure and Servicing

Maximum Demand Estimation

The maximum demand for the proposed development area has been calculated using the typical after-
proposed dwelling type, and standard allocations in accordance with AS/NZS3000:2018 have been applied to the commercial area developments.

The demand in the Active sports area has been determined based on the type of sports lighting to be installed. The daily demand variation for each of these categories has not been deemed necessary at this stage, but the overall maximum demand might be lower than the total outlined in Table 1.

Further assessment of the Evo Energy network is necessary, including technical network studies to identify constraints, identify potential feeder candidates for future load transfers, and construct new 11kV feeders along Ginninderra Drive. These network technical studies will be carried out by Evo Energy, and detailed information will be needed to commence them.

Non-network solutions, such as medium-scale battery storage with pad substations, can be used to manage demand peaks and cut distribution network development costs. These options should be discussed with Evo Energy in detail during the later stages of
as the number and type of dwellings, sports lighting
agreed upon.

It is noted that while the AIS Podium project will introduce additional electrical demand, the proposed facilities are not considered major electrical load centres, with the primary higher-demand component being sports lighting associated with the Indoor Sports Dome. Based on the available information, the
relative to the broader Bruce Precinct development. Evo Energy has planned for future growth within the broader precinct, and the cumulative electricity demand associated with future development across the Bruce Precinct should be considered as part of ongoing network planning and engagement with Evo Energy at subsequent stages.

It is reiterated that servicing requirements for the North Canberra Hospital upgrade are being assessed independently as part of the current Design and Construct phase being undertaken by the ACT Government. Accordingly, this component has been excluded from the above preliminary electrical servicing assessment.

Ref	Load Type	Á â â Û Dwellings	Þ É ´ ã ø å · ê ø ß ß Ü á Ú	Ç â ç
1	Dwelling 2 people living	5800	2.5 kVA ADMD	14.5
		No of SQM	Watts per SQM	
2	Commercial Area	41400	150	6.21
3	Active Sports area	90000	15	1.35
	Pro TV Broadcast Standard			
4	Miscellaneous (street and pathway lights, car parks, etc.).			0.25
Total				22.31

Figure 62. Table 1



4.6

**DELIVERING A LEGACY
OF RESILIENCE FOR
GENERATIONS TO COME**

Environmental Sustainability and Resilience

á é Ü å å à Ø á ç Ò ß Æ è æ ç Ò Ü á Ò Õ Ü ß Ü ç ì Ò á × Å Ø æ Ü ß Ü Ø á Ò Ø Ù å å µ å è Ö Å å Ø Ò Ü á Ò ç æ Ø Ø Þ æ ç â ß Ø é Ø å Ò Ú Ø Ò â ß Ò Ò å å Ò ç Ü å á â ã å å ç è á Ü ç Ü Ò Ø ç è Ø Ø á à è ß ç Ü ã ß Ø æ ç Ò Þ Ø Ü â ß × Ø å æ ç â Ü á æ å Ü å Ø Ò Ò å á á Ø Ò ç Ø á Ø ç í Ø å å Ø á Ò Ò ß Ø × ÿ Ò á × æ å Ò Ü Ò ß ß Ò Ü á Ò ß è æ Ü é Ø å å Ø Ò Ü á Ò ç ì

The purpose of this section is to align Bruce Precinct's stakeholders around a common vision, clear priorities, and actionable initiatives. It has been designed to enhance innovation, attract investment, and create long-term value for users and the broader community.

It comprises the following strategic components: relevant regulatory frameworks and guidelines, principles from the United Nations Sustainable Development Goals (SDGs), and precinct ambition.

Å å Ø Ò Ò å Ò Ü ç Ü Ò å æ Ü å å è Ü å Ø æ Ø á ç Ü Ø × during an interactive sustainability workshop with stakeholders



Strategic Alignment

Å Ø Ú è ß Ô ç â à ì ¹ â Ô à Ø ê â å þ æ Ô á × ° è Ü × Ø ß Ü á Ø æ

The site is informed by the strategic planning for the Belconnen District and ACT policies to guide sound sustainability planning and alignment with statutory strategic goals.

Instrument	Description	Relevance to Bruce Precinct
Environment Protection and Biodiversity Conservation Act 1999 (EPBC Act)	Federal National legislation protecting matters of national environmental significance.	Ensures precinct's planning and development avoid or mitigate impacts on protected species, habitats, and cultural heritage.
Belconnen District Strategy	ACT Aligns district outcomes, priorities, and assessment criteria.	Ensures alignment of Bruce Precinct with broader Belconnen growth, transport connections, and land use priorities.
Territory Plan	ACT Statutory framework for land use, zoning, and development controls in the ACT.	Provides the legal basis for zoning, density, and land use decisions in Bruce Precinct.
ACT Climate Change Strategy 2019-2025	ACT Sets a pathway to net zero emissions by 2045, with interim targets and a focus on reducing greenhouse gas emissions from transport.	Informs Bruce Precinct's energy strategy, building performance, and climate adaptation measures.
ACT Government's Active Travel Plan	ACT Sets out priorities and design guidance to make walking, cycling, and micromobility safer and more accessible.	Promotes active transport infrastructure, reducing emissions, enhancing community health and connected movement networks in Bruce.
ACT Government's Water Sensitive Urban Design	ACT Provides principles and practical guidance for integrating water management into urban design.	Supports stormwater reuse, water quality, and biodiversity in Bruce's open space and streetscapes.
Gender Sensitive Urban Design Framework	ACT Toolkit for inclusive, safe public spaces.	Promotes equitable access and safety for all genders in Bruce's public realm.
ACT Urban Design Guide	ACT Design principles for public realm, streetscapes, and built form.	Enhances quality, accessibility, and sustainability of Bruce's urban environment.

Figure 63. Overview table of Sustainability Regulatory Frameworks and Guidelines

Environmental Sustainability and Resilience (continued)

Sustainability Approach

The United Nations Sustainable Development Goals (SDGs) provide a globally recognised framework for guiding sustainable development outcomes across environmental, social, and economic dimensions.

Adopted as part of the 2030 Agenda for Sustainable Development, the SDGs comprise 17 interconnected goals that collectively aim to address key global challenges, including climate change, resource

The strategies outlined in the following pages have been developed through the multidisciplinary analysis presented in the preceding sections of this report and are mapped against this global best practice framework to ensure alignment with internationally recognised sustainability objectives and outcomes.

Environmental Sustainability and Resilience (continued)



Build resilient infrastructure, promote inclusive and sustainable industrialisation and foster innovation.

industry, and government to drive integrated outcomes across sport, health, and education.



Figure 68. Map of the district covered by the Kendall Square Association, an example of a precinct-wide collaboration framework.



Figure 69. A directional sign for the St Kilda Arts Precinct, showing various cultural venues.

- Develop a precinct-wide collaboration framework, such as a charter or alliance model, to align key stakeholders (e.g. AIS, CIT, North Canberra Hospital and government) around shared objectives, governance arrangements, and coordinated delivery of initiatives.
- Institutional and Industry Partnerships: Facilitate structured partnerships between major institutions, industry, and private sector stakeholders to support joint research, shared facilities, and innovation-led economic development within the precinct.
- Establish a coordinated location of sport, health, education, research, and commercial uses to promote knowledge exchange, cross-sector collaboration, and the development of innovation clusters.
- Employment Pathways for Traditional Custodians: Engage climate adaptation services and vegetation management led by Traditional Custodians. Interweave Non-Human Kin Country materials into the landscape, buildings and urban areas.
- Establish a coordinated governance structures and working groups to manage precinct-wide initiatives, support stakeholder alignment, and enable delivery of innovation outcomes at a whole-of-precinct scale.



Figure 70. Pingshan Sports Park blending sports facilities with the surrounding urban fabric.



Ensure access to affordable, reliable, sustainable and modern energy for all.



Figure 71. A win-win solution with shade and renewable energy generation.



Figure 72. Community battery in Cammeray, NSW.




Figure 73. A datacentre located adjacent to the precinct which could provide waste heat energy for water or space heating

¾, Ì Æ Ç Ä ´ Ç, ° ¼, Æ -

- Buildings by eliminating reliance on fossil fuels for heating, hot water, and cooking, and aligning new development with all-electric design principles. Provide no new piped gas connections and phase out existing.
- An integrated precinct-scale energy infrastructure, including microgrids and energy sharing networks, to optimise electricity grid operation and increase access to locally generated renewable energy across precincts such as AIS, CIT, and health facilities.
- Maximise solar photovoltaic (PV) generation across large roof areas and carparking structures, including potential solar shading over car parks.
- Energy storage at building and precinct scale to support load balancing, improve resilience, and enable effective use of on-site renewable energy.
- Waste Heat Recovery: Investigate waste heat recovery opportunities by capturing and reusing excess heat from the neighbouring datacentre for pool water heating or domestic hot water systems.
- Provide an integrated low-emission transport infrastructure across the precinct, including public, low-emission transport.
- Upgrade existing buildings and infrastructure to improve energy performance, recognising the constraints of the precinct.
- Coordinate energy planning across stakeholders to optimize precinct-wide outcomes, including demand management, infrastructure planning, and integration of emerging technologies.

Environmental Sustainability and Resilience (continued)



Take urgent action to combat climate change and its impacts.

proactively to the impacts of higher temperatures and extreme weather events.

- Provide extensive tree canopy and green infrastructure to streets, public spaces, and open areas to provide shade, reduce heat, and enhance ecological performance.
- Integrate cool building mitigation strategies, including shading structures, high-albedo and cool materials, and water-based cooling elements within the public realm and built environment.
- Develop a coordinated precinct-wide climate adaptation strategy that addresses weather across all development phases.
- Preserve and integrate existing bushland, green corridors, and natural landscapes within the precinct to support biodiversity, cooling, and long-term resilience.



Figure 74. Lake Ginninderra, Canberra.

PROJECTED CHANGES						
	 Low-emissions scenario		 Medium-emissions scenario		 High-emissions scenario	
	2050	2090	2050	2090	2050	2090
 Increase in average temperature	+1.1°C	+1.2°C	+1.4°C	+2.5°C	+1.8°C	+3.7°C
 Increase in hot days per year	+2.6	+3.2	+3.6	+8.0	+5.3	+12.8
 Decrease in cold nights per year	-19.1	-22.3	-26.8	-46.6	-32.4	-67.7
 Decrease in average spring rainfall	-9.9%	-16.6%	-12.6%	-22.6%	-16.8%	-21.8%

Figure 75. Projected changes to the climate (2025, Australian Capital Territory, Climate Change Snapshot, NARCIIM)



Figure 76. The rise in average temperatures is projected to be 2-2.5 degrees Celsius by 2090 under a medium-emissions scenario. (2025, Australian Capital Territory, Climate Change Snapshot, NARCIIM)



and regenerative water cycle that enhances environmental performance and supports



- **Integrating permeable paving, rain gardens, rain barrels, rainwater harvesting, and other green infrastructure practices to improve stormwater quality and support on-site water reuse.**

- **Blue Corridors:** Provide water body connectivity throughout the site and neighbouring site, linking these with green spaces in blue-green infrastructure to improve water quality and strengthen landscape outcomes.

through passive watering approaches that direct runoff into adjacent landscape areas, and harvesting in the existing ponds, reducing potable water demand and supporting tree canopy and vegetation health.

- $\frac{1}{4}$ of the world's gravel trenches, and similar subsurface systems along

- stormwater leakage on-site to mimic natural environmental



Environmental Sustainability and Resilience (continued)



Ensure sustainable consumption and production patterns.

Develop an environment that minimises waste and reduces material consumption across all stages of development and operation.

- Support precinct-scale initiatives for material reuse and sharing, including opportunities for salvaging, stockpiling, and redistributing reusable materials across development stages. Collaborate to develop strategies and identify opportunities across institutions.
- Align procurement processes with circular economy principles by prioritising materials with sustainability credentials.
- Operational Waste and Organics Management Systems: Support precinct-scale systems for ongoing waste management, including organics recycling, to reduce operational waste streams and enable circular resource use across businesses and facilities.




Figure 83. Wheelstops made from recycled plastic in Burwood, Victoria.



Figure 84. Vermicomposting units part of Canberra's Worms Downunder for management of organic waste.



Figure 85. Provide space for an item library, swap shop or recycling centre like the Recyclery in Harrison, ACT.



Figure 86. Support the local Bruce UC Repair Café, by helping them to expand from clothing repairs.

Measurable Targets

Establishing clear sustainability targets is essential to guiding the Bruce Precinct Master Plan towards

measurable environmental, social and economic outcomes. Targets provide a framework for additional sustainability goals that align design decisions with broader policy goals and ensure that the development of the precinct is resilient to climate change, and that the precinct is a model for sustainable development. By setting ambitious yet achievable benchmarks, the master plan can lead by example.

Category	Targets	Sources
Water Use	40% reduction in mains water	WSUD Central Code
Stormwater Quality	80% reduction in average annual stormwater pollutant loads	ACT WSUD Guidelines
Stormwater Reuse	Stormwater to be used on site	WSUD Central Code
Construction Water	Use non-potable water sources for construction where feasible	Sustainable Civil Works Framework
Urban Canopy	30% urban tree canopy cover	ACT Climate Change Strategy / Urban Forest Act / Urban Forest Strategy
Surface Permeability	30% surface permeability	ACT Climate Change Strategy
Water Use in Precinct Systems	30% reduction in water use in precinct systems	ACT Climate Change Strategy
GHG Emissions Reduction	Reduction in GHG emissions	Climate Change and GHG Reduction Act
Renewable Energy	Increase renewable energy use and generation	Climate Change and GHG Reduction Act
EV Infrastructure	Expansion of EV charging network	ZEV Strategy
Transport Mode Share	80% of trips by walking, cycling, or public transport	ACT Active Travel Plan / One Planet Living
Green Space / Biodiversity	10% increase in green space or habitat	Green Star Communities
Affordable Housing	10% increase in affordable/social housing	ACT Housing Strategy / Best practice precincts
Construction Waste	98% of construction and demolition waste diverted from landfill	Sustainable Civil Works Framework
Material Reuse	100% of usable spoil to be reused	Sustainable Civil Works Framework
Recycled Materials	Increase recycled content in construction materials	Sustainable Civil Works Framework / Circular Economy Strategy
Operational Carbon	Net zero operational carbon (buildings)	Green Star Buildings / Living Building Challenge
Embodied Carbon	10% reduction in embodied carbon	Green Star / NABERS Embodied Carbon Guide
Residential Energy Performance	10% increase in energy efficiency	Green Star Communities / ACT Housing Strategy
Design Process / Governance	100% of design phases include co-design with community and Traditional Custodians	Connecting with Country / Gender Sensitive Urban Design

Figure 87. Overview table of Sustainability Regulatory Frameworks and Guidelines

Indicative Costing

Costing of infrastructure, public realm, environmental, sustainability and planning costs required to support the future development of the Bruce precinct.

Using benchmarks of urban development rates (rather than detailed design), the estimate is based on a site area for development of 1.5ha. The estimate includes costs for infrastructure to support around 5,800 dwellings, including transport upgrades, utility networks, public open space improvements, planning approvals, further investigations/studies and gross construction costs.

Costs of construction of residential and commercial buildings and any development within AIS precinct and North Canberra Hospital developments. This represents the cost of enabling infrastructure and precinct-wide improvements rather than the full development cost of the Bruce Precinct.

Table 1: Indicative Costing Summary

- Site area assumed for development to be 1.5ha
- Green space area assumed to be 0.5ha
- Based on 260626_BPM_Final Scenarios Report_DRAFT_Optimized.
- Assumes most works are undertaken during normal working hours.
- Rates current as of July 2026.
- Costs are based on urban development benchmarks.
- Assumes residential development is split 50/50 between high and low density.

Table 2: Indicative Costing Breakdown

- Way/Haydon Dr intersection, signalisation Battye/Braybrooke/Purdie St intersection, Masterman St extension,
- Active travel paths upgrade
- Green space and landscaping and outdoor recreation space allowances.
- Upgrades of stormwater trunk, sewer trunk, electrical network supply and NBN Infrastructure to 5,800 dwellings.
- Further investigations, reports, approvals, environmental investigations, Indigenous design advisory, transport and sustainability studies, business case and surveys and investigations.
- Construction cost preliminaries, 5% builder's margin, 2% allowance for hazardous materials risk, 15% design development contingency, and 2% staging allowance.

Table 3: Indicative Costing Assumptions

- Work at penalty rates for out of hours construction (if required)
- Construction cost of dwellings and commercial buildings
- Developments within the AIS precinct and the North Canberra Hospital precinct,
- Off-site works other than the intersection upgrades.
- HV Supply upgrades
- Legal costs
- Australian Goods and Services Tax (GST).



SITE AREAS INCLUDED FOR COST ESTIMATION

- Developable area: 497,573 sqm
- Green Space area: 283,339 sqm

Figure 88. - Costing Area Map

Infrastructure	Estimated Cost
Transport infrastructure	\$42,371,127
Water	\$7,723,344
Sewer	\$2,327,284
Stormwater and WSUD	\$10,584,664
Electrical	\$15,855,339
Communications	\$2,045,848
Public Space, Community, and Stadium	
Public domain and landscape	\$13,689,856
Community and cultural infrastructure	\$3,288,124
Stadium and anchor related enablement	Excluded
Sustainability	
Sustainability Initiatives	\$2,557,310
Incidental Works	
Incidental Works	\$4,091,695
Further Studies and Design Fees	
Phase 1 - Due Diligence	\$1,141,120
Phase 2 - Detailed Master Plan	\$3,828,960
Phase 3 - SDA and Approval	\$2,100,400
Phase 4 - Detailed Design	\$1,783,120
Other Cost	
Gross Construction Cost (GCC)	\$41,765,104
Statutory Fees and Charges	\$1,564,294
Goods and Service Tax (GST)	Excluded

Infrastructure
\$80,907,606

Open Public Space
\$16,977,980

**Sustainability
Initiatives**
\$2,557,310

Further Studies
\$8,853,600

05

CONCLUSION

Next Steps

The development potential of Bruce Precinct

× Ø æ Ò å Û Ö Ø × ê Û ç Û Û á ç Û Û æ × â Ö è à Ø á ç ç Û á â è Û Û Ö à è ß ç Û × Û æ Ò Û ã ß Û á Ö å ì ß Ø á æ Þ Û á Ö ß è × Û á Û ç á Ö á æ ã â á ç ÿ ß Ö á × æ Ò Ö ã Ø ÿ Û á Û å Ö æ ç á è Ö ç è å Ø ÿ æ è æ ç Ò Û á Ö Ò Û ß Û ç ì ÿ ã ß Ö á á Û á Û Ö á × Ø Ö å á â à Û Ö × Ø é Ø ß â ã à Ø á ç Þ ê Û ß Û è Û × Ø × Ø Ò Û æ Û á á à Ö Þ Û á Û Ö á × Û Ö Ò Û ß Û ç Ö ç Ø ç Û Ø Û Û Û Û Ø æ ç Ö á × Ö Ø æ ç è æ Ø ÿ

ç Û Û æ × â Ö è à Ø á ç ÿ Ö å à à Û æ æ Û á á Ø × Ö ÿ

Commonwealth to provide advice for future

decisions, is a critical foundational step to

Ø á æ è å Ø ç Û Ö ç ç Û Ø ã å Ø Ò Û á Ö ç Ö à Ö Û ç Û á á æ Ö Ö á Ö Ø ã å Ö Ö ç Û Ö Ö ß ß ì Ö Ö Û Û Ø é Ø × Ö Ö ß Ö á Ö Û á Û ã ß Ö Ö æ è ç Ö å à Ø æ

with technical and commercial realities.

° â é Ø å á à Ø á ç × Ø Ò Û æ Û á á æ ê Û ß ß Ö Ø å Ø æ Û å Ø × á á Ö á è à Ö Ø å â Û Û æ æ è Ø æ Û á Ö ß è × Û á Û Û á å Ø ß Ö ç Û á á ç â -

Land ownership,

The future of the stadium, and

Upgrades to the related movement network.

In order to realise the long-term vision for Bruce Innovation Precinct, a number of next steps are required. These steps are not required to be sequential but are critical to unlocking future development for Bruce Precinct.

In addition to those listed above, government decisions will be required on issues in relation to:

- Divestment arrangements across the sites to optimise the Bruce Precinct.
- Structure Planning for the Bruce Innovation Precinct that detail land use, density and networks for redevelopment areas that may include the CIT site and the Stadium Precinct.
- Market Sounding and analysis to determine accommodation typologies in terms of supply, demand and value.
- Governance model.
- Nomination of a Local Custodian representative as a member of the PWG.
- Determination of a detailed planning pathway.

Land Use, Built Form, Density & Planning

- Divestment & Consolidation of land within the Precinct for best use
- Development of 'Bruce Village' character areas

Country Systems & Sustainability

- Designing with Country
- Cultural Knowledge
- Sustainable Design Solutions

Health, Education, Sport & Economics

- Catchment/Population-based Retail
- Proximate/Complementary uses
- Formal MOU or Partnership Agreement

Movement & Infrastructure


- Off-peak carpark uses
- Purpose-built adaptable parking
- Decoupled parking models
- Early encouragement of modal shift through a walkable public realm



Decisions needed to unlock




Key deliverable or investment decision



Current Best Practise

meets the present needs of Bruce





APPENDIX

Bruce Precinct Master Plan

Transport Access and Movement Report

Prepared for:
DITRD CSA & ACT Government

Prepared by:
Chris Coath

Date:
17 July 2026

Project/File:
304001675



Revision Schedule

Revision No.	Date	Description	Prepared by	Quality Reviewer	Project Manager Final Approval
A-Dr	22/06/26	Draft	Lara Al-Hassany	Chris Coath	Chris Coath
A ' U	17/07/26	) L Q D O ' U D	Lara Al-Hassany	Chris Coath	Chris Coath

Disclaimer

The conclusions in the report are Stantec's professional opinion, as of the time of the report, and concerning the scope described in the report. The opinions in the document are based on conditions and information existing at the time the document was published and do not take into account any subsequent changes. The report relates solely to the specific project for which Stantec was retained and the stated purpose for which the report was prepared. The report is not to be used or relied on for any variation or extension of the project, or for any other project or purpose, and any unauthorized use or reliance is at the recipient's own risk.

Stantec has assumed all information received from the client and third parties in the preparation of the report to be correct. While Stantec has exercised a customary level of judgment or due diligence in the use of such information, Stantec assumes no responsibility for the consequences of any error or omission contained therein.

This report is intended solely for use by the client in accordance with Stantec's contract with the client. While the report may be provided to applicable authorities having jurisdiction and others for whom the client is responsible, Stantec does not warrant the services to any third party. The report may not be relied upon by any other party without the express written consent of Stantec, which may be withheld at Stantec's discretion.

1	Introduction	1
1.1	Background	1
1.2	Previous Reports.....	1
1.3	Scope of Report	2
1.4	Design Standards.....	2
1.5	Reference Documents	2
2	Precinct Context	4
3	Strategic Context	6
4	Principles and Objectives	7
4.1	Transport Principles	7
4.2	Transport Objectives	8
4.3	Desired Outcomes	9
5	Bruce Master Plan Scenarios	11
5.1	Scenario 1	11
5.2	Scenario 2	12
6	Road Network and Operation	14
6.1	Existing Road Network.....	14
6.2	Master Plan Traffic Generation	17
6.3	Network Traffic Operation	21
6.4	Master Plan Assessment	29
7	Parking Provisions	32
7.1	Existing Conditions.....	32
7.2	Master Plan Parking Generation.....	32
7.3	Master Plan Assessment	34
7.4	Scenario 1	35
7.5	Scenario 2	35
8	Active Travel Connections	36
8.1	Existing Conditions.....	36
8.2	Master Plan Assessment	39
9	Public Transport	40
9.1	Existing Conditions.....	40
9.2	Light Rail/Transit Corridor	44
9.3	Master Plan Assessment	47
10	Loading and Servicing	51
10.1	Objectives	51
10.2	Key Considerations	51
11	Future Transport	54
11.1	Objectives	54
11.2	Key Considerations	54
12	Summary and Conclusions	55

List of Tables

Table 2-1	Land Uses
Table 6-1	Frontage Road Classifications
Table 6-2	Internal Road Classifications
Table 6-3	Weekday Average Volumes
Table 6-4	Game Day Effect on Intersection Volumes
Table 6-5:	Residential Peak Hour (AM and PM) Traffic Generation
Table 6-6	Commercial AM Peak Hour Traffic Generation
Table 6-7	Commercial PM Peak Hour Traffic Generation
Table 6-8	Master Plan Peak Hour Traffic Generation
Table 6-9	Density plots of Reference Case and Option Case in AM period
Table 6-10	Density plots of Reference Case and Option Case in AM period
Table 6-11	Network Statistics results
Table 7-1	Commercial Parking Generation
Table 9-1	Bus Routes Passing through Precinct

List of Figures

Figure 2-1	Site Location and Key Stakeholders
Figure 2-2	Land Uses
Figure 5-1	Scenario 1 Master Plan
Figure 5-2	Scenario 2 Master Plan
Figure 6-1	Existing commercial and residential zones
Figure 6-2	Bruce Precinct zones and site accesses
Figure 6-3	Example Transit Boulevard Section
Figure 8-1	Existing Active Travel Routes
Figure 8-2	Transport Canberra Bike and Ride Services
Figure 9-1	Routes R2, R3, R4, R5, R6
Figure 9-2	Route R9
Figure 9-3	Route 901
Figure 9-4	Route 1055
Figure 9-5	Route 2012
Figure 9-6	Moving Canberra 2019-2045 Integrated Transport Strategy: Current Planned Network
Figure 9-7	Belconnen to City Transitway Option 1- Bus Lanes
Figure 9-8	Belconnen to City Transitway Option 2- T2 Lanes
Figure 9-9	Scenario 1 Public Transport Catchment 400m
Figure 9-10	Scenario 2 Public Transport Catchment 400m
Figure 10-1	Freight Current and Planned Network

1 Introduction

1.1 Background

The Bruce Sports, Health and Education Precinct is located within the Australian Capital Territory (ACT) in the suburb of Bruce. The precinct sits within an established institutional and recreational hub, with major sporting facilities, health services, and tertiary education providers, positioning it as a key destination within Canberra.

The ACT Government is committed to delivering a high value, integrated mixed-use precinct that maximises public value and delivers strong community benefit. The vision for the precinct is to create a vibrant and connected place that leverages its existing assets to support a diverse range of uses, including sport, health, education and complementary commercial and community activities.

Recognising the complexity of the precinct the ACT Government is preparing a Draft Strategic Framework. This framework is intended to establish a shared vision and enable strategic alignment between Commonwealth and Territory Government stakeholders, ensuring a coordinated and cohesive approach to planning and delivery.

The development of the precinct ambition and strategic maps plans has already been completed, providing a foundation for future planning. The project has now progressed to the preparation of the final Strategic Framework and Options Report, which will guide decision making and the next stages of implementation of the precinct.

1.2 Previous Reports

Stantec and Hatch were engaged by the Department of Infrastructure, Transport, Regional Development, Communications, Sports and the Arts (DITRDCA) to prepare the Bruce Precinct Master Plan, building on previous strategic work and aligning with the Australian Government and ACT Governments visions.

A 'Background Review and Place Analysis Report' reviewed existing background reports and information, identifying key opportunities, constraints and gaps to guide design decisions.

Subsequently, the 'Bruce Precinct Master Plan Scenarios Report' documented two development scenarios. These scenarios tested assumptions across the eight design brief elements, mapped similarities, and put forward urban design recommendations to inform the Strategic Framework.

The 'Precinct Ambition Report' summarised the place principles that informs the framework at a strategic level enabling the delivery of stakeholders and community aspirations for the site.

To provide a clear and integrated basis for future decision making, the 'Strategic Maps Report' validated the urban design recommendations against the strategic direction established by the place principles.

1.3 Scope of Report

This report sets out a transport movement and access assessment of the master plan with the strategic context of the site and surrounds, relevant standards and its anticipated transport implications on the surrounding transport network, including consideration of the following:

- x Road network and operation
- x Master plan traffic generation
- x Site access
- x Network traffic operation
- x Parking provisions
- x Active travel connections
- x Public transport including light rail
- x Loading and servicing
- x Future transport

1.4 Design Standards

The master plan transport assessment has been prepared having regard to the following key design guidelines and standards including:

- x Austroads Guide to Road Design series
- x Austroads Guide to Traffic Management series
- x Austroads Guide to Road Safety series
- x Australian Standard, Parking facilities series (AS2890)
- x ACT Government, Territory Plan and associated Design Guides
- x ACT Government, Municipal Infrastructure Design Standards (MIS)
- x ACT Government, Estate Development Code

1.5 Reference Documents

In preparing this report, reference has been made to the following documents:

- x Austroads Guide to Road Design series
- x Austroads Guide to Traffic Management series
- x Austroads Guide to Road Safety series
- x Australian Standard, Parking facilities series (AS2890)
- x ACT Government, Territory Plan and associated Design Guides and technical specifications
- x ACT Government, Municipal Infrastructure Design Standards (MIS)
- x ACT Government, Estate Development Code
- x ACT Government, ACT Transport Strategy 2020
- x ACT Government, ACT Climate Change Strategy
- x ACT Government, Active Travel Plan 2024-2030, 2023
- x ACT Government, Design Guide- Best Practices for intersections and other active travel infrastructure in the ACT, 2024
- x ACT Government, Movement and Place Assessment Guide, May 2025
- x ACT Government, ACT Road Safety Action Plan 2024-2025, 2023

- x ACT Government, ACT Infrastructure Plan Update – Transport
- x ACT Government, Parking Action Plan

2 Precinct Context

The Bruce precinct is located in Canberra's Belconnen District and covers approximately 214 hectares. The site is strategically significant, comprising major education, health and sporting institutions including the Australian Institute of Sport (AIS), Canberra Institute of Technology (CIT) Bruce campus, North Canberra Hospital and GIO Stadium. These anchors generate diverse travel demands resulting in the need to effectively master plan the precinct to optimise land use and improve movement, access and connectivity across the precinct.

The site is located approximately 7 kilometres northwest of Canberra's city centre and is bounded by major arterial roads, including Belconnen Way to the south, Ginninderra Drive to the north, Haydon Drive to the west and Gungahlin Drive to the east.

Generating diverse travel demands and patterns, the precinct accommodates daily commuter, student, visitor and event based demand associated with major sporting and entertainment uses. As such, the precinct requires a well-coordinated and multimodal transport system to support efficient movement, improve connectivity and enable future growth opportunities.


The land uses within the precinct comprises community facilities (i.e. North Canberra Hospital and CIT), transport and services (i.e. Evoenergy switching station) and designated areas (GIO stadium and AIS). The areas marked as non-urban represent the substantial proportion of green space across the precinct.

Figure 2-1 Site Location and Key Stakeholders



Source: Hatch

Figure 2-2 Land Uses



Source: ACTmap! Map

Table 2-1 Land Uses

Land Uses	Sites Represented in this Area
CFZ- Community Facilities	North Canberra Hospital, CIT
TSZ1- Transport and Services	Evo Energy
Designated Areas	GIO Stadium, AIS
NUZ3 Non Urban- Hills Ridges and Buffers	N/A

3 Strategic Context

The Bruce precinct is defined by a concentration of key institutions of national and regional significance, including the Canberra Institute of Technology (CIT) Bruce campus, the Australian Institute of Sport (AIS), GIO Stadium and North Canberra Hospital. Together, these stakeholders anchor the precinct's role in education, elite sport, health and major events, forming a strong foundation for its repositioning as an innovation precinct.

There is significant opportunity to leverage this institutional base through mixed use development, enabling a more vibrant and integrated precinct with complementary commercial, residential, education, health and hospitality and enabling greater day-to-day activation alongside event-based activity.

Strategically, Bruce benefits from strong regional connectivity. It is bordered by major arterial routes, Gungahlin Drive, Belconnen Way, Haydon Drive, and Ginninderra Drive, which serve as key transport corridors within the ACT. The future rapid transit boulevard will further strengthen this role, providing a critical spine for public and active transport and connecting the precinct to the regionally significant Centenary Trail.

Building on these strengths and informed by the Belconnen District Strategy (2022), which identifies Bruce as a key component of the broader National Canberra Innovation Corridor, the masterplan focuses on unlocking the precinct's potential through improved multimodal connectivity, enhanced walking and cycling networks, and stronger integration with regional active travel routes. It also prioritises more efficient land use through the rationalisation of dispersed car parking and better management of peak event demand. Together, these initiatives support stronger collaboration between institutions and enable integrated mixed-use development, positioning Bruce as a leading and connected innovation precinct in Canberra.

4 Principles and Objectives

The Bruce Precinct Strategic Maps Report provides Place principles, movement framework and urban design recommendations. Based on this, the following Transport Principles have been prepared to guide the design and delivery of the Bruce precinct.

4.1 Transport Principles

Transit Oriented Development First

Prioritise rapid transit, aligning destinations and public spaces within walkable catchments to maximise accessibility and patronage. Leverage transit to reinforce the precinct's role within the National Canberra Innovation Corridor.

Active Movement as the Default

Enable walking, cycling and micromobility as the most safe, convenient and attractive modes to move within and through the precinct. Transform movement corridors to link key anchors and public spaces by active modes.

Integrated Multimodal Network

Deliver a coordinated transport system where rapid transit, active travel, micromobility and vehicles operate efficiently as a network.

Hierarchy of Movement

Establish a clear movement hierarchy with active travel and transit prioritised in the core; vehicles accommodated at the periphery; and strategic access provided for key destinations (hospital, stadium, AIS).

Efficient Land Use and Parking Strategy

Consolidate car parking into strategically located facilities. Support land use optimisation and daily efficiency through coordinated parking and demand management.

Access for All

Ensure transport infrastructure is inclusive and intuitive. Provide safe and convenient access for all users regardless of age, ability, or travel mode.

Event and Peak Demand Management

Plan for major event conditions through peripheral parking strategies; managed access from arterial roads; and strong public transport provision to reduce car dependence. Prioritise high capacity, public transport modes to reduce congestion and support efficient, safe crowd movement.

Future Ready and Flexible Infrastructure

Design corridors and transport infrastructure to accommodate staged delivery, evolving technologies, and long term growth. Enable adaptability and intensification aligned with precinct ambition.

4.2 Transport Objectives

The transport objectives identify the specific desired outcomes of the transport system.

Strategic Connectivity

- x Connect the precinct to Belconnen, Canberra City and the broader region via high-quality rapid transit
- x Integrate key anchors (hospital, AIS, CIT, stadium) through direct, intuitive movement corridors
- x Strengthen links to surrounding neighbourhoods and regional trails (e.g. Centenary Trail)

Mode Shift

- x Achieve a meaningful shift toward public and active transport use
- x Reduce reliance on private vehicles for internal and event- related trips

Accessibility and Walkability

- x Enable daily internal trips to occur within a 5-10 minute walk
- x Deliver continuous, safe and attractive pedestrian and cycling routes
- x Provide high-quality connections between transit stops and destinations
- x Strengthen connections to regional networks including the Centenary Trail.

Network Efficiency

- x Provide logical, efficient access to key destinations and parking
- x Manage congestion during events and peak periods

Place and Amenity

- x Create vibrant, activated streets along transit corridors and green spines
- x Integrate transport infrastructure with public space and urban design outcomes
- x Enhance the experience of arrival to major destinations

Safety and Comfort

- x Deliver safe environments for all users, prioritising vulnerable modes
- x Provide clear wayfinding and intuitive navigation
- x Ensure comfort through shading, lighting and passive surveillance

Resilience and Adaptability

- x Support long term growth and intensification
- x Enable staged delivery aligned with development timing

4.3 Desired Outcomes

4.3.1 Road Network

To achieve the previously identified transport principles, the road network should aim to be structured to accommodate future development while supporting best practice transport planning practices of mode shift and reducing reliance on private vehicle for internal and event related trips. A clear movement hierarchy will concentrate higher traffic volumes on peripheral routes and limit through movements in core areas, ensuring efficient circulation while discouraging unnecessary car travel. Roads will be well integrated with the surrounding urban environment, with clear layouts, appropriate speed environments and reduced conflict points to support all users. The network will perform effectively during peak and event conditions through managed access, clear routing, and directing traffic to the periphery.

This approach will maintain reliable, strategic access to key destinations and parking facilities while reinforcing a road network that prioritises essential vehicle trips. In doing so, it will support sustainability outcomes, efficient network use and provide for long term growth and intensification, without resulting in unnecessary expansion or over-provision of road infrastructure.

4.3.2 Parking Provisions

Parking provision should support land use optimisation and best practice transport planning practices for a shift toward more sustainable transport modes by reducing reliance on private vehicles and encouraging greater uptake of public and active transport. It must also accommodate peak demand associated with major sporting and recreational events through a coordinated and efficient parking management approach. Particular consideration should be given to integrating the access and operational requirements of the North Canberra Hospital into the overall parking strategy. The precinct will rely on a combination of structured parking to accommodate future demand, supported by demand reduction measures to encourage alternative travel choices.

4.3.3 Active Travel Connections

The desired outcome to support best practice transport planning practices is to establish a people-focused movement environment supported by safe, convenient, and attractive walking, cycling, and micromobility networks that connect key anchors, public spaces and destinations across the precinct.

A highly permeable network will enable direct and legible routes, supported by comfortable, low stress environments with appropriate levels of separation, low speed conditions and safe crossings. High-quality amenity, including shade, active frontages, and well-designed public realm interfaces, will make active travel an appealing and intuitive choice for everyday and recreational trips.

A fully integrated multimodal system will enable seamless connections to rapid transit while ensuring active travel and micromobility operate efficiently as a cohesive network. This will be supported by appropriate end-of-trip facilities, secure bicycle parking, and infrastructure that accommodates a range of users and micromobility options.

The network will be underpinned by a clear movement hierarchy that prioritises active travel within the precinct core and maintains strategic access to key destinations such as the hospital, stadium, and AIS.

4.3.4 Public Transport

The desired outcome to align with best practice transport planning practices is to create a clear movement hierarchy that will prioritise public transport within the core of the precinct, while accommodating vehicles at the periphery and maintaining access to strategic destinations, including the hospital, stadium and AIS.

It will effectively respond to peak and event demand through managed access, peripheral parking and high-capacity public transport. Integration of existing game day bus services with future light rail will be critical to managing event surges, with a clear hierarchy that prioritises light rail as the primary high-capacity mode and positions bus services as a complementary secondary and local access network.

Overall, the network will provide intuitive and efficient access to destinations, manage congestion during peak and event conditions, and support long term growth and intensification. Its delivery will be flexible and staged, aligned with development timing and will reinforce a connected, resilient and future focused public transport system.

5 Bruce Master Plan Scenarios

Hatch has prepared two scenarios for the master plan, developed following the establishment of the ambition for the precinct. These scenarios explore alternative approaches to land use, connectivity, and movement within the area.

The following sections introduce each scenario from a transport perspective, highlighting their key features, network structure and approach to connectivity.


5.1 Scenario 1

Scenario 1 relocates the renewed GIO stadium to within the current CIT campus along with additional space for housing, mixed use development and public amenities. This establishes the key civic destinations along the rapid transit alignment along Haydon Drive and Belconnen Way.

Battye Street is extended east to form a new at-grade connection at Gungahin Drive.

A new pedestrian corridor is introduced linking Purdie Street to the North Canberra Hospital, while Leverrier Street is upgraded to an additional pedestrian corridor.

Figure 5-1 Scenario 1 Master Plan




5.2 Scenario 2

Scenario 2 presents a central rapid transit alignment forming a strong east-west link through the precinct. The Rapid transit corridor also serves to provide a vehicle connection running under Gungahlin Drive toward the City.

An extension of Masterman Street creating two new connections from Battye Street and North Canberra Hospital to increase the flexibility of vehicle movement through the precinct.

Upgrades consistent with Scenario 1 include the new pedestrian link from Purdie Street to North Canberra Hospital; pedestrianisation of Leverrier Street; and extension of Battye Street eastward.

Figure 5-2 Scenario 2 Master Plan



5.2.1 Master Plan Development Yield Assumptions

A preliminary assessment of development capacity within the master plan precinct has identified the following indicative development yields:

Residential Development:

- x Approximately 4,000 to 5,800 dwellings.

This range is understood to primarily reflect medium- to high-density residential development. However, the ultimate composition is expected to comprise a mix of land uses, including conventional apartments, student accommodation, aged care / seniors living, and other specialised housing typologies.

Commercial Development:

- x Approximately 30,000 to 43,000 square metres (sqm) of gross floor area (GFA).
This is anticipated to include a mix of retail, commercial office, innovation, and institutional uses, consistent with the strategic vision for a mixed-use precinct.

6 Road Network and Operation

6.1 Existing Road Network

6.1.1 Frontage Roads

The frontage roads located within and adjacent to the precinct are listed in the table below along with their classification (based on the ACT Active Travel Planning Tool).

Table 6-1 Frontage Road Classifications

Frontage Roads	Classification
Gungahlin Drive	Arterial
Belconnen Way	Arterial
Haydon Drive	Arterial
Ginninderra Drive	Arterial
Battye Street	Major Collector
Braybrooke Street	Minor Collector

Table 6-2 Internal Road Classifications

Internal Roads	Classification
Masterman Street	Local Access Road
Leverrier Street	Local Access Road
Purdie Street	Minor Collector

6.1.2 Road Connections

The following intersections provide access to the precinct and are present within the precinct:

- x Ginninderra Drive/Braybrooke Street – Signalised T-Intersection
- x Masterman Street/Braybrooke Street – Roundabout controlled T-Intersection
- x Masterman Street/Leverrier Street – Unsignalised T-Intersection
- x Braybrooke Street/Battye Street/Purdie Street – Unsignalised Cross Intersection
- x Battye Street/Leverrier Street – Unsignalised T-Intersection
- x Haydon Drive/Battye Street – Signalised Cross Intersection
- x Haydon Drive/Purdie Street – Unsignalised T-Intersection
- x Haydon Street/Belconnen Way – Signalised T-Intersection
- x Belconnen Way/Gungahlin Drive – Grade separated interchange
- x Ginninderra Drive / Agar Street – Unsignalised T-Intersection (only open during GIO Stadium events)

No vehicular access to the precinct is available directly from Gungahlin Drive.

6.1.3 Internal Road Network

There is an internal road network connecting the major destinations to their associated at-grade car parking and to the surrounding arterial roads at the perimeter of the precinct. Individual institutions are serviced by smaller internal access roads which primarily support movement within their own areas. The

movement within the site is characterised by vehicle travel needs from arterial roads to specific destinations. Local road network connectivity exists between the AIS, GIO Stadium and CIT. The North Canberra Hospital is however isolated from the remaining precinct network not having any local road network connections between itself and the other precinct land uses. Its access is solely to and from Haydon Drive.

The lack of through connections between institutions restricts the ability for traffic to distribute across the broader precinct, reducing overall network efficiency.

6.1.4 Existing Traffic Volumes

Weekday average daily traffic volumes (average of Tuesday, Wednesday, Thursday) by approach have been assessed at the signalised intersections providing access to the precinct and within the nearby vicinity. These volumes are identified in the table below. This was undertaken to understand typical demand on the intersection approaches. While a direct comparison of volumes is not possible between tables 5-3 and 5-4, the weekday average volumes do allow an understanding of the magnitude of traffic demand experienced on a typical weekday.

Table 6-3 Weekday Average Volumes

Weekday (Tues, Weds, Thurs) Average Volume by Approach				
Intersection	North	South	West	East
Belconnen Way/Haydon Drive	9,467	N/A	15,650	22,555
Battye Street/Haydon Drive	8,361	10,047	1325	5,794
Ginninderra Drive	N/A	6719	11036	10,883
Haydon Drive/Mary Potter Circuit	11,034	12,308	N/A	2,899
Jaeger Circuit/Haydon Drive	10,798	10,219	504	N/A
Ginninderra Drive/Braybrooke Street	N/A	4,682	12,874	10,919

In addition, it is recognised that GIO Stadium is a major event destination boasting a 25,000 seat capacity that attracts substantial crowds to the precinct on event days. According to the AUS Stadiums website, rugby league matches featuring the Canberra Raiders recorded crowds of 13,723 on Thursday 19 March 2026 and 17,457 on Sunday 29 March 2026.

To understand how these events influence traffic conditions, SCATS data from key signalised intersections within the precinct has been analysed and compared against typical (non-event) conditions. This assessment focuses on intersections that capture the primary access routes to the stadium precinct. The signalised intersections at Mary Potter Circuit have been excluded, as it is assumed that traffic using these approaches is already accounted for at the Haydon Drive/Battye Street and Haydon Drive/Belconnen Way intersections.

For the purpose of this analysis¹, traffic volumes have been assessed for the period of arrival before the event the period of the event and the departure period following the event. Arrival periods have been

¹ It is recognised that egress traffic may extend beyond this period however for the purposes of volume analysis at this time, this timeframe has been adopted.

assumed to occur between one hour and 15 minutes prior to the commencement of each event, while departure periods are considered to extend from game end to approximately 30 minutes post event.

These same time periods on a non-event day have been assessed to understand the impact that events have on the road network. Specifically, the Thursday 8:00pm event has been benchmarked against a typical alternate Thursday evening, while the Sunday 4:05pm event has been compared with a corresponding alternate Sunday afternoon period.

This approach provides a basis for quantifying the impact of event-related traffic and demonstrates the extent to which game days increase traffic volumes across the precinct relative to typical daily conditions.

The traffic volumes assessed are shown in the table below.

Event attendance records on AUS Stadiums, showed GIO Stadium held Rugby League games on the following days:

- x Thursday 19 March 2026 NRL Raiders vs Bulldogs @8:00pm
- x Sunday 29 March 2026 NRL Raiders vs Sharks @4.05pm

In comparison, two dates have been selected to compare traffic volumes for non-game days as follows:

- x Thursday 26th March 2026
- x Sunday 22nd March 2026

Table 6-4 Game Day Effect on Intersection Volumes

Intersection	Thursday			Sunday		
	Non-game day	Game Day	Volume %	Non-game day	Game Day	Volume %
Belconnen Way/Haydon Drive	1745	2583	48%	2429	3454	42%
Battye Street/Haydon Drive	957	2357	146%	1035	2359	128%
Ginninderra Drive	1214	1962	62%	1471	1760	20%
Jaeger Circuit/Haydon Drive	795	1775	123%	840	1982	136%
Ginninderra Drive/Braybrooke Street	1261	1764	40%	1459	1767	21%

All intersections saw substantial traffic volume increases on game days as expected, with the most notable increases at the Haydon Drive/Battye Street and Haydon Drive/Jaeger Circuit intersections. While the intersection of Ginninderra Drive / Braybrooke Street only experiences an increase of between 20 - 40%, it is noted that the Agar Street access point would be open allowing access into the precinct from the east prior to drivers reaching the Braybrooke Street intersection.

6.2 Master Plan Traffic Generation

6.2.1 Traffic Generation Considerations

The estimation of traffic generation has been undertaken having regard to the principles Integrated Transport Assessments principles, which emphasises the need to consider land use context, travel demand characteristics, and broader network impacts when assessing development-related traffic.

Key considerations include:

- x Variability in the ultimate development yield within the identified ranges; and
- x Variation in trip generation rates associated with different land use types and operational characteristics.

The assessment adopts an integrated, multi-modal perspective, recognising that traffic generation should not be considered solely in terms of vehicular demand, but in the context of the overall transport system, including public and active transport networks. This includes consideration of the importance of balancing network performance with broader community outcomes, including safety, accessibility, and environmental considerations.

In this context, designing the road network to accommodate a theoretical worst-case traffic scenario—particularly where such a scenario is unlikely to eventuate—may result in an over-provision of road capacity and infrastructure. This can contribute to induced demand, reinforcing private vehicle reliance and potentially undermining objectives to promote public and active transport modes. An overemphasis on vehicle capacity may also weaken the strategic and economic justification for investment in sustainable transport infrastructure.

To address the variability in development outcomes and associated traffic generation rates, a matrix of scenarios has been developed. This matrix considers a range of residential and commercial development combinations and their corresponding trip generation characteristics.

Residential

A range of daily traffic generation rates are defined by the ACT Government ranging from 6 vehicle movements per dwelling for medium density dwellings to 3.37 for high density dwellings within city and town centres. While the precinct does not sit within a 'town centre' the future intensification of this precinct and the collection of land uses could give rise to the consideration of adopting a rate more in line with the higher density rate rather than a more typical medium density rate. Further lower traffic generation rates are typically associated with alternate housing typologies such as student housing and aged care / seniors living. On this basis rates of 0.6 and 0.337 vehicle trips per dwelling have been used to form the limits of the ranges to be tested. These rates apply to both the AM and PM peak hours.

Table 6-5: Residential Peak Hour (AM and PM) Traffic Generation

Traffic Generation Rate Range (Peak Hour)	Land Use Scale Range (dwellings)	
	4,000	5,800
0.337 mvmts / dwelling (High Density)	1,348	1,955
0.6 mvmts / dwelling (Medium Density)	2,400	3,480
Average	2,296 vehicle movements	

Commercial

A range of traffic generation rates are applicable for a range of commercial use types that could be expected to make up an overall commercial offering across the precinct.

In this regard rates have been referenced from the TfNSW Guide to Transport Impact Assessments for retail shopping centres and office land uses as follows:

- x Retail:
 - o AM Peak: 2.25 vehicle movements per 100 sqm
 - o PM Peak: 4 vehicle movements per 100 sqm
- x Office
 - o AM Peak: 1.69 vehicle movements per 100 sqm
 - o PM Peak: 1.2 vehicle movements per 100 sqm

These would be expected to form the key range limits to be tested, however it should be noted that lower traffic generation rates such as 'business park' could be associated with innovation type uses should these be applicable in the future refinement of uses.

Table 6-6 Commercial AM Peak Hour Traffic Generation

Traffic Generation Rate Range (Peak Hour)	Land Use Scale Range (sqm)	
	30,000	43,000
1.69 mvmts / 100sqm (Office)	507	727
2.25 mvmts / 100sqm (Retail)	675	968
Average	719 vehicle movements	

Table 6-7 Commercial PM Peak Hour Traffic Generation

Traffic Generation Rate Range (Peak Hour)	Land Use Scale Range (sqm)	
	30,000	43,000
1.2 mvmts / 100sqm (Office)	360	516
4.0 mvmts / 100sqm (Retail)	1,200	1,720
Average	949 vehicle movements	

For the purposes of this assessment, an average traffic generation scenario has been adopted. This approach limits the influence of both:

- x Lower-bound scenarios, characterised by low development yield and low trip generation; and

- x Upper-bound scenarios, comprising high development yield combined with conservative (i.e. high) trip generation rates.

The adoption of an average scenario is considered appropriate for the following reasons:

- x Low likelihood of extreme scenarios:

The combination of maximum development yield and highest applicable trip generation rates is unlikely to represent a realistic development outcome.

- x Recognition of demand-moderating factors:

Higher-density, mixed-use precincts typically exhibit characteristics that reduce external vehicle trip generation, including:

- i) Mode shift to public and active transport;
- ii) Internal trip capture within the precinct; and
- iii) Trip chaining and shared travel behaviour.

Adopting high-end traffic generation scenarios do not adequately account for these moderating factors.

- x Alignment with sustainable transport objectives:

Austrorads guidance and associated research emphasise the importance of delivering transport systems that support sustainability outcomes and efficient network use, rather than encouraging unnecessary expansion of road capacity.

It is further relevant to apply typical arrival and departure splits to these generations as follows:

- x Residential:
 - o AM Peak – 20% Arrival / 80% Departure
 - o PM Peak – 60% Arrival / 40% Departure
- x Office:
 - o AM Peak – 90% Arrival / 10% Departure
 - o PM Peak – 10% Arrival / 90% Departure
- x Retail:
 - o AM Peak – 80% Arrival / 20% Departure
 - o PM Peak – 50% Arrival / 50% Departure

On this basis, Table 6-8 provides a summary of the average vehicle movements to be applied to the transport modelling to be discussing in subsequent section of this report.

Table 6-8 Master Plan Peak Hour Traffic Generation

Land Use	AM Peak		PM Peak	
	Arrival	Departure	Arrival	Departure
Residential	459	1,837	1,377	918
Commercial	606	113	387	562
Total	1,065	1,950	1,764	1,480

Having regard to the above the use of an average traffic generation scenario provides a balanced, realistic, and policy-aligned basis and robust basis for transport planning and network assessment. This approach reflects the likely range of development outcomes while appropriately accounting for the influence of mixed-use development, travel behaviour change, and sustainable transport objectives.

Accordingly, the adopted scenario supports the design of a transport network that is efficient, fit-for-purpose, and aligned with broader strategic planning principles, without resulting in unnecessary over-provision of road infrastructure.

6.2.2 Existing Precinct Land Use Development

In addition to the master plan development, it is understood that redevelopment and augmentation of existing facilities are expected across the precinct. The exact nature of these redevelopments has however not been made available at this time. As such the following assumptions have been made:

GIO Stadium

It has been assumed that the capacity of GIO Stadium will remain the same in the future. Notwithstanding the primary operating times of the stadium occur outside of the road network peak hours (and outside of the modelled periods), therefore should capacity changes eventuate they are unlikely to significantly impact the traffic modelling undertaken as part of this project.

North Canberra Hospital

It is understood that a significant redevelopment of the North Canberra Hospital is planned which includes more than 200 inpatient beds, a birth centre and at least 700 additional parking spaces.

Details of additional traffic generations associated with the redevelopment have not been made available to date, however the transport model provided by the ACT Government as part of this project includes the hospital development. This includes in the order of an additional 1,000 vehicle movements during the AM and PM peak hours (1,130 and 897 vehicle movements respectively).

These generations will be adopted for the purposes of modelling.

Australian Institute of Sport (AIS)

It is understood that an Architect has been engaged to investigate the redevelopment of the AIS which includes three major infrastructure components:

- x Multi-level athlete accommodation for up to 200 people
- x An indoor all-weather sports dome for year-round training
- x A new High Performance Testing and Training Centre equipped with state-of-the-art sports science and recovery facilities

Further details of the redevelopment have not been provided to date.

While the redevelopment will provide improved facilities and the potential greater year round use of these facilities it is not expected that these changes will result in significant changes to peak hour traffic generations.

Notwithstanding the future transport model provided by the ACT Government as part of this project includes a traffic increase between 2024 and 2041 in the order of 100 vehicle movements during the AM and PM peak hours (100 and 86 vehicle movements respectively) at the nodes serving the AIS.

These generations have been adopted for the purposes of modelling.

Canberra Institute of Technology (CIT)

Details of any redevelopment of the Canberra Institute of Technology have not been provided to date.

Notwithstanding the future transport model provided by the ACT Government as part of this project includes a traffic increase between 2024 and 2041 in the order of 100 vehicle movements during the AM and PM peak hours (86 and 111 vehicle movements respectively) at the nodes serving the CIT.

These generations have been adopted for the purposes of modelling.

6.3 Network Traffic Operation

6.3.1 Overview

The ACT Government (City and Environment Directorate) has provided Aimsun microsimulation models for the Bruce area which included the 2041 Project Case model (refer to as 2041 Reference Case henceforth for the purpose of this study) which included the background traffic growth to 2041 and traffic increases associated to the proposed North Canberra Hospital redevelopment as identified in Section 5.3.3 of this report. This model was updated and used to assess the impact of the Bruce Precinct Master Plan land use development on the existing network.

6.3.2 Assumptions

6.3.2.1 Direction distribution & demand profiling


The directional distribution of the additional demand has been based on the future demands (i.e. 2041 Reference Case) included in the original model representing the residential zones (Zone 323, 325, 326, 327 and 328) and commercial zones (Zone 332, 334A, 334B, 334C and 334D).

As the additional demand was developed on an hourly basis, demand profiling was applied to disaggregate the hourly demand into 15-minute intervals. The profiling factors were derived from the future demand patterns in the original model by calculating the percentage of hourly demand occurring within each 15-minute period.

6.3.2.2 Site Accesses


Two zones (Commercial and Residential) in the model representing the proposed Bruce Precinct Master Plan development are shown in Figure 6-1 below.

Figure 6-1 Existing commercial and residential zones



All trips generated by these zones allow access the surrounding road network via the six existing site access points. No additional site access connections or network capacity enhancements have been incorporated into this model. The location of the site access points serving the two development zones is shown in Figure 6-2.

Figure 6-2 Bruce Precinct zones and site accesses



6.3.2.3 Signal Optimisations

The signalised intersections in the original model were controlled using fixed-time signal plans. To accommodate the additional development traffic, the following intersections were converted to actuated signal control with associated detector function based on the existing signal phasing and operation.

Signal optimisation was undertaken concurrently to improve overall network performance and traffic efficiency:

x Battye Street / Haydon Drive Intersection

The existing fixed-time signal control plan at the Battye Street / Haydon Drive intersection was converted to an actuated control plan. For both the AM and PM scenarios, green time allocated to the northbound and southbound through movements was reduced and reassigned to the northbound right-turn movement to accommodate the increased right-turn demand generated by the development.

x Belconnen Way / Haydon Drive Intersection

To improve coordination with the Haydon Drive / Mary Potter Circuit intersection and facilitate more efficient discharge of inbound and outbound traffic, the cycle time at the Belconnen Way / Haydon Drive intersection was reduced to 90 seconds in the AM peak and 76 seconds in the PM peak, matching the cycle time adopted at the Haydon Drive / Mary Potter Circuit intersection.

In both the AM and PM peak periods, the southbound right-turn movement at Belconnen Way / Haydon Drive was coordinated with the southbound through movement at Haydon Drive / Mary Potter Circuit. Further the westbound right-turn movement from Haydon Drive to Belconnen

Way was coordinated with the northbound right-turn movement at from Haydon Drive to Mary Potter Circuit.

In addition, green time allocated to the eastbound and westbound through movements was reduced and reassigned to the westbound right-turn and southbound movements during both peak periods to accommodate the additional traffic demand.

x Haydon Drive / Mary Potter Circuit Intersection

In addition to the signal coordination measures implemented with the Belconnen Way / Haydon Drive intersection, the green time allocated to the northbound right-turn movement from Belconnen Way to Haydon Drive was increased during AM peak periods to accommodate the higher commuter demand associated with hospital traffic compared to the Reference Case scenario.

6.3.3 Model Outcome

In general, the Option Case scenario results in a deterioration of network performance compared to the Reference Case scenario due to the additional traffic demand associated with the Bruce Precinct.

The Belconnen Way / Haydon Drive intersection is already at/approaching capacity in the 2041 Reference Case, with competing demands from the right turn movement from Belconnen Way into Haydon Drive and the right turn from Haydon Drive onto Belconnen Way. Additional traffic to the network from the proposed Bruce Precinct developments further intensifies this existing bottleneck, while the ability for the network to accommodate and release this demand remains constrained.

Furthermore, the increased demand exacerbates congestion at the Haydon Drive / Mary Potter Circuit intersection, particularly in the southbound direction where right turn queues extends from Belconnen Way / Haydon Drive intersection, limiting throughput.

Capacity limitations at the unsignalised Battye Street / Braybrooke Street intersection also restrict traffic discharge, which in turn degrades overall network performance and limits the ability to accommodate/redistribute demand in the northern area of the network.

Table 6-9 compares the 15-minutes density plots for the Reference Case and Option Case in the AM period. The last 15 minutes of the previously reported (i.e. "Bruce Precinct Traffic Model Base year update" prepared by WSP dated 3 October 2025) peak hour have been selected which is also the critical 15 minutes of the peak hour simulation.

Table 6-9 Density plots of Reference Case and Option Case in AM period



Table 6-9 indicates:

- x Significant congestion is observed in the southbound direction at the Haydon Drive / Mary Potter Circuit intersection, driven by high through movement demand as well as throughput being limited by meeting the back of the right turn queues from Belconnen Way/Haydon Drive intersection. As a result, queues extend back to the Haydon Drive / University Drive intersection.
- x A significant queue is also observed on the southbound approach of the Battye Street / Braybrooke Street intersection, extending back towards the Ginninderra Drive and Gungahlin Drive northbound off-ramp. This queue also increases congestion at the Braybrooke Street / Ginninderra Drive intersection, particularly for the southbound left-turn movement from Ginninderra Drive to Braybrooke Street. The unsignalised nature of this intersection restricts traffic discharge and contributes to increased queuing.
- x Significant congestion is further observed at the Belconnen Way / Haydon Drive intersection in the westbound direction. Driven by high right-turn demand from Belconnen Way to Haydon Drive, the queue extends back to the Gungahlin Drive northbound off-ramp. The off-ramp queues extend beyond the storage length and impedes the mainline flows.

Table 6-10 compares the 15-minute density plots for the reference case and option case in the PM period.

Table 6-10 Density plots of Reference Case and Option Case in AM period




Table 6-10 indicates:

- x Similarly to the AM peak, significant congestion is observed in the southbound direction of the Haydon Drive / Mary Potter Circuit signalised intersection during the PM period compared to the Reference Case. Caused by high through movement demand and queues extending back to the Haydon Drive / Battye Street intersection. However it is noted that the southbound queues are shorter compared to the AM peak with queues extending back to Haydon Drive / College Street intersection.
- x Queuing on Braybrooke Street in the southbound direction is worse compared to the AM peak period which is stemming from Battye Street / Braybrooke Street unsignalised intersection. Increased traffic demand associated with the Bruce Precinct, combined with give-way restrictions, significantly constrains vehicle entry into Battye Street. This results in congestion at the Braybrooke Street / Ginninderra Drive intersection, with westbound queues on Ginninderra Drive extending back and affecting throughput on the northbound off-ramp.
- x A significant queue is observed at the westbound right-turn movement at the Belconnen Way / Haydon Drive intersection due to additional traffic demand, with queues extending back to the Caswell Drive northbound off-ramp.

The key network performance metrics are summarised in the Table 6-11 below for AM and PM peak.

Table 6-11 Network Statistics results

Statistics	2041 Reference Case	2041 Bruce Precinct Master Plan Option
AM Peak (7:30am – 9:30am)		
Total Vehicle Kilometres Travelled (VKT) – kms	130,005	118,080
Total Hours Travelled (VHT) – hours	4,136	6,107
Average Speed – km/hr	36.6	27.6
Average Delay (sec/km)	81.8	161.7
Average Distance Travelled (km/veh)	3.7	2.9
Average Travel Time (sec/km)	135	215
Total Number of Stops	60,502	93,893
Total Missed Turns	72	552
Total Traffic Demand (veh)	35,282	41,067
Latent Demand (veh)	72	3,317
Latent Demand (%)	0%	8%
PM Peak (04:15pm – 06:15pm)		
Total Vehicle Kilometres Travelled (VKT) – kms	133,965	118,300
Total Hours Travelled (VHT) – hours	3,698	5,796
Average Speed – km/hr	41.3	30.7
Average Delay (sec/km)	72.9	160.8
Average Distance Travelled (km/veh)	3.6	2.7
Average Travel Time (sec/km)	125.99	215
Total Number of Stops	37,970	82,677
Total Missed Turns	26	372
Total Traffic Demand (veh)	37,470	43,833
Latent Demand (veh)	97	4,286
Latent Demand (%)	0%	10%

In general, the network performance of the Bruce Precinct Master Plan Option is worse than that of the Reference Case due to the additional demand. The network performance results for the Reference Case and Option Case indicate the following key outcomes:

AM Peak

- x The additional traffic demand in the Option Case is expected to significantly increase congestion levels, with average speed decreasing by approximately 9 km/h (24%), average delay increasing by approximately 80 seconds (98%), and average travel time increasing by approximately 80 seconds (60%) compared to the Reference Case.
- x In addition, the total number of stops increases by 55%, while the total number of missed turns increases by 667% during the AM peak period in the Option Case compared to the Reference Case.

PM Peak

- x Similarly, under the PM peak scenario, the additional traffic demand in the Option Case is expected to significantly increase congestion levels, with average speed decreasing by approximately 10 km/h (26%), average delay increasing by approximately 88 seconds (121%), and average travel time increasing by approximately 89 seconds (71%) compared to the Reference Case.
- x In addition, the total number of stops increases by 118%, while the total number of missed turns increases by 1,331% during the PM peak period in the Option Case compared to the Reference Case.

6.3.4 Potential Mitigation Recommendations / Opportunities

The modelling, at this time undertaken on the existing road network, indicates that both demand side (achieving mode shift from private vehicle travel) and supply side (increasing road network capacity) measures need to be investigated. Further investigations and potential opportunities need to be explored at later stages of the project as follows:

- x Site access arrangements to encourage Ginninderra Drive rather than Haydon Drive and Belconnen Way.
- x Upgrade of the Belconnen Way/Haydon Drive intersection is recommended, particularly to increase the right turn capacity from Haydon Drive to Belconnen Way. Currently, only a single right turn lane is provided, and this movement is susceptible to queues extending back to adjacent intersection, limiting throughput. This queueing issue is also observed in 2041 Reference Case scenario.
- x Upgrade internal intersections, in particular the Battye Steet / Braybrook Street / Purdie Street intersection from priority controlled to a signalised intersection to manage internal congestion and pedestrian prioritisation.
- x Provide additional access to the precinct by opening Agar Street to Ginninderra Drive on non-event days and signalising the intersection. The intersection would be located approximately 280 m from the Ginninderra Drive interchange and 390 m from the existing signalised intersection at Ginninderra Drive/Braybrooke Street, indicating that there is adequate spacing from nearby signalised intersections. Given the constraints of the site this intersection represents one of the few opportunities to create additional access to the external road network. Appropriate internal road network configuration would be required to ensure that such an external access point aligns with the internal design of the precinct. The use of Agar Street could assist to collect traffic travelling around the eastern side of the site from future parking provisions rather than forcing these drivers all the way to Braybrooke Street, therefore potentially minimising intrusions into more sensitive areas where pedestrians are to be prioritised. Ultimately a new access to Agar Street would be subject to future modelling and integration with future precinct design.
- x Increase/encourage in travel model shift to reduce reliance on private vehicle trips.
- x Increase the mixed-use nature of the precinct to enhance the internal trip capture by active travel modes, thus reducing vehicle trip generation.

- x Consideration and feasibility for ACT Government investment in additional vehicle access under Gungahlin Drive to the south.

Any proposed road network mitigations identified within this report are indicative only at this early planning phase of the study, with further detailed investigations required in the subsequent planning processes. For example, the operation and capacity of the following roads and intersections should continue to be reviewed in subsequent assessments, identifying any opportunities for additional upgrades to minimise potential impacts with refinements to the proposed development yields and site access arrangements changes:

- o Haydon Drive
- o Belconnen Way
- o Ginninderra Drive
- o Braybrooke Street

The increase in event traffic volumes, albeit outside of typical road network peak periods, will further add to the traffic congestion in the precinct highlighting the need for further demand and supply side measures and specific event traffic management planning.


6.4 Master Plan Assessment

6.4.1 Network Configuration

The transport networks presented for each scenario explore alternative alignments of the Rapid Transit Boulevard which influences the broader movement framework across the precinct. While the alignments vary between scenarios, a representative cross section is proposed to illustrate the intended corridor design and functionality.

The rapid transit boulevard integrates capacity for future light rail (or dedicated bus lanes), with a single traffic lane in each direction, alongside planting, on-street parking, indented bus bays and an 8.0m wide promenade designed for community use. This indicative cross section, shown in Figure 6-3 below illustrates the intent of the transit boulevard for shared transport and public realm outcomes. Priority is given to public transport, while accommodating limited vehicle access through one traffic lane in each direction.

Figure 6-3 Example Transit Boulevard Section



Source: Hatch

The following sections describe the key differences between the scenarios in terms of the east-west and north-south corridors, the distribution of movement between the precinct core and its periphery, the balance between internal connectivity and through-connections to surrounding areas, and the location and function of access points into the precinct.

6.4.2 Scenario 1

Scenario 1 establishes a clear distinction between the precinct core and its periphery. The Rapid Transit Boulevard is positioned along the edge of the precinct, running along Haydon Drive and Belconnen Way. This draws public transport to the perimeter while reinforcing the route as the primary movement corridor.

In contrast, the core of the precinct accommodates vehicles along Battye Street while prioritising pedestrian movement along north-south internal connections via Leverrier Street and an active travel link between the stadium, CIT and North Canberra Hospital. While these destinations benefit from improved connection, AIS is more separated and relies on arterial connections via Ginninderra Drive and Haydon Drive.

East west connectivity is anchored by Battye Street and its potential extension to Gungahlin Drive, forming the main internal spine and a key-through connection to surrounding suburbs. The additional precinct access point increases direct connectivity to the precinct but has the potential to affect the operation of Gungahlin Drive due to the existing interchanges being already at minimum spacing.

Geometric and physical spacing constraints may affect the feasibility of an additional Gungahlin Drive interchange, particularly in respect to providing adequate ramp tapers and storage length. Weaving of traffic especially during event days will put pressure on north-south traffic flow on Gungahlin Drive. While this additional access point could be anticipated to be predominantly used for providing additional event capacity, it is more suitable to provide event specific access solutions rather than introducing a permanent new interchange. Further investigation of such an access point would need to be explored through modelling, geometric design and government engagement.

Traffic modelling undertaken in the Belconnen to City Transitway report indicates a reduction in Haydon Drive operation will require improvements, in particular, recommending corridor widening near Belconnen Way and Haydon Drive to support interim operations and the potential longer term transition to light rail. Further modelling of the Transit Boulevard configuration would be required along Haydon

Drive to understand its impact more fully, along with the densification of the Bruce Precinct. However, based on the Belconnen to City Transitway modelling it would be expected that a reduction in general traffic capacity along Haydon Drive would need to be accepted as an inherent consequence of any upgrade to Transitway proposals.

In summary, Scenario 1 aligns public transport with the arterial through traffic route however separating its connection with land use attractors and increases potential conflicts for pedestrians to access future public transport.

6.4.3 Scenario 2

Scenario 2 is structured to prioritise a transit and active travel focused precinct core, with general vehicle movement shifted to the periphery. The rapid transit boulevard runs centrally through the precinct along the Battye Street alignment, passing beneath Gungahlin Drive and bringing public transport directly to the centre. This reinforces the core as people focused environment, while existing arterial routes accommodate vehicle movement around the edges.

Opportunity exists to for private vehicle movements to be combined with the Rapid Transit Boulevard providing an eastern precinct connection across (under) Gungahlin Drive through the Bruce Ridge Nature Reserve to Dryandra Street and Fairfax Street.

East-west connectivity is defined by this central rapid transit boulevard, which forms the primary spine of movement and a strong connection to outer suburbs. Private vehicle movement is distributed to the surrounding arterial network, supporting reduced traffic within the core and aligning with the ambition for internal movement to be dominated by public transport and active modes.

North-south movement within the precinct is provided via the pedestrianised Leverrier Street and the extended Masterman Street along the eastern edge, which functions as an important internal link. This corridor supports access between major destinations, including North Canberra Hospital, the CIT campus and GIO Stadium while also keeping this traffic off Gungahlin Drive. The extension of Masterman Street seeks to provide opportunity for greater dispersal and flexibility of traffic movements across the precinct.

Overall, under this scenario, the network emphasises internal connectivity through high quality public transport and pedestrian links, while maintaining broader accessibility via the peripheral road network.

7 Parking Provisions

7.1 Existing Conditions

Parking across the precinct is predominantly provided through a combination of large at-grade car parks and select parking buildings associated with individual institutions. Provision and management vary with a mix of free and controlled parking supporting staff, students, visitors and event based demand.

While this approach accommodates existing needs, it results in a dispersed and land-intensive parking pattern, with limited coordination across the precinct. The following outlines the current parking arrangements for key institutions.

North Canberra Hospital

The hospital campus has a free 24/hr multi-storey car park on the Mary Potter Circuit approximately 100m from the main hospital entrance. Across the campus, enforced parking conditions and time limits apply to the at grade uncovered car park opposite the main hospital entrance, and short term parking outside the Marian Building and Emergency Department.

Accessible parking is available around the campus and within the multi storey car park.

CIT Bruce Campus

A large at grade uncovered car park is available at the Bruce campus, free for all students. Accessible parking is provided outside various buildings.

GIO Stadium

Designated car parks are available on the east and west sides of the stadium catering to visitors for \$10 per vehicle. VIP, corporate and disabled parking is also provided. Additionally, GIO stadium directs visitors to additional parking at CIT and the University of Canberra about 10 or 20 minutes' walk respectively.

AIS

Three parking areas are provided for visitors, with two areas accommodating buses. Separate staff and athlete parking is also available. Accessible parking is available close to the main entrances.

7.2 Master Plan Parking Generation

In a similar manner to traffic generation above, an estimate the future parking needs of the contemplated master plan uses has been undertaken in the following.

Residential

Adopting a rate of 1 car parking space per dwelling would result in a demand in the order of 4,000 to 5,800 resident spaces.

Commercial

A range of parking generation rates are applicable for a range of commercial use types that could be expected to make up an overall commercial offering across the precinct.

In this regard car parking expectations have been referenced from the ACT Government Technical Specification (Commercial Zone) for retail shop and office land uses as follows:

- x Retail (Shop): 5 spaces per 100 sqm
- x Office: 2 spaces per 100 sqm

These would be expected to form the key range limits to be tested.

Table 7-1 Commercial Parking Generation

Traffic Generation Rate Range (Peak Hour)	Land Use Scale Range (sqm)	
	30,000	43,000
2 spaces / 100sqm (Office)	600	860
5 spaces / 100sqm (Shop)	1500	2150
Average	1,278 spaces	

Table 7-1 indicates an average commercial parking expectation of 1,278 spaces. This average has been obtained by adopting the mid point of a range of parking rate and land use scale outcomes associated with potential future office and retail (shop) commercial uses.

Combined with future resident parking a total additional parking requirement in the order of 5,000 – 7,000 spaces could be required above that currently provided within the precinct.

The above figures are considered to represent an upper bound scenario, noting that a significant proportion of demand is likely to be accommodated through shared and walk-up trips between future residential development and adjacent retail/commercial uses. This internalisation of trips is expected to reduce the overall parking demand compared to a conventional, stand-alone land use approach.

The internalisation of trips is influenced by a number of factors known as the 7D's. These factors represent those that most influence travel in the urban development process:

- x Density of population and employment
- x Diversity of different land uses
- x Design of street network and development
- x Destination accessibility
- x Distance to mass transit (rail/light rail)
- x Demand management
- x Demographics

Many of these elements are imbedded in the evolution of the Bruce Precinct Master Plan and will therefore contribute to a change in future transport characteristics.

It is important to put in place a forward-looking parking strategy at the outset which balances travel and parking needs now, however, has the flexibility to evolve in the future as densification of a mixed-use activity centre occurs. Parking controls and future planning provisions and ownership of parking assets play a role in creating a future flexibility for change.

Notwithstanding this, the provision and distribution of parking will require careful calibration in future development stages, particularly in response to the congestion issues identified in the traffic assessment. Parking supply should be aligned with network capacity constraints to avoid exacerbating peak period pressures on the surrounding road network.

It is important to recognise that parking provision is a key determinant of private vehicle travel behaviour. As such, parking supply may need to be deliberately moderated to discourage unnecessary car use, mitigate congestion impacts, and support a shift toward more sustainable transport modes. An oversupply of parking can induce additional vehicle trips, undermining broader transport and land use objectives.

In this context, opportunities to maximise the efficiency and utilisation of parking should be actively pursued. This includes, but is not limited to, shared parking arrangements across complementary land uses with differing peak demand profiles, flexible allocation strategies, and potential integration with demand management measures. These approaches will help to optimise parking provision across the precinct and avoid unnecessary capital investment in underutilised parking infrastructure, while still maintaining appropriate levels of accessibility for residents, workers, and visitors.

These measures will need to be documented via a development framework at future planning stages. This framework should establish a clear and adaptive guide for parking provision, appropriate to the evolving needs of each development phase as the precinct densifies, and is structured to support sustainable mode shift outcomes.

As densification progresses, subsequent development will be expected to provide adjusted parking supply ratios that reflect changing demand and transport priorities. Notwithstanding this longer-term transition, current requirements must be addressed through immediate provisions embedded within the same development framework, ensuring that the existing deficit in public transport accessibility and active travel infrastructure is appropriately mitigated in the interim.

As a whole, each phase of development should respond to precinct-wide requirements, allowing benefits to be progressively unlocked and realised through a cumulative approach toward the desired long-term outcomes.

7.3 Master Plan Assessment

The revitalisation of the precinct is expected to place increased pressure on parking provision, driven by new development, including additional dwellings and intensified land uses. This demand is shaped by an established expectation of parking availability in the ACT, where private vehicle use remains dominant.

Without intervention, this is likely to result in increased demand for on-site parking and continued reliance on dispersed at-grade supply.

To respond effectively, future parking provision should be carefully managed and optimised, with a greater proportion of demand accommodated through high-capacity public transport, including rapid transit, and improved active travel connections. This will be critical to reducing parking demand long term, supporting more efficient land use, and avoiding the expansion of land intensive parking.

7.4 Scenario 1

Scenario 1 identifies, two multi-storey parking structures. The first parking structure is located adjacent to the relocated stadium and is accessed from Haydon Drive. It supports both hospital staff and stadium demand while keeping vehicles out of the precinct core and utilising existing parking land. The second parking structure is located on mixed-use development land and is proximate to the proposed access to Gungahlin Drive.

Together, these multi-storey parking structures respond to event-related congestion and reduce excess traffic movements through the precinct. They provide the ability to supplement and provide shared parking for hospital staff and stadium events, while accommodating increased traffic associated with development intensification and the anticipated needs of institutions, residents, and visitors within the precinct.

Overall, the approach delivers shared benefits across the wider precinct and a range of stakeholders, noting that considerations of investment, ownership and ongoing operation and maintenance of these structures have not been addressed at this stage.

7.5 Scenario 2

Scenario 2 identifies two multi-storey parking structures. The first parking structure involves upgrading existing parking land adjacent to the CIT campus to a multi-storey facility, accessed from Haydon Drive.

The second parking structure is located adjacent to the rapid transit boulevard near AIS. It is accessed from the extension of Masterman Street and the proposed connection under Gungahlin Drive. This utilises existing parking land. This peripheral parking approach reduces the need for vehicles to enter the core of the precinct, supporting event day traffic management.

Collectively, these multi-storey parking structures support the precinct's evolving access and parking demands by accommodating increased traffic associated with development intensification. By locating parking at the periphery, they reduce the need for vehicles to enter the precinct core, enabling the epicentre to be prioritised for active travel.

8 Active Travel Connections

8.1 Existing Conditions

8.1.1 Path Networks

A series of active travel routes exist through the precinct comprising both Principal Routes and Main Routes.


The Main Route provides connection along the northern side of Battye Street from Haydon Drive to GIO Stadium travelling onwards under Gungahlin Drive continuing through the Bruce Ridge Nature Reserve to Fairfax Street. This route facilitates a number of crossing points of local roads through the use of raised pedestrian zebra crossing treatments. As precinct intensification increases vehicle volumes, the route will experience heightened interaction between pedestrians, cyclists and traffic, reinforcing the need for safe crossing design and effective traffic management. This existing route network will become increasingly valuable, offering users an attractive alternative to private vehicle use which enables a shift toward more active travel modes while maintaining the continuous connection between Belconnen Town Centre and the Canberra CBD.

A further main route is provided from Ginninderra Drive providing connections from the north to the GIO Stadium linking with the path network that continues south under Gungahlin Drive.

The Main Route through the site provides a connection to the Centenary Trail, a 138 km shared use trail which runs through urban and rural Canberra and passes through the Bruce precinct. This provides an important corridor for walking, running and cycling. Connection of this trail is provided under Gungahlin Drive to the Bruce Ridge Nature Reserve. To the west the path crosses Haydon Drive in an uncontrolled manner linking with the Gossan Hill Nature Reserve. Kerb ramps are provided however formal crossing control is not.

These routes are shown in Figure 8-1.

Figure 8-1 Existing Active Travel Routes



Source: ACT Active Travel Planning Tool

Several local streets support cycling in lower-speed environments such as Braybrooke Street and Leverrier Street which function as bicycle friendly streets, these include:


- x Traffic calming measures, raised crossings, and signage to encourage slower vehicle speeds particularly through the AIS area
- x Raised zebra crossings e.g. on Braybrooke near Battye Street intersection that further support pedestrian safety

Battye Street includes sections of shared path infrastructure known as the Belconnen Bikeway, supporting both pedestrians and cyclists and connecting to the main entrance of the GIO stadium.

8.1.2 Bike and Ride

Transport Canberra provides a network of Bike and Ride facilities that support multimodal travel by enabling seamless connections between cycling and bus or light rail services. One such facility is located within the precinct at the CIT Bruce campus, with several additional sites in the surrounding area. These facilities allow cyclists to securely park their bikes before transferring to other modes, supporting convenient access into and through the precinct.

Figure 8-2 Transport Canberra Bike and Ride Services



Source: Transport Canberra

8.1.3 Pedestrian Access

Around Mary Potter Circuit, footpaths and crossings are provided to support access to bus services, improving connections to public transport, however footpath provision across the precinct is inconsistent, for example Braybrooke Street has a footpath on one side only which many local roads have limited or no formal footpath provision.

8.1.4 Recreational Routes

The precinct does contain an extensive network of informal trails and mountain bike tracks through surrounding green open space areas, which provide strong recreational opportunities, however they are not well integrated with key destinations for everyday transport use.

8.1.5 Micromobility

GIO Stadium promotes an e-scooter share scheme run by Transport Canberra and ACT Government. The scheme allows visitors to the stadium to ride e-scooters directly from Belconnen to Civil and back, with drop off points provided on Leverrier Street in front of the AIS arena.

8.2 Master Plan Assessment

8.2.1 Scenario 1

Scenario 1 drives significant land use and movement change by transforming Haydon Drive into an active mixed-use rapid transit boulevard, forming a key north–south spine along the precinct. This corridor utilises the socialised space along Haydon Drive to connect major anchors, including the hospital, Fern Hill residential neighbourhoods, and Radford College. It strengthens connectivity by facilitating links to Jaeger Circuit and Purdie Street, as well as pedestrian connections into Aranda to the southwest. While access to the AIS and the precinct core would rely on the internal local movement network, the boulevard enhances broader connectivity by linking into the existing Centenary Trail, improving access to surrounding nature reserves. The scenario prioritises active travel through upgrades to the north–south route while retaining the east–west recreational trail, supporting a framework for a more integrated and walkable movement network across the precinct.

While links to regional and recreational routes are provided, connectivity at a local level is more limited, necessitating a more comprehensive internal movement network. Scenario 1 has a clearer separation between commuter movement along the rapid transit boulevard and connections to the broader precinct, which results in weaker direct integration, particularly in relation to the pedestrianised Leverrier Street.

Enhancements such as the development of Battye Street are required to establish continuous and legible active travel infrastructure, ensuring both effective connections between key destinations and also improving overall network permeability.

8.2.2 Scenario 2

Scenario 2 establishes a regionally significant active transit corridor along an east–west boulevard, forming the primary movement spine of the precinct. This is complemented by north–south links that transition into pedestrian-focused street environments, creating a fine-grained and people-oriented network. This scenario builds on and expands the existing Centenary Trail, strengthening connections to recreation and surrounding open space. Permeability is enhanced through new, upgraded and extended connections, including Leverrier Street and additional thoroughfares—particularly in the northern section—at intervals of up to 100 metres, supporting a highly walkable urban form. Active travel is prioritised along the east–west transit boulevard through activated frontages, with movement and land use focused around the precinct epicentre and integrated with key recreational connections.

With large traffic volumes arriving via rapid transit and from the CIT parking centre, strong active travel connections—particularly between Battye Street and the CIT—are critical to ensure efficient and safe movement. Access to the hospital is closely tied to station placement, which must be optimised to maintain walkable distances. Similarly, access to other key destinations may require complementary measures such as bicycle depots or a loop bus to support last-mile connectivity.

In this scenario, the direct stadium link to the light rail caters for event traffic, reducing the need for additional active travel measures to manage game day surges.

9 Public Transport


9.1 Existing Conditions

The existing public transport network comprises a mix of regular, event and school bus services, each serving a distinct function in providing coverage, managing commuter and event related demand and supporting access to destinations across the precinct and wider network.

9.1.1 Regular Bus Services

The precinct is serviced by a network of local bus routes that provide connections between the major interchanges in nearby areas. Rapid routes R2, R3, R4, R5, and R6 form the primary public transport spine, operating at a high frequency between Belconnen Interchange and City Interchange. These routes cater to the majority of commuter demand and provide access to key employment, retail and activity centres.

Figure 9-1 Routes R2, R3, R4, R5, R6



Source: Transport Canberra


Route 9 supplements this network by linking Belconnen Interchange to Dickson Interchange, supporting cross-town movement and improving connectivity to the inner north.

Figure 9-2 Route R9



At a more local level, route 901 operates as a circulator service from Belconnen Interchange through the Bruce precinct. This route provides important access to major local institutions, including North Canberra Hospital and CIT campus, facilitating shorter intra-precinct trips and improving overall accessibility within the area.

Figure 9-3 Route 901



9.1.2 School Bus Services

Dedicated school bus routes also form an important component of the existing network. Routes 1055 and 1012 operate along Haydon Drive and Belconnen Way, connecting residential areas with schools across the surrounding precincts. These services are focused on peak school travel periods and contribute to increased demand along these corridors, particularly during morning and afternoon peaks.

Figure 9-4 Route 1055





Figure 9-5 Route 2012



9.1.3 Game Day Bus Services

GIO Stadium provides free game day bus services for ACT Brumbies and Canberra Raiders matches. These services depart from major interchanges across Canberra and drop off and pick up passengers at the East Gate of GIO Stadium, adjacent to the East car park.

Services are scheduled with staggered arrivals ahead of the match, and return trips commence approximately 20 minutes after the game concludes. These buses are free of charge and operated by CDC Canberra.

For regular, non-event bus services, there are no stops located close to the stadium. Passengers typically arrive at bus stops on the western side of the precinct and walk on average 15 minutes to reach the venue.

9.1.4 Additional Services

Additional transport services are available to support ACT residents who may have difficulty accessing conventional public transport. These include community bus services operating Monday to Friday, offering flexible, pre-booked routes tailored to individual passenger needs.

Flexible bus services are also provided for eligible users, including those aged over 70, people with mobility challenges, or those unable to access regular bus services.

In addition, an Aboriginal and Torres Strait Islander transport program operates during weekday business hours, providing targeted bus services for individuals who do not have access to standard public transport options.

The presence of these services highlights the importance of delivering an accessible and inclusive transport network that effectively connects and supports residents across the region.

9.1.5 Key observations

Overall, the public transport network exhibits a strong radial structure centred on Belconnen Interchange, with high frequency rapid routes providing efficient connections City Interchange and supporting regional travel demand. Local routes such as the 901 complement this structure by servicing key destinations within the Bruce precinct and enabling accessibility.

School services further reinforce the importance of key corridors such as Haydon Drive and Belconnen Way, highlighting concentrated peak-period movements associated with education facilities.

While the existing network provides a solid foundation of coverage and connectivity, it is primarily oriented towards connecting outer suburbs and passing through Bruce. This suggests opportunities to enhance cross-precinct and local connectivity, as well as to better integrate key institutions and activity centres within the broader transport network.

A summary of the available bus routes is in Table 9-1 below along with maps showing the routes as they relate to the Bruce precinct.

Table 9-1 Bus Routes Passing through Precinct

Route Number	Route	Roads through Precinct
R2	Belconnen to Fyshwick Via City and Railway Station	Belconnen Way, Haydon Drive
R3	Belconnen to Airport Via City and Russell	Belconnen Way, Haydon Drive
R4	Tuggeranong to Belconnen Via Woden and City	Belconnen Way, Haydon Drive
R5	Belconnen to Lanyon Via ANU, City, Woden and Erindale	Belconnen Way, Haydon Drive
R6	Belconnen to Woden Via ANU, City and Kingston	Belconnen Way, Haydon Drive
R9	Belconnen to Watson via Bruce and Dickson	Braybrooke Street, Battye Street
901	Belconnen to North Canberra Hospital Via UC Hospital and CIT Bruce	Mary Potter Circuit, Haydon Drive, Purdie Street, Vowels Crescent
Route Number	Schools	Roads through Precinct
1055	Aranda Primary School, Canberra High School	Braybrooke Street, Battye Street
2012	St Clare's/St Edmund's College	Belconnen Way, Haydon Drive

9.2 Light Rail/Transit Corridor


The existing light rail network comprises the north-south Route R1, which connects Alinga Street in the City to Gungahlin Place. Operated by Canberra Metro Operations, the line provides a high-frequency rapid transit service, with services running approximately every 5 to 15 minutes across weekdays, weekends, and public holidays. All stops along the corridor are fully accessible.

While the current light rail alignment does not directly service Bruce, indirect access is available via connecting bus service Route 9 from Dickson Interchange.

9.2.1 Future Expansion

Transport Canberra has planned network expansion which will extend light rail to additional destinations, following a hub-and-spoke model centred on the City, with new corridors radiating outward to serve surrounding areas.

Figure 9-6 Moving Canberra 2019-2045 Integrated Transport Strategy: Current Planned Network




Source: Moving Canberra 2019-2045 Integrated Transport Strategy: Current Planned Network

A feasibility study undertaken by WSP in March 2026 investigated opportunities to enhance transit performance along Haydon Drive and eastern portion of Belconnen Way through targeted interventions that address the short to medium term needs. The existing connections of this corridor are currently constrained, and infrastructure limitations affect the efficiency and reliability of public transport. The study developed two tactical kerbside treatment options described below.

Option 1 - Bus Lanes

This option proposes the repurposing of existing kerbside lanes as dedicated bus lanes, maximising public transport priority and improving service reliability along the corridor.

Figure 9-7 Belconnen to City Transitway Option 1- Bus Lanes




Source: WSP Belconnen to City Transitway Feasibility Report, March 2026

Option 2 - T2 Lanes

Option 2 introduces high occupancy vehicle (T2) lanes, allowing access for buses and vehicles with two or more occupants. This option provides a balance between enhanced transit priority and broader network efficiency, with the potential to reduce impacts on general traffic while still supporting mode shift.

Figure 9-8 Belconnen to City Transitway Option 2- T2 Lanes



Source: WSP Belconnen to City Transitway Feasibility Report, March 2026

Both options are designed to operate within the existing road corridor and avoid the need for major widening or reconstruction works, enabling cost effective and immediately deliverable improvements to transit performance. From a strategic perspective, while Option 2 represents a lower cost and potentially less disruptive measure, it is less aligned with the corridor's long term mass transit objectives. Through a multi-criteria assessment, Option 1 has therefore been identified as the preferred short term intervention for the Belconnen to City transitway corridor, as it provides stronger immediate public transport benefits while maintaining compatibility with the future transition to light rail.

9.3 Master Plan Assessment

9.3.1 Scenario 1

Under Scenario 1, no new or modified bus services are specifically identified at this time. Instead, the focus is on enabling infrastructure, including the provision of new bus stops and an upgraded bus corridor integrated within the proposed rapid transit boulevard. This approach is intended to support direct and convenient public transport access to the future mixed-use development, as well as key destinations such as the stadium and hospital.

With the stadium centrally located and new mixed-use development, housing and public amenity surrounding the precinct, these key destinations will be anchored by the rapid transit corridor along Haydon Drive.

The overall strategy maintains a strong emphasis on the future delivery of high-capacity light rail as the primary mode, with bus services playing a complementary role in providing local access and network coverage.

Under Scenario 1, the rapid transit alignment is oriented to serve key civic destinations, including the hospital, northern education precincts, and the proposed stadium location (noting the relocation of the stadium is required to place it within a reasonable walking catchment of the Transit Corridor). The corridor follows Haydon Drive and Belconnen Way, providing strong regional connectivity and direct access to these high-demand uses. This aligns with the short and medium term transitway alignments contained within the recent feasibility study prepared by the ACT Government. While this configuration supports efficient movement to major destinations, the perimeter alignment limits coverage over the core of the precinct. In particular, it introduces a degree of separation from the AIS campus, reducing the directness of connections and potentially constraining accessibility within this area. As a result, while the alignment performs well at a strategic level, additional measures may be required to strengthen internal connectivity and ensure equitable access across the precinct.

Figure 9-9 below shows a 400m catchment along the transit corridor representing the coverage of the public transport network available to the precinct and surrounding areas.

Figure 9-9 Scenario 1 Public Transport Catchment 400m



9.3.2 Scenario 2

Under Scenario 2, there are no new or modified bus routes proposed at this time, with the public transport strategy relying on a new east–west light rail corridor along Battye Street, supported by active travel, to address future transport demand. In this context, bus services are not identified as a primary intervention, reflecting a shift toward high-capacity rapid transit as the dominant mode. The concept design only identifies the potential for a loop bus service, subject to patronage and demand analysis, to support the light rail corridor by providing local circulation and informing stop placement and coverage. Overall, bus services are envisaged as a secondary, adaptable layer, complementing the light rail network rather than driving network structure.

The rapid transit alignment along Battye Street, extending to Gungahlin Drive, establishes a regionally significant and highly active transit corridor through the precinct. This alignment strengthens east–west connectivity and creates a strong public transport spine that integrates with the wider network. With the stadium retained in its existing location, the corridor is well positioned to support event-related demand,

providing direct and efficient access for large passenger volumes. It also enhances connectivity to key destinations within the precinct, including the heart of the AIS campus, the CIT campus, and other education facilities to the north. Overall, the alignment supports both daily and peak demand, reinforcing the role of rapid transit as the primary mode while improving accessibility across major activity centres. This alignment is however at the expense of the North Canberra Hospital which would fall outside of a 400m walking catchment of the Rapid Transit route.

Figure 9-10 Scenario 2 Public Transport Catchment 400m



10 Loading and Servicing

10.1 Objectives

Loading and servicing will support the operational needs of the precinct while maintaining a high standard of liveability and accommodating future intensification, with detailed requirements to be refined through subsequent planning and design stages.

Servicing and waste management functions will be integrated to enable safe and efficient access for service and collection vehicles while minimising conflicts with pedestrians, cyclists, general traffic and the primary movement network, particularly within high activity areas. The design and operation of these functions will also protect the visual and acoustic amenity of the public realm.

The strategy should aim to respond to the anticipated operational demands of key destinations, including GIO Stadium, ensuring event related servicing is accommodated without compromising visitor experience. To deliver best practice transport planning practices it will align with the precinct's road network principles to support efficient operation without driving unnecessary road expansion or over provision of infrastructure and remain adaptable to emerging delivery technologies and evolving servicing models.


10.2 Key Considerations

10.2.1 Existing and Planned Routes

The strategy will respond to the existing and planned transport network, including key orbital links and freight routes identified in the ACT Freight Strategy. Servicing access will align with these corridors to support efficient regional movement while minimising impacts on local streets.

The precincts bordering arterial roads all currently allow B-Double access as part of the National Heavy Vehicle Register. The future orbital network is shown in Figure 10-1 below.

Figure 10-1 Freight Current and Planned Network



Source: ACT Transport Strategy 2020

10.2.2 Land Use

A diverse mix of residential, health, education and event uses generates varied servicing and waste management needs. Future residential growth will increase demand, requiring solutions that protect amenity, while major destinations such as the hospital, stadium and CIT campus will require tailored servicing approaches to support their specific operational needs.

10.2.3 Vehicle Types and Frequency

The precinct must accommodate a range of vehicle types, including waste trucks, delivery vans, removalists, trades, emergency services and event related loading vehicles. Increasing small vehicle parcel deliveries will require flexible, short term loading spaces near residential areas and local centres, with servicing managed to balance efficiency and minimise disruption.

10.2.4 Access and Circulation

Servicing access will be designed to support safe and efficient operations by:

- x Accommodating MRV and where required HRV and Semi Trailer turning paths
- x Minimising reversing in public streets
- x Maintaining clear sightlines and pedestrian priority
- x Integrating with the street hierarchy and traffic calming measures

11 Future Transport

11.1 Objectives

Future transport in the precinct should integrate land use and movement to support a mixed-use environment, prioritising active and public transport while maintaining efficient, managed vehicle access. A forward looking approach will enable the adoption of emerging technologies and innovative mobility solutions, ensuring the network remains accessible, resilient, and aligned with broader ACT objectives.

The infrastructure should be designed to support long term growth and intensification, with corridors capable of staged delivery aligned to development timing. The network will remain flexible and adaptable to evolving technologies and travel behaviours while maintaining efficient and sustainable performance.

11.2 Key Considerations

11.2.1 Emerging Technologies and Multimodal Integration

The Bruce Master Plan Precinct will support the integration of emerging transport technologies while reinforcing a coordinated, multimodal network. This includes expanding EV charging infrastructure, integrating real-time transport information systems, and enabling mobility-as-a-service (MaaS) platforms. Future-ready design will accommodate autonomous and connected vehicle technologies, supported by data driven traffic and demand management tools, particularly around event related surges. These advancements will be integrated with strong active and public transport connectivity, alongside strategically located mobility hubs, to enable seamless interchange, efficient travel across the precinct, and support of the travel mode hierarchy.

11.2.2 Monitoring and Adaptability

The future transport strategy will remain flexible and responsive to changing conditions. This will include ongoing monitoring of travel patterns and mode share and periodic review of infrastructure performance and capacity. The approach will allow for adaptation to evolving technologies, user behaviours, and policy settings, including the use of pilot programs and temporary interventions.

11.2.3 Sustainability and Behaviour Change

Encouraging sustainable travel behaviour will be central to the precinct vision, particularly given its role as a major destination for events, education, and health services. Travel demand management will be critical to reducing reliance on private vehicles, with measures tailored to these uses, such as event travel planning, and incentives for staff, students, patients and visitors to choose active and public transport.

Flexible working and study arrangements, personalised travel planning, and targeted initiatives during major events will further support mode shift. Community engagement and education can further reinforce sustainable travel choices and support a transition to less car dependent travel patterns.

12 Summary and Conclusions

The precinct as envisioned, will generate diverse travel demands, including commuter, student, visitor and major event travel, requiring a coordinated and integrated multimodal transport system. Anchored by the North Canberra Hospital, CIT, AIS and GIO Stadium, and supported by strong regional connections via surrounding arterial roads, the precinct is well positioned to leverage a future rapid transit corridor as the primary spine for movement and connectivity.

Road Network and Operation

Traffic modelling indicates that both demand-side and supply-side measures would be required to support efficient operation of the road network. In general, the Master Plan Option Case results in a deterioration and breakdown of network performance compared to the 2041 Reference Case, driven by the additional traffic demand associated with the Bruce Master Plan.

Increasing mode shift to public and active transport, along with stronger internal trip capture, will therefore be critical to reducing reliance on private vehicles. However, targeted upgrades to intersections, site access arrangements, and local circulation will also be needed to address key constraints. Event traffic will place additional pressure on the road network, reinforcing the need for dedicated event management strategies.

All mitigation measures remain indicative and require further investigation. Overall, an integrated approach combining travel demand management, land use optimisation, and targeted infrastructure improvements will be essential to support efficient network performance without widespread road expansion.

Scenarios Assessment

Both Master Plan Scenario 1 and Scenario 2 align strongly with the desired transport outcomes by establishing a clear movement hierarchy and integrating land use with transport. High-capacity rapid transit forms the backbone of the public transport network, supported by active travel connections and a road network that accommodates vehicles primarily at the periphery. This approach supports mode shift, improves access to key destinations, and limits unnecessary vehicle movement within central areas, creating a more efficient and people focused environment.

Next Planning and Design Stages

Further work is required to resolve gaps in connectivity and network performance. This includes refining road access points; intersection performance; improving the permeability and coverage of active travel networks; and strengthening integration between rapid transit and local connections to support first/last mile access. Ensuring equitable access to key destinations including AIS and the North Canberra Hospital, and developing effective event management strategies will be critical. These refinements will help ensure all modes operate efficiently under daily and peak conditions while maximising mode shift.

A parking framework strategy will be important to deliver a parking plan that provides for the current precinct needs and allows for evolution in provision and management in the future to support the future precinct needs.

Loading, servicing and future transport strategies should be further developed through the next stages of planning and design. These should support efficient servicing within the road network while

minimising conflicts with pedestrians and cyclists and protecting public realm amenity. A flexible, future focused approach should also support emerging technologies, integrated multimodal networks and staged delivery to ensure adaptability as the precinct grows.

Overall, the master plan provides a strong foundation for a coordinated, multimodal transport system that supports growth, enhances accessibility, and promotes sustainable travel, positioning Bruce as a high value and integrated mixed-use precinct.



Stantec is a global leader in sustainable engineering, architecture, and environmental consulting. The diverse perspectives of our partners and interested parties drive us to think beyond what's previously been done on critical issues like climate change, digital transformation, and future-proofing our cities and infrastructure. We innovate at the intersection of community, creativity, and client relationships to advance communities everywhere, so that together we can redefine what's possible.

 Stantec Australia Pty Ltd stantec.com	
--	--

B

APPENDIX

BRUCE PRECINCT MASTERPLAN

DESIGNING WITH COUNTRY
FINAL DESIGN REPORT | MAY 2026



Aboriginal and Torres Strait Islander peoples should be aware that this document may contain voices, images, names of people who have passed away.

We acknowledge the Cultural Landscape that we are working upon, and the Ngunnawal and Ngambri peoples as the Traditional Custodians of the Country where the Bruce Precinct Masterplan is located.

We acknowledge all First Nations people and their ongoing connection to Culture, lands and waters and their valuable contribution to the community. We recognise, acknowledge, and extend our respects to many others who have custodial obligations for Country who have been connected to Country for many generations, including their Elders past, present and emerging.



Yerrabingin is an Aboriginal owned design studio. At the core of our work is custodianship and care for Country. Our expertise encompasses Designing with Country, landscape architecture and urban design. We are recognised for our collaborative design approach, bringing together Cultural knowledge and sustainable design solutions. We walk together to amplify the powerful language of Country for the betterment of our collective future.

We are guided by the inspiration of Country, the stories and knowledge a place contains and gifts us. We acknowledge its contribution to wellbeing both mental and physical, providing a refuge and safe place to learn and share.

Our Vision is that sensing and caring for Country is something that transcends Cultural differences and highlights the many values that are similar across the Cultures of our contemporary communities, supporting a socially inclusive, resilient, and innovative community based on, and honouring the wisdom and kinship of all Cultures, captured through the lens of custodianship.




Figure.1 - Nearmap. 2026. Aerial photo of site location - Suburb of Bruce.

TABLE OF CONTENTS

Glossary Key Words and Terms	6	COLLECT / EMPATHISE	NOURISH / ITERATE	Design Development 2 S S R U W X Q L W L H V \$ F U R V V W K H 6 L W H	41
Executive Summary	7	Introduction Project Overview	13 Ideation Development Workshop ' L V F X V V L R Q D Q G) L Q G L Q J V	22 Project Legacy Future of Connecting with Country at Bruce	42
CONNECTING WITH COUNTRY DESIGN		Ngunnawal and Ngambri Country Place in Country	14 TEND / SUSTAIN	Figures List	43
	9	Elements of Country Understanding Place	15 Community Feedback Session ' L V F X V V L R Q D Q G) L Q G L Q J V	25 Figures List + References	44
	10	Living Connection between People and Place 6 L W H 6 S H F L 4 F 2 S S R U W X Q L W L H V	16 Design Development Elements of Country Exploration	29	
	11	PLANT / COLLABORATE	Elements of Country Site Exploration	30	
		Collaborative Design Methodology Process and Progress	18 Design Development ' : & 2 S S R U W X Q L W L H V	31	
		How Might We? 2 X U ' H V L J Q & K D O O H Q J H	19 Design Development Country as our Teacher	32	
		Collaborative Design Workshop : R U N V K R S 2 Y H U Y L H Z	20 Design Development Country as our Healer	35	
			Design Development Country as our Legacy	38	

DOCUMENT NAME	REV	DATE
0240YB_BPM_REP_DRF	A	20 05 2026
0240YB_BPM_REP_DRF	B	16 07 2026

AUTHORSHIP

At Yerrabingin, we acknowledge and respect the Traditional Custodians and ancestors of the lands we walk across.

The terms First Nations, Indigenous and Aboriginal are used interchangeably throughout this report. When referring to a specific group or individual, nation or language group names are used.

Yerrabingin abide by the Australian Indigenous cultural and intellectual property (ICIP) guidance in the GANSW (2023) Connecting with Country Framework, which notes that ICIP refers to ‘the rights that Aboriginal people have to protect their cultural heritage, traditional knowledge and cultural expression... It is the product of generations of accumulated knowledge and expression, and reflects the unique history, values and traditions of Aboriginal people. Care and respect is always needed, to ensure cultural knowledge is not appropriated or interpreted without permission from the Aboriginal Community to which this knowledge belongs’ (p.23). The cultural knowledge included in this report can only be used for the purpose it was provided, to share background information to the project team. In this and future stages of the project, Aboriginal people need to be recognised as the ongoing guardians of this knowledge and how it is used, and engaged on the use of knowledge for design.

Permission should be sought from copyright holders if the report is published with the graphic material or the graphic material is used for other purposes.

Cover Image - Yerrabingin. 2026. Image of Woodland Country.



Figure.2 - Yerrabingin. 2026. Freshwater Lakes.

GLOSSARY

Key Words and Terms

To better understand key terms referenced throughout the report, please consult the glossary.	7KH IROORZLQJ WHUPV GHULYH IURP WKLHRS, RABs (Registered Aboriginal Parties), LALC (Land Councils), and local Aboriginal members of the community.	• Aboriginal Community: Within the context of Sydney, the Aboriginal Community refers to a range of peoples that often include Traditional Custodians, Knowledge Holders, Elders, RABs (Registered Aboriginal Parties), LALC (Land Councils), and local Aboriginal members of the community.	• Design: Design is both a process and an outcome - a way of engaging together to deliver information to a proposal, challenge, or outcome.	• Peoples: Peoples is used in plural to reference First Nations peoples, recognising that there are many Nations and many groups.
Connecting with Country Framework.	W KH QDWXUDO HQYLURQPHQW –W LQFOENGAGED TOGETHER TO DELIVER INFORMATION TO A PROPOSAL, CHALLENGE, OR OUTCOME.	• Built Environment: Understood as distinct from encompasses cities and towns, neighbourhoods, parks, roads, buildings, infrastructure, and utilities like water and electricity.	• Engagement: A process whereby a particular group is engaged together to deliver information to a proposal, challenge, or outcome.	• Place: A social and physical concept, a physical setting, people and communities. In this sense, place can describe town is a place, and a building can be a place.
	Country includes Earth, Waters, Sky and our Non-human Kin. It encompasses tangible and intangible aspects, knowledge and cultural practices, belonging and identity, well-being and relationships. People are inhabited by Country and Country inhabits us.		• First Nations: Is an encompassing term that ceded. This term is growing in preference for First Nations Australians but may also be interchanged with Aboriginal and Indigenous in this report.	• Practices:
			Knowledge: \$ERULJLQDO NQRZOHGJH FRPHV IURP GL•HUHQW nations and family groups. Knowledge is multifaceted and enabling them to comprehend the world, make informed	

EXECUTIVE SUMMARY

This document has been developed by Yerrabingin following our Collaborative Design process, in partnership with the Federal and ACT Government, Hatch, Stantec, and local Indigenous Community members through the Collaborative Workshop and project meetings. The purpose of this document is to share the findings and design recommendations from our collaborative design process.

The opening section - Connecting with Country Design - provides an introduction to how we understand Country and what Country means to us.

The second section - Contextual Analysis - includes a project overview and provides a recap of the scope and intent of the Bruce Precinct Masterplan development. We then introduce the site’s Place in Ngunnawal and Ngambri Country and explore the context of the site within the wider Cultural landscape.

The third section - Collaborative Design - firstly recounts our design methodology and then shares a summary of each step in the process, including the How Might We Session and the Collaborative Workshop. For each engagement, we include a description of the engagement and a summary of the sessions.

The fourth section - Ideation Development - recounts the targeted design team workshop and captures the tangible design outcomes created based on the activities of the Collaborative Workshop. We explore the Community Driven Design Opportunities developed following the Collaborative Design Workshops - *Country as our Teacher, Country as our Healer, and Country as our Legacy*. Where we discuss how each Opportunity could be activated at the site and throughout the project.

The final section, Toward Final Design - Bruce Precinct Masterplan, summarises our Community Feedback Session on the project and presents the refined Designing with Country opportunities, completing the current engagement process for the Bruce Precinct Masterplan.



Figure.3 - Kroll, M. 2021. *Pinker Pond Bruce* - site image.



CONNECTING WITH COUNTRY DESIGN

INTRODUCTION TO CWC DESIGN

Beginning with Country

*Country is our mother, our teacher,
our library and our kin; it sustains
us, inspires us and surrounds us. The
experience of Country is both individual
and collective, both new and familiar.
From her we learn, share and flourish.
Continuing to care for Country is central
to our being and our identity.*

Christian Hampson, Yerrabingin

Country reaches into and across the earth and into the sky. The unique and distinctive elements of Country are connected, and open to everyone. They are the connective tissue, the interstices, the flow between Water, Earth, Sky, our Non-Human Kin, and ourselves. In this way, we are part of the system of Country and have a responsibility to future generations. Our actions must always be Country positive.

Country-centric

We inhabit and are inhabited by Country. To inhabit Country and connect with Country is to be grounded in the landscape and to practice the cultural knowledge stored within it. This encourages physical and emotional wellbeing for people and Country.

The innate symbiosis of being connected to Country moves us into being Eco or Country centric, rather than being Human centric. This connection and position in relation to Country is a central component of Aboriginal people’s ideology. It is a cultural value that places humans within the ecological and landscape system, not as dominators but as caretakers and custodians. This function requires constant interaction and observation, being tuned in to reactive requirements and response.




Figure.4 - Yerrabingin. 2026. We inhabit and are inhabited by Country.

YERRABINGIN PILLARS

What guides our work

Yerrabingin has four pillars that guide our work. The pillars link together our values, Country, Culture, professional practice, and Cultural practice.

Each pillar is one part of the larger task of caring for Country. Together they contribute to a holistic commitment to care and design for Country. The pillars are Custodianship, Innovation, Legacy and Regeneration. As a key civic offering to Canberra, the Bruce Precinct Masterplan development provides an opportunity to deliver outcomes across all four pillars.

-  **Innovation**
-  **Custodianship**
-  **Regeneration**
-  **Legacy**

Innovation

We are a transformative force for change. We draw on ancient wisdom, guided by ecological kinship, to share the powerful voice of Country and disrupt conventional systems and perceptions. Inspired by Country, we take a holistic view, centring creativity, adaptation and reciprocity. Our work propels us towards a collective future that considers the life of all kin.

Regeneration

We deeply understand the connections between all things and work towards balance. We overcome limitations in conventional design thinking by centring the needs of Country and all kin. We create places for people to experience the many ways Country sustains and holds them, to connect them with their role in the system of their place. Learning from Country, we take a long-term view, with the knowledge that health and healing will come, given the right conditions of care.

Custodianship

We are custodians of Country. We draw on Cultural knowledge to advocate and care for Country. It is our responsibility to improve the health of Country and our diverse communities through our work. In our role as designers, we listen deeply to the needs of Country and walk together with our partners to foster connection. Country benefits and grows in our care.

Legacy

Our works sits at the intersection of Culture and design. We are industry leaders in collaborative design, bringing together First Nations communities and built environment professionals for an enduring conversation. By introducing people to Country, we transform the experience of belonging and connection to place in Australia. We show people that if we care for Country, she will care for us in return. Healthy Country and connected communities are our legacy.

YERRABINGIN COLLABORATIVE DESIGN METHODOLOGY

2XU 'HVLJQ 3URFHVV

Our design methodology is informed by components of design thinking, user-centred design and Connecting with Country design disciplines to create our Country-focused, FRODERUDWLYH GHVLJQ DSSURDFK

Country-focused :KDW VHWV XV DSDUW IURP FRQYHQWLRQDO Design Methodology Stages design is our recognition of the interconnection of &RXQWU\ ZLWK KXPDQ DFWLYLW\ DQG RXU \PSHUDWLYH WR collect)LUVW ZH FROOHFW E\ HPSPDWKLVLQJ ZLWK RXU SURMHFW partners and with Country. We gather ideas, inspiration, (PSDWKHWLF REVHUYDWLRQ DQG FRQVLGHUDWLRQ RI &RXQWU\ LV facts, desires, research and limitations. This occurs in the central to our approach. GLVFRYHU\ DQG +RZ OLJKW :H VHVVLRQ

The outcome of our Country-focused approach is that Country is designed for and cared for, allowing Country to FDUH DQG SURYLGH IRU IXWXUH JHQHUDWLRQV

Collaborative Inspired by the natural processes of fostering and sustaining life on Country, our design methodology follows D\FOLFDO FRODERUDWLYH SURFHVV RXWFRPHV SHODQV SQRXVLJQ and tend.

The Connecting with Country Design Report – Final contributes to the Tend / Sustain stage in our PHWKRGORJ\ –Q WKLW VWDJH ZH WHQG D\RXVXSWMQDEOH DQG KDYH RQJRLQJ SRVLWLYH RXWFRPHV IRU ensuring that the partnerships and outcomes created DUH VXVWDLQDEOH DQG KDYH RQJRLQJ SRVLWLYH RXWFRPHV for Country and communities. A key part of tending is

HPSPDWKLVLQJ ZKLFK NHHS WKH F\FOH PRYLQJ :H WHQG LQ feedback sessions with the Community and our ongoing partnerships and new custodial relations created through RXU SURMHFW 2XU RXWSXW RI WKLW VWDJH LV WKLW 'HVLJQLQJ ZLWK Country Design Report - Final.

Collect -)LUVW ZH FROOHFW E\ HPSPDWKLVLQJ ZLWK RXU SURMHFW partners and with Country. We gather ideas, inspiration, GHUDWLRQ RI &RXQWU\ LV facts, desires, research and limitations. This occurs in the GLVFRYHU\ DQG +RZ OLJKW :H VHVVLRQ

Plant - After understanding the design challenge, we plant. &RODERUDWLYH GHVLJQ ZRUNVKRSV LQYROYH)LUVW 1DWLRQV SHRSOHV DQG WKH ZLGHU WHDP LQYROYHG WR JHQHUDWH GLYHUVH DQG LQQRYDWLYH GHVLJQ VROXWLRQV

Nourish -)ROORZLQJ WKH FRODERUDWLYH GHVLJQ VHVVLRQV ZH QRXULVK WKURXJK LWHUDWLRQ :H VKDUH WKH FRODERUDWLYH RXWFRPHV SHODQV SQRXVLJQ VROXWLRQV DQG FRQFHSWV further based on feedback.

Tend - Finally, we tend to our creation. We tend by ensuring that the partnerships and outcomes created DUH VXVWDLQDEOH DQG KDYH RQJRLQJ SRVLWLYH RXWFRPHV IRU Country and communities.




Figure.5 - Yerrabingin. 2026. Methodology Process.



COLLECT / EMPATHISE

CONTEXTUAL ANALYSIS

INTRODUCTION

Project Overview

The Bruce Precinct Masterplan is being developed to provide a coordinated framework for land use, infrastructure, and investment across a significant section of the suburb of Bruce in the ACT. Led by the Department of Infrastructure, Transport, Regional Development, Communications, Sports and the Arts (DITRDCA) in partnership with the ACT Government, the plan seeks to integrate existing campuses, including the Australian Institute of Sport, North Canberra Hospital, and CIT Bruce, into a cohesive and sustainable scheme. It will address key considerations such as movement networks, environmental resilience, and institutional integration, ensuring the Precinct is welcoming and fit for purpose for all users (SLA, 2025).

As part of this project, Hatch and Stantec have engaged Yerrabingin to undertake the Designing with Country scope.



Figure.6 - Canberra Daily. n.d. The 'Pink Lake' in Bruce with its blanket of native aquatic fern *Azolla Pinnata* covering the water.

NGUNNAWAL AND NGAMBRI COUNTRY

Place in Country

The Bruce Precinct site is on Ngunnawal and Ngambri Country in the north of Canberra. The landscape, with mountain ranges to the south and west, the Murrumbidge River running to the west and the open area of Lake George leading towards the coast, makes it a connecting place between surrounding regions.

Country in this region is rich in biodiversity and Cultural heritage. The high-altitude climate and the landscape crossed by rivers and creeks between rolling plains, hills, and mountain ranges support diverse ecological systems. When looking at Country close to the Bruce Precinct site, we see Ginninderra Creek and the surrounding catchment, the ridgelines and hills of Bruce Ridge Nature Reserve and O’Conner Ridge as important landscape features.

The Ginninderra Creek catchment covers the northwest of the Canberra region. It sits to the east of the Murrumbidgee River, which it feeds. Ginninderra Creek travels from Mulligans Flat, to the northeast of Bruce though the suburbs of northern Canberra to Lake Ginninderra at Belconnen, directly to the west of Bruce.

One small waterway connected to the Ginninderra Catchment crosses the master plan site. Pinker and Duck ponds, at the north of the site, feed from a storm water channel that runs through the Kaleen from the Giralang Wetlands. Ephemeral waterways stream south from the ponds in wet periods, to reach beside the AIS Residence of Champions building.



Figure.7 - Gininderra Catchment. n.d. Ginninderra Creek in northern Canberra. Figure.8 - Australian Wildlife Conservatory. n.d. Gang-gang Cockatoos.

ELEMENTS OF COUNTRY

Understanding Place

As part of our place analysis, we explore the unique nature of Country where the project is located and use this analysis to consider opportunities to design with Country in this place.

A way to think and learn about Country is to consider the interconnected elements that we inhabit and can relate to: Move with Country, Water Country, Sky Country, Non-Human Kin Country, Deep Country and Wind Country.

Acknowledging these elements, their place and the processes they are involved in provides an opportunity to celebrate the all-encompassing nature of these elements, their infinite reach into and across the earth and the sky. This allows us to look at different parts of Country and the role they play in an overall system.

“Country as made up of a series of interconnected elements that come together to form the environmental, Cultural and social system of a place. To design with Country is to design with the elements of Country.” - Yerrabingin



Move with Country



Water Country



Sky Country



Non-Human Kin Country



Deep Country



Wind Country

LIVING CONNECTION BETWEEN PEOPLE AND PLACE

Site Specific Opportunities

Despite the transformations that have occurred across Ngunnawal and Ngambri Country since European settlement, the deep systems of Country remain intact. This truth must guide the way we imagine new development in Bruce.

Country is a living network of relationships between water, wind, soil, plants, animals, and people that sustains life and Culture. Designing with Country means recognising these interconnections and working with them to create places that endure.

Bruce sits within a landscape of ridgelines, river flats and ephemeral waterways, connected to Ginninderra Creek and adjacent to Bruce Ridge Nature Reserve in an ecological corridor linking Black Mountain, O'Connor Ridge and the Molonglo River. These connections are not incidental, they are vital pathways for species and stories. They invite us to see the precinct as part of a continuum of this important Cultural landscape of Country.

The Place in Country Research Report identified several site-specific opportunities, including:

- Consideration of seasonal cycles, water management and plant use offers a guide for sustainable design.
- Strengthen links, regenerate landscapes and foster custodianship.
- Restore ecological health and Cultural connections.
- Community planting days with local custodians.
- Consider water management across the precinct through permeable surfaces, vegetated swales and wetlands.
- Movement networks that reflect Country's patterns, creating paths that follow natural contours and connect people to reserves and Cultural sites.



Figure.9 - Sitchu. n.d. Exploring Tidbinbilla Nature Reserve.



PLANT / COLLABORATE

COLLABORATIVE DESIGN

COLLABORATIVE DESIGN METHODOLOGY

Process and Progress

As described above in the introduction to Yerrabingin’s Collaborative Design Methodology, our design process is made up of four stages, Collect / Empathise, Plant / Collaborate, Nourish / Iterate and Tend / Sustain. Each project is unique, and we tailor our design approach within each of the four stages for each project.

Our Progress

We have completed the Collect / Empathise, Plant / Collaborate, Nourish / Iterate and Tend / Sustain stages and this report summarises our findings across each stage and our final design recommendations to answer our design challenge, the How Might We statement.

The graphic to the right shows the Collaborative Design Methodology for this project including each deliverable within our scope.




Figure.10 - Yerrabingin. 2026. BPM DwC project timeline.

HOW MIGHT WE?

Our Design Challenge

When: Wednesday 3rd December, 2026

Who:

- DITRDSCA
- SLA
- Yerrabingin
- Hatch

In the How Might We Session, we worked with the project team to learn as much as we could about the aims of the project and to introduce the design team to our process. We created the following How Might We statement for the project:

How Might this Masterplan create a legacy, guided by Country and cared for across generations?

We use the How Might We statement to understand the design team’s thoughts on the project users, impact, connection and value. By gaining as much information as we can from the beginning, we aim to ensure that we can direct the project more accurately and generate more impact. This helps in defining our design challenge.

Activity One Outcomes

This activity sparked curiosity by looking at the Superb Parrot to ask questions. Responses fell into three themes: behavioural, environmental and physiological.

Activity Two Outcomes

This activity revealed participants value a universally accessible, exemplary place grounded in deep connections to Country and context. Where Cultural continuity, connection to the elements, and holistic health and wellbeing is central to the vision. Seeking to evoke strong feelings of tranquility, inspiration, and pride.

Activity Three Outcomes

This activity highlighted a collective ambition for the project to drive long-term social, Cultural and ecological regeneration. Grounded in First Nations knowledge and custodianship, it seeks to embed place-specific innovation across wellbeing, planning and ecology. Together, these approaches aim to foster deep belonging and active participation, while establishing a resilient, adaptive legacy into the future.

Closing Themes

Participants envisioned a place that regenerates people and Country through connection, inclusivity and wellbeing, guided by First Nations knowledge. It is seen as a unique, place-led precinct integrating health, Culture and ecology, with a long-term goal of being self-sustaining, resilient and community-led for generations to come.

ACTIVITY ONE - SPARKING CURIOSITY



ACTIVITY TWO - INVESTIGATING NEEDS



Figure.11 - Yerrabingin. 2025. Collection of images from the online How Might We? session.

COLLABORATIVE DESIGN WORKSHOP

Workshop Overview

The Collaborative Design Workshops were split across three sessions; 2 x Ngunnawal and 1 x Ngambri. The aim of the workshops was to introduce Community to the project, get to know each other, and understand the needs of Country. Community members and representatives from the project team took part in targeted activities that explored Designing with Country opportunities for the Bruce Precinct Masterplan.

When: 4th, 5th & 13th February, 2026
Where: Canberra Museum and Gallery, ACT
Who:

- 49 x Local Aboriginal community members:
 - 12 x Ngunnawal Group 1
 - 17 x Ngunnawal Group 2
 - 20 x Ngambri Group
- 8 x Project team representatives (DITRDSCA, SLA, Stantec, North Canberra Hospital, and Hatch)
- 5 x Yerrabingin staff [redacted]

Each session began with an Acknowledgement of Country or Welcome to Country, followed by introductions and an outline of our roles within the project. The presentation commenced with Yerrabingin providing an overview of Designing with Country and the engagement process guiding this work.

This was followed by a project overview which was shared by Hatch and Yerrabingin, situating ourselves on Country and where the Bruce Precinct Masterplan sits in its context. As part of the project overview, we had a virtual site tour followed by four key workshop activities, including:

Warm-Up Activity: Looking after Country

Participants individually brainstormed their thoughts and feelings around the idea of looking after Country, considering:

- *What does caring for Country mean to them?*

Activity 01: Elements of Country

Using a large map and printed site images, participants located Yerrabingin’s Elements of Country within the site,

considering the following prompts:

- *What elements are unique to this site?*
- *What elements might need protection or care here?*
- *What elements might be missing or need to be added back here for a healthy Country?*

Activity 02: Yerrabingin Pillars

Building on what was shared and mapped before, participants brainstormed which of the four Yerrabingin Pillars (Regeneration, Custodianship, Legacy and Innovation), might apply to the Bruce Precinct project, considering:

- *What do these pillars mean to you and your group?*
- *What could they mean for Country, Community and Culture here?*
- *How could they guide the design of this Masterplan?*

Closing Activity: Final Vision

Participants took a moment to reflect on the sessions activities, then using a small piece of paper- they were encouraged to complete the sentence below:

- *In the future, this masterplan should _____, _____ and _____ !*



Figure.12 - Yerrabingin. 2026. Collaborative workshop team photo - Ngunnawal Group 2.



NOURISH / ITERATE

IDEATION DEVELOPMENT

IDEATION DEVELOPMENT WORKSHOP

Discussion and Findings

When: Friday 13th March, 2026

Who:

- DITRDSCA
- SLA
- Yerrabingin
- Hatch

Following the Collaborative Design Workshop with Aboriginal community members and the project team, we held an Ideation Development Workshop with the project team to review the summary of outcomes of the Collaborative Design Workshop and investigate ideation opportunities, expand thinking, understand constraints and limitations and together develop the next stages of the Connecting with Country design work. The discussion and findings under the topic areas explored is as follows:

Country as our Teacher

- Welcome to Country signage and acknowledgement upon arrival / at entry points across the precinct.
- Opportunity for connection to Sky Country and education on First Nations astronomy.
- Education around native species, medicinal species, their Cultural uses and healing properties.

- Implementation of a ‘bush school’ program within the precinct and education on Cultural bushfire burning.
- Use of traditional Cultural practices on site. Seasonal fire management, land management practices and plant cultivation.
- Wall art potential to educate about textures, colours and patterns of Non-human Kin species.
- Whispers and nods to outlines of significant mountain ranges visible from site - Black Mountain, etc.
- Cultural interpretation into paving/architecture to spark curiosity and subtly educate on local kin and context.
- A rotating series of ‘story walls’, these could be added to by patients, students, community and athletes.
- HortiCulture - opportunities for a first nations business to lead the Bruce Precinct public space maintenance contract and collaborate with hortiCulture school on regeneration projects and test new ways to bring back old practices.
- Education through play elements and waterplay.



Figure.13 - Yerrabingin. 2026. Image from our online Ideation Workshop.

Discussion and Findings

Country as our Healer

- First Nations advisory group to inform how hospital renewal can be more welcoming and embrace the green open space around the hospital as a healing and recovery space for patients.
- Training for all hospital employees regarding Culturally sensitive medical practices.
- Research into the endemic pink algae and its purifying properties - learning new ways to heal Country.
- Connection to water in everyday healing spaces.
- Therapeutic views from hospital into soft landscape.
- Ensuring little moments within nature to rest, recharge and reflect. Either for individuals or in groups.
- Shaded outdoor spaces that can facilitate outdoor rest and respite.
- Co-design of gathering spaces - ensure that they are providing the right amenities to support a gathering space.
- Immersive walking trails that touch the landscape 'lightly', lifting you up into the tree canopies.

Country as our Legacy

- Community involvement in art strategy across the precinct.
- Using facades and surfaces to tell stories and subtly educate- ensuring legacy is continued.
- Acknowledgement of nationally recognised First Nations leaders and sporting figures.
- Indigenous nursery that grows bush tucker food, medicine, native plants that help threatened species.
- Name the trails and walks after famous Aboriginal athletes, doctors, professors. etc.
- Ensuring First Nations community contribute to design development.
- Truth telling - acknowledging unrecognised athletes and support for First Nations athletes. NRL Reconciliation Action Plan - 2026 All Stars Documentary.
- Indigenous learning circles, and other campus learning spaces precedents - Swinburne Campus VIC.
- Invite students from Tafe, staff from hospital, staff from sports precinct to partake in regeneration and planting days - instill Custodianship.



Figure.14 - Yerrabingin. 2026. Collection of images from our online Ideation Workshop.



TEND / SUSTAIN

TOWARD FINAL DESIGN - BRUCE PRECINCT MASTERPLAN

Discussion and Findings

When: 5th & 6th May, 2026

- 14 x Local Aboriginal community members
- 2 x Project team representatives (Hatch)
- 4 x Yerrabingin staff [REDACTED]

Using the three Designing with Country outcomes as a framework, the following points capture the feedback from each of the sessions:

Row	Black Bar Length (approx. %)	Grey Bar Length (approx. %)
1	75	5
2	85	0
3	90	5
4	100	0
5	95	5
6	30	0
7	90	10
8	25	5
9	100	0
10	55	5
11	90	10
12	90	0
13	100	0
14	90	10
15	80	10
16	70	10
17	100	0

A horizontal bar chart with two rows of bars. The top row represents 'Total' respondents, and the bottom row represents 'U.S. only' respondents. Each row has two bars: a dark grey bar for 'Men' and a light grey bar for 'Women'. The x-axis represents the percentage of respondents, ranging from 0 to 100. The y-axis lists age groups: 18-29, 30-49, 50-69, and 70+.

Age Group	Gender	Total (%)	U.S. only (%)
18-29	Men	~95	~95
	Women	~95	~95
30-49	Men	~95	~95
	Women	~95	~95
50-69	Men	~95	~95
	Women	~95	~95
70+	Men	~95	~95
	Women	~95	~95



Discussion and Findings

A horizontal bar chart comparing responses in 2009 (black bars) and 2012 (gray bars) across 12 demographic groups. The x-axis represents the percentage of respondents, ranging from 0 to 100. The y-axis lists the demographic groups. The chart shows that in 2009, a majority of respondents in all groups believed the current government was responsible for the economic crisis. By 2012, this belief had shifted significantly, with only 16% of the total respondents holding this view.

Group	2009 (%)	2012 (%)
Total	77	16
White	77	16
Black	77	16
Hispanic	77	16
Men	77	16
Women	77	16
18-29	77	16
30-49	77	16
50-64	77	16
65+	77	16
High school or less	77	16
College or more	77	16

Group	Percentage of respondents who believe the U.S. should take more action to address climate change
Total	~75%
Democrats	~85%
Republicans	~65%
Independents	~78%

Discussion and Findings

Country as our Healer

[illegible]

Figure.16 - Yerrabingin. 2026. Online Community Feedback Session 01.

Discussion and Findings

Country as our Legacy

Category	Number of people	Number of people with a job
1	100%	100%
2	100%	100%
3	100%	100%
4	100%	100%
5	100%	100%
6	100%	100%
7	100%	100%
8	100%	100%
9	100%	100%
10	100%	100%

[illegible]

• [REDACTED]

[REDACTED]

1 [REDACTED]

[REDACTED]

1 [REDACTED]

[REDACTED]

[REDACTED]

[REDACTED]

[REDACTED]

[REDACTED]

[REDACTED]

1 [REDACTED]

[REDACTED]

[REDACTED]

[REDACTED]

[REDACTED]

1 [REDACTED]

[REDACTED]

[REDACTED]

1 [REDACTED]

[REDACTED]

[REDACTED]

1 [REDACTED]

[REDACTED]

[REDACTED]




Figure.17 - Yerrabingin. 2026. Online Community Feedback Session 04.

DESIGN DEVELOPMENT

Elements of Country Exploration

The Deep Place in Country report shared an exploration of the Elements of Country across the Bruce Precinct Masterplan. This section elaborates on that exploration and looks at how the planned development interacts with the elements and therefore, how the elements need to be considered in the design. Zones related to the presence of the elements have been identified in the plan on the following page.

Some of the key interactions of the Elements within the proposed design can include:

Deep Country

- Reduction of excavation works.
- Re-use of materials from site where possible.
- Design in line with the natural topography of the land.

Water Country

- Consider how water travels through the site and maintain its natural flow and health.
- Capture, store and re-use of water.
- Plan for dryer seasonal periods will proposed vegetation.

Move with Country

- Consideration of Cultural heritage sites.
- Educational layer across the development to teach people about Community and their custodial roles within Country.
- Encouraging interaction for gathering, sharing and learning.

Wind Country

- Consider the movement of the prevailing winds. Protecting people from it and / or celebrating it.
- Develop a seasonal planting scheme to celebrate seasonal flourishes and changing time.

Sky Country

- Consideration of natural sunlight and openness to sky.
- Design to frame views out to significant landscapes.
- Orientate the development to existing landforms, highlighting views.

Non-human Kin Country

- Protect existing trees on the site where possible.
- Regeneration of healthy ecosystems.
- Propose vegetation to support habitat for non-human kin - building resilient landscape and habitats.
- Connect the development to surrounding reserves.
- Prioritise native / endemic planting.



Figure.18 - Yerrabingin. 2026. Details of site flora.

ELEMENTS OF COUNTRY

Site Exploration

The Elements of Country exploration above has shared key features of each element in and around the site that contribute to the unique nature of Country at the site. By looking at all of the elements, and considering them separately, and holistically, we can begin to understand some of the needs of Country in this place.

The image to the right shares the elements mapped spatially across the site. Reviewing where the elements are present within the site and how they might interact can help us understand how we could design for Country with respect to the elements.

- LEGEND
- Site Location
 - Water Country
 - Green Space & Vegetation
 - Lyneham Ridge Reserve
 - Bruce Ridge Nature Reserve
 - Black Mountain Nature Reserve
 - Gossan Hill Nature Reserve
 - Crace Grasslands Nature Reserve
 - Areas of Significance




Figure.19 - Yerrabingin. 2025. Elements of Country Exploration.

DESIGN DEVELOPMENT

DWC Opportunities

The design development to date has integrated the findings from the place analysis, Collaborative Design Workshops and Ideation Workshop into three key Designing with Country opportunities for the Canberra Aquatic Centre:



Country as our Teacher

We listen deeply to the needs of Country and walk together with our peers to foster connection. Drawing on Cultural knowledge, we observe the cues Country offers to understand how to maintain balance. This outcome recognises Country as a source of knowledge, guidance, and Cultural truth, inviting visitors and the local community to slow down, observe, and learn.



Country as our Healer

Health and wellbeing at the centre of Bruce, means a healthy Community, thus healthy Country. Promote physical, mental and Cultural wellbeing through nature, sport, recreation, and shared healing spaces. This theme requires us to heal Country so that Country can heal and bind community and kin.



Country as our Legacy

Legacy is established through practices of caring for Country and Non-human Kin, which allows for preservation of traditions, landscapes and ecological systems. This theme is all about building a resilient Country that will span across generations and thrive with time, leaving a lasting legacy of Place deep in time.

Figure.20 - Koichi Takada Architects. 2023. The Upper House Brisbane Figure.21 - Landezine, UDLA. 2018. Curtin University. Figure.22 - Yerrabingin. 2026. Textures of woodland Country.

DESIGN DEVELOPMENT

Country as our Teacher

We listen deeply to the needs of Country and walk together with our peers to foster connection. Drawing on Cultural knowledge, we observe the cues Country offers to understand how to maintain balance. This outcome recognises Country as a source of knowledge, guidance, and Cultural truth, inviting visitors and the local community to slow down, observe, and learn.

Across the workshops, Community emphasised learning from Country and sharing traditional Culture, stories, and environmental knowledge across generations. Key ideas included educational walking trails with QR codes, interpretive signage, interactive hubs, youth engagement, and connections between schools, hospitals, sport, and landscape. These perspectives frame the Bruce Precinct as a living classroom that fosters Cultural understanding, awareness, and stewardship.

Together, these ideas reflect a shared commitment to restoring Country as a living, visible presence embedded in the everyday spaces of the masterplan. Integrating and celebrating language and Cultural practices will enhance connection to Country.




Figure.23 - Yerrabingin. 2026. Windy grasslands. Figure.24 - Flickr. 2009. The Bat- Masked Owl. Figure.25 - Yerrabingin. 2026. Mossy bark details. Figure.26 - Koichi Takada Architects. 2023. The Upper House Brisbane. Figure.27 - Yerrabingin. 2026. New flora growth.

DESIGN DEVELOPMENT

Country as our Teacher

Opportunity

- Colours, textures, materials and tones of Deep Country and Non-Human Kin Country reflected through the architectural and open space design.
- Visual connections to Country, Culture and story telling - embedded through Indigenous artwork integrated into different design elements.
- Both formal and informal educational programs that support the sharing, continuation, and embedding of First Nations knowledge, Culture, and stories. This can include institution-based learning programs as well as more casual, self-guided opportunities such as signage, interpretation, and QR-enabled content.
- Opportunities to educate the community on Culturally significant features and kin specific to the project site and region. Through waterplay, interpretative design elements and signage.
- Provision of spaces that are safe, comfortable and inclusive for gathering and knowledge sharing.

Answering the How Might We

Country as our Teacher is an outcome that seeks to educate, connect and spark curiosity of place through visual and subtle cues of Country and Culture. These can include both formal and informal means of educating.

Yerrabingin Pillars

Custodianship and Legacy: Country as our Teacher holds the essence of Country across Culture, ritual, resources, stories, and Non-human Kin, all of which carry deep legacy and responsibility for stewardship.

Innovation: By learning and listening from Country we can know how to better take care of it.

Element of Country

This outcome offers a unique opportunity to engage all the Yerrabingin Elements of Country, with many ways to subtly reveal and celebrate each. Sky Country, Water Country, Deep Country, Non-Human Kin Country, Wind Country, and Move with Country.

Users

Both human and Non-human Kin users interacting with Country and learning more about the layered history of this region.



Figure.28 - Landezine, UDLA. 2018. Curtin University Gathering space. Figure.29 - Arcadia Landscape Architecture. 2020. St Leonards Health Organisation Relocation. Figure.30 - Christies. 2021. Green River Formation, Wyoming USA. Figure.31 - Jones, C, F. 2025. Plant Facility. Figure.32 - Yerrabingin. 2026. Non-human Kin - Echida. Figure.33 - Koichi Takada Architects. 2023. The Upper House Brisbane.

Country as our Teacher - Design Exploration



Figure.34 - Yerrabingin. 2026. Country as our Teacher, explorative visualisation.

DESIGN DEVELOPMENT

Country as our Healer

Health and wellbeing at the centre of Bruce, means a healthy Community, thus healthy Country. Promote physical, mental and Cultural wellbeing through nature, sport, recreation, and shared healing spaces. This theme requires us to heal Country so that Country can heal and bind community and kin.

Community highlighted creating spaces that support physical, mental, and Cultural wellbeing through interaction with nature, sport, and community-based activities. Ideas included accessible walking/cycling trails, shaded seating areas, and water-play spaces. With desire to ensure the hospital is integrated and continues to connect to its surrounding landscape. Additionally, there was strong support for reinforcing ‘Traditional Indigenous Games’ within the precinct - not only as recreation, but as a living expression of Culture in a place already dedicated to sport and health.

These perspectives frame the Bruce Precinct as a supportive environment where people can engage with Country, nurture their health, and experience wellbeing in connection with nature and Culture.




Figure.35 - Landezine, UDLA. 2018. Curtin University. Figure.36 - Clark, J. n.d. The Superb Parrot. Figure.37 - Fennessy, S. 2022. Miniscapes, Fisher House. Figure.38 - Yerrabingin. 2026. Learning and listening to Country. Figure.39 - Yerrabingin. 2026. Healing powers of Eucalyptus.

DESIGN DEVELOPMENT

Country as our Healer

Opportunity

- Outdoor gathering and healing spaces surrounded by bushtucker and medicinal planting.
- Specific areas for human kin and Non-Human Kin to dwell, supporting habitat for endemic flora and fauna species of the Bruce Precinct district.
- Minimise the removal of material from site, including soil, geology, flora and fauna to keep resources within the systems of Country and reduce disruption to the existing kinship networks as much as possible. These materials can be re-used and re-purposed within the design.
- Ensure a Cultural audit of the existing trees have been undertaken to protect key species.
- Promote health and wellbeing through carefully integrated walking and cycling tracks, outdoor healing spaces, outdoor classrooms, and sporting nodes.
- Bushtucker and medicinal planting gardens.

Answering the How Might We

Country as our Healer is an outcome that seeks to promote the health and wellbeing of all Kin, human and non-human, in a place already dedicated to sport, health, education and innovation. Leaving a lasting legacy of resilience and prosperity.

Yerrabingin Pillars

Custodianship and Legacy: Health and wellbeing at the centre enstills a sense of pride, responsibility and care across all Kin. Healthy community, means healthy Country. Regeneration: The repair and enhancement of endemic species ecologies and ecosystems. Innovation: By listening and learning from Country we can know how to better take care of it.

Element of Country

This outcome offers the opportunity to engage with: Move with Country, Non-human Kin Country, and Water Country.

Users

Human Kin: local residents, Canberra locals, workers, educators, students, doctors and athletes.
Non-human Kin users: endemic flora and fauna.




Figure.40 - Nancy Studio. n.d. Photograph Park China. Figure.41 - Mirvac. 2016. Harold Park. Figure.42 - Skarlakidis Architecture. 2017. Avatel Hotel. Figure.43 - City of Moreton Bay. n.d. Bushcare Volunteer Groups. Figure.44 - Peter, E. 2021. GROW Housing. Figure.45 - Yerrabingin. 2026. Healing from Country. Figure.47 - Jonas, V. 2017. Landezine, Cycling through the trees. Figure.46 - Doherty, Y. 2020. School of Indigenous Studies, UWA.

Country as our Healer - Design Exploration



Figure.48 - Yerrabingin. 2026. Country as our Healer, explorative visualisation.

DESIGN DEVELOPMENT

Country as our Legacy

Legacy is established through practices of caring for Country and Non-human Kin, which allows for preservation of traditions, landscapes and ecological systems. This theme is all about building a resilient Country that will span across generations and thrive with time, leaving a lasting legacy of Place deep in time.

Throughout all workshop groups, Community emphasised a strong custodial responsibility to care for Country through both ecological regeneration and protection, as well as the continuation of Cultural practice. Ideas around this included protecting remnant woodlands, restoring habitats and waterways, retaining mature trees, and applying Cultural practices of fire management when necessary. A strong push for governance guided by local Aboriginal Elders and First Nations working groups was seen as essential to embedding long-term care across the precinct. They also highlighted the importance of Cultural legacy - including ceremony, storytelling, and traditional Aboriginal games - as active expressions of ongoing custodianship.

Collectively, these ideas position the Bruce Precinct as a place where land, Culture, and community are cared for, ensuring responsibility is carried across generations.



Figure.49 - Yerrabingin. 2026. Flora budding. Figure.50 - Hatch. 2025. Images from the site visit. Figure.51 - Yerrabingin. 2026. Textures of woodland Country. Figure.52 - Kroll, M. 2021. Pink microfern. Figure.53 - Alamy Stock Photos (n.d.) Gang-gang Cockatoos.

DESIGN DEVELOPMENT

Country as our Legacy

Opportunity

- Acknowledgement of Country upon arrival and celebration of famous First Nations athletes, educators and students across the Precinct - ensuring legacy of place is carried throughout generations.
- Designing a balance of gathering and knowledge sharing spaces that are formal/informal, internal/external and in a variety of shapes and scales.
- Opportunity for First Nations Community driven art strategy unique to this Country and its legacy.
- Ensure a range of shaded outdoor areas, meeting places and BBQ areas. Allowing opportunity for community gathering, celebrating and being.
- Establish resilience of existing Non-human Kin and their habitats while inviting species back in that once existed here.
- Support opportunities for First Nations led Cultural maintenance programs. For example, implementing Rangers program with NRM (National Resource Management) team.

Answering the How Might We

Country as our Legacy is the outcome that seeks to embed the enduring presence of Country, it’s Culture and unique stories of place, deep in time and into the future.

Yerrabingin Pillars

Custodianship and Legacy: By honouring and acknowledging past and present Cultural traditions, ceremonies and stories, ensures a legacy of all kin and Country, carried into the future.

Regeneration: By repair of traditions, revitalising of disconnected ecosystems and strengthening of social recognition, we can foster a strong legacy of place across generations.

Element of Country

This outcome offers the opportunity to engage with Non-Human Kin Country, and Move with Country.

Users

Human Kin: First Nations Communities and families, local residents, Canberra locals, workers, educators, students, doctors and athletes.

Non-human Kin users: endemic flora and fauna on site and their living systems.




Figure.54 - Jim Sanborn. 2009. The Meridian. Figure.55 - Krall, M. 2021. Pink microfern. Figure.56 - Green Adelaide. 2022. Kaurna cultural burn. Figure.57 - Landezine, UDLA. 2018. Curtin University Gathering space. Figure.58 - Dan Stockholm. 2016. By Hand. Figure.59 - Doherty, Y. 2020. School of Indigenous Studies, UWA. Figure.60 - Tide. n.d. Monero-Ngarigo Welcome to Country.

Country as our Legacy - Design Exploration



Figure.61 - Yerrabingin. 2026. Country as our Legacy, explorative visualisation.

DESIGN DEVELOPMENT

Opportunities Across the Site

This plan includes the proposed key Connecting with Country opportunities presented in the above pages mapped onto the proposed site plan.

Country as our Teacher

- 1. Celebrate colours, textures, materials and tones of deep Country + Non-Human Kin Country
- 2. Formal / informal education opportunities and meeting places
- 3. Educate and teach about Country through play, art and interperative design elements / signage

Country as our Healer

- 4. Supporting habitats of existing endemic flora and fauna
- 5. Nature-based walking and cycling trails
- 6. Outdoor healing spaces and classrooms
- 7. Bushtucker and medicinal planting nodes
- 8. Green links, wildlife tunnels and passages for Kin

Country as our Legacy

- 9. Acknowledgement of Country and celebration of significant First Nations figures of the past
- 10. First Nations Rangers Bushfire Management Strategy
- 11. Preserve and restore the Pink Lakes




Figure.62 - Yerrabingin. 2026. Mapping opportunities across the site.

PROJECT LEGACY

Future of Connecting with Country at Bruce

We have followed our Collaborative Design process to first define our design challenge, and then with the project team and Aboriginal community members, worked together to develop a solution to our challenge in the form of an answer to our How Might We Question as shared in the above opportunities.

At the beginning of the process, Yerrabingin identified the opportunity to explore bringing the four pillars into the design solution, and our process has focused on developing design solutions that will achieve long term outcomes at the project site.

Together, *Country as our Teacher*, *Country as our Healer*, and *Country as our Legacy*- will contribute to bringing the pillars to life at the site in the short term, and into the future.



Figure.63 - Yerrabingin. 2026. Views to Black Mountain.

FIGURES LIST

Figure.1 - Nearmap. 2026. Aerial photo of site location - Suburb of Bruce.	Figure.11 - Yerrabingin. 2025. Collection of images from the online How Might We? session. Authors own images.	Figure.23 - Yerrabingin. 2026. Windy grasslands. Authors own image.
Figure.2 - Yerrabingin. 2026. Freshwater Lakes. Authors own image.	Figure.12 - Yerrabingin. 2025. Collection of images from the online How Might We? session. Authors own images.	Figure.39 - Yerrabingin. 2026. Healing powers of Eucalyptus. Authors own image.
Figure.3 - Kroll, M. 2021. Pinker Pond Bruce - site image. https://region.com.au/pinklake-the-secrets-of-canberras-hidden-natural-phenomenon/498063/ .	Figure.13 - Yerrabingin. 2026. Image from our online Ideation Workshop. Authors own image.	Figure.24 - Flickr. 2009. The Bat- Masked Owl.
Figure.4 - Yerrabingin. 2026. We inhabit and are inhabited by Country. Authors own info-graphic.	Figure.14 - Yerrabingin. 2026. Collection of images from our online Ideation Workshop. Authors own images.	Figure.25 - Yerrabingin. 2026. Mossy bark details. Authors own image.
Figure.5 - Yerrabingin. 2026. Methodology Process. Authors own info-graphic.	Figure.15 - Yerrabingin. 2026. Online Community Feedback Session 01. Authors own image.	Figure.26 - Koichi Takada Architects. 2023. The Upper House
Figure.6 - Canberra Daily. n.d. The 'Pink Lake' in Bruce with its blanket	Figure.16 - Yerrabingin. 2026. Online Community Feedback Session 01. Authors own image.	Figure.37 - Koichi Takada Architects. 2023. The Upper House
Figure.7 - Gininderra Catchment. n.d. Ginninderra Creek in northern Canberra. https://gininderralandcare.org.au/aboriginal-landcare/ . Accessed: March, 2026.	Figure.17 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.38 - Yerrabingin. 2026. Learning and listening to Country. Authors own image.
Figure.8 - Australian Wildlife. n.d. Gang-gang Cockatoo. https://www.australianwildlife.org/animals/gang-gang-cockatoo?s	Figure.18 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.40 - Nancy Studio. n.d. Photograph Park China. https://mooolol.com/en/2022/04/20/photograph-park-china/
Figure.9 - Canberra Daily. n.d. The 'Pink Lake' in Bruce with its blanket	Figure.19 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.41 - Nancy Studio. n.d. Photograph Park China. https://mooolol.com/en/2022/04/20/photograph-park-china/
Figure.10 - Canberra Daily. n.d. The 'Pink Lake' in Bruce with its blanket	Figure.20 - Koichi Takada Architects. 2023. The Upper House	Figure.42 - Nancy Studio. n.d. Photograph Park China. https://mooolol.com/en/2022/04/20/photograph-park-china/
Figure.11 - Yerrabingin. 2025. Collection of images from the online How Might We? session. Authors own images.	Figure.21 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.43 - City of Moreton Bay. n.d. Bushcare Volunteer Groups.
Figure.12 - Yerrabingin. 2025. Collection of images from the online How Might We? session. Authors own images.	Figure.22 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.44 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.13 - Yerrabingin. 2026. Image from our online Ideation Workshop. Authors own image.	Figure.23 - Yerrabingin. 2026. Windy grasslands. Authors own image.	Figure.45 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.14 - Yerrabingin. 2026. Collection of images from our online Ideation Workshop. Authors own images.	Figure.24 - Flickr. 2009. The Bat- Masked Owl.	Figure.46 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.15 - Yerrabingin. 2026. Online Community Feedback Session 01. Authors own image.	Figure.25 - Yerrabingin. 2026. Mossy bark details. Authors own image.	Figure.47 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.16 - Yerrabingin. 2026. Online Community Feedback Session 01. Authors own image.	Figure.26 - Koichi Takada Architects. 2023. The Upper House	Figure.48 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.17 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.27 - Koichi Takada Architects. 2023. The Upper House	Figure.49 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.18 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.28 - Koichi Takada Architects. 2023. The Upper House	Figure.50 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.19 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.29 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.51 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.20 - Koichi Takada Architects. 2023. The Upper House	Figure.30 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.52 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.21 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.31 - Jones, C, F. 2025. Plant Facility. https://www.archdaily.com/1044444/plant-facility	Figure.53 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.22 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.32 - Yerrabingin. 2026. Non-human Kin - Echida. Authors own image.	Figure.54 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.23 - Yerrabingin. 2026. Windy grasslands. Authors own image.	Figure.33 - Koichi Takada Architects. 2023. The Upper House	Figure.55 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.24 - Flickr. 2009. The Bat- Masked Owl.	Figure.34 - Koichi Takada Architects. 2023. The Upper House	Figure.56 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.25 - Yerrabingin. 2026. Mossy bark details. Authors own image.	Figure.35 - Koichi Takada Architects. 2023. The Upper House	Figure.57 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.26 - Koichi Takada Architects. 2023. The Upper House	Figure.36 - Koichi Takada Architects. 2023. The Upper House	Figure.58 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.27 - Koichi Takada Architects. 2023. The Upper House	Figure.37 - Koichi Takada Architects. 2023. The Upper House	Figure.59 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.28 - Koichi Takada Architects. 2023. The Upper House	Figure.38 - Yerrabingin. 2026. Learning and listening to Country. Authors own image.	Figure.60 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.29 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.39 - Yerrabingin. 2026. Healing powers of Eucalyptus. Authors own image.	Figure.61 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.30 - Yerrabingin. 2026. Online Community Feedback Session 04. Authors own image.	Figure.40 - Nancy Studio. n.d. Photograph Park China. https://mooolol.com/en/2022/04/20/photograph-park-china/	Figure.62 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.31 - Jones, C, F. 2025. Plant Facility. https://www.archdaily.com/1044444/plant-facility	Figure.41 - Nancy Studio. n.d. Photograph Park China. https://mooolol.com/en/2022/04/20/photograph-park-china/	Figure.63 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.32 - Yerrabingin. 2026. Non-human Kin - Echida. Authors own image.	Figure.42 - Nancy Studio. n.d. Photograph Park China. https://mooolol.com/en/2022/04/20/photograph-park-china/	Figure.64 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.33 - Koichi Takada Architects. 2023. The Upper House	Figure.43 - City of Moreton Bay. n.d. Bushcare Volunteer Groups.	Figure.65 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility
Figure.34 - Koichi Takada Architects. 2023. The Upper House	Figure.44 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility	Figure.66 - Peter, E. 2021. GROW Housing. https://www.archdaily.com/1044444/plant-facility

FIGURES LIST

Figure.46 - Doherty, Y. 2020. School of Indigenous Studies, UWA.

KWWSV ZZZ XGOD FRP DX SURMHFWV ELO\DPDUHHSXZDDQGHJLQH FRP FXUWLQ XQLYHUVLW\ LQGLIHORXY QH\DUQLQJ FLUEOH F\ (FRORJLEFDO &RPPXQLW\ \$FWLRQ 3ODQ KWWSV \$VZZZVMDHQWRQPHQW YHFUWJWV KWWSV EUXFHU
udla/.
)LJXUH 6NDUODNLGLV \$UFKLWHFWXUH \$YDWHO +RWHO KWWSV ZZZ
VNDUODNLGLV DUFKLWHFWXUH FRP SURMHFWV

)LJXUH /DQGHJLQH 8'/\$ &XUWLQ 8QLYHUVLW\ *DWKHULQJ VSDFH
\$&7 *RYHUQPHQW 1DWXUDO 7HPSHUDWH *UDVRODQG (QG8QLYHUVLW\ RI &DQEHUUD \$&7 \$E
LQGLIHORXY QH\DUQLQJ FLUEOH F\ (FRORJLEFDO &RPPXQLW\ \$FWLRQ 3ODQ KWWSV \$VZZZVMDHQWRQPHQW YHFUWJWV KWWSV EUXFHU
udla/.
DX BBGDWD DVVHWV SGIB4OH *UDVVODQG 6WUDWHJ\)LQDO :H
bAccess-Part-B-1-Natl-Temperate-Grassland.pdf *RYHUQPHQW \$UFKLWHFW 16: 'HVLJQLQJ

Figure.49 - Doherty, Y. 2020. School of Indigenous Studies, UWA.

KWWSV ZZZ XGOD FRP DX SURMHFWV ELO\DPDUHHSXZDDQGHJLQH FRP FXUWLQ XQLYHUVLW\ LQGLIHORXY QH\DUQLQJ FLUEOH F\ (FRORJLEFDO &RPPXQLW\ \$FWLRQ 3ODQ KWWSV \$VZZZVMDHQWRQPHQW YHFUWJWV KWWSV EUXFHU

Figure.45 - Yerrabingin. 2026. Healing from Country. Authors own image.

)LJXUH <HUUDELQJLQ &RXQWU\ DV RXUPHODNDU498063 ORUDWLYH
YLVXDOLVDWLRQ \$XWKRUV RZQ YLVXDOLVDWLRQ

Figure.55 - Kroll, M. 2021. Pink microfern. <https://region.com.au/pinklake-the-secrets-of-canberras-hidden-natural-phenomenon/498063/>.

)LJXUH <HUUDELQJLQ &RXQWU\ DV RXUPHODNDU498063 ORUDWLYH
YLVXDOLVDWLRQ \$XWKRUV RZQ YLVXDOLVDWLRQ

Figure.49 - Yerrabingin. 2026. Flora budding. Authors own image.

Figure.60 - Tide. n.d. Monero-Ngarigo Welcome to Country. <https://region.com.au/pinklake-the-secrets-of-canberras-hidden-natural-phenomenon/498063/>. Accessed: March, 2026.

LQWHUSUHWLYHGHVLJQ FRP DX SURMHFWV ZHORJPHWR FRXQWU\ VLJQDJH

Figure.53 - Alamy Stock Photos (n.d.) Gang-gang Cockatoos. <https://www.alamy.com/stock-photo-gang-gang-cockatoos-image123456789.html>.

ZZZ LQVWDJUDP FRP S '5 <7' \$YV2 \$FFHVVHG
)LJXUH +DWFK -PDJHV IURP WKH VLWH YLVLW

Figure.58 - Dan Stockholm. 2016. By Hand. <http://danstockholm.com/byhand.html>.

Figure.58 - Dan Stockholm. 2016. By Hand. <http://danstockholm.com/byhand.html>.

Figure.51 - Yerrabingin. 2026. Textures of woodland Country. Authors own image.

Figure.56 - Green Adelaide. 2022. Kurna cultural burn. <https://www.greenadelaide.com.au/cultural-burn/>.

JUHHQDGHODLGH VD JRY DX QHZV FXOWXUDO EXUQLQJ VRXWK DXVWUDOLD
)LJXUH <HUUDELQJLQ &RXQWU\ DV RXUPHODNDU498063 ORUDWLYH
YLVXDOLVDWLRQ \$XWKRUV RZQ YLVXDOLVDWLRQ

Figure.52 - Kroll, M. 2021. Pink microfern. <https://region.com.au/pinklake-the-secrets-of-canberras-hidden-natural-phenomenon/498063/>.

)LJXUH -LP 6DQERUQ 7KH 0HULGLDQ KWWSV ZZZ MLPVDQERUQ
net/main.html?utm_source=Pinterest&utm_medium=organic.

Figure.62 - Yerrabingin. 2026. Mapping opportunities across the site. Authors own mapping.

Figure.63 - Yerrabingin. 2026. Views to Black Mountain. Authors own image.

REFERENCES

ACT Heritage Council, 2017, Background Information: Corroboree-
*URXQG DQG \$ERULJLQDO &XOWXUDO \$UHD 48HBDQGHDDQSHLYHD \$VH VWXGLHV FRQQHFWLQJ Z
pdf?la=e.
\$(&20 8QLYHUVLW\ RI &DQEHUUD 0DVWHU SODQ +LVWRULF +HULWDJH
3DUNV \$&7 %UXFH 5LGJH 1DWXUH 5HVHUYH
JRY DX 4QG D QDWXUH SDUN FDQEHUUD-QDWXUH
\$(&20 6WRUPZDWHU 0DQDJHPHQW 30DQ 8QLYHUVLW\ RI &DQEHUUD
Campus Community.
\$(&20 &R[8QLYHUVLW\ RI &DQEHUUD &DPSXWHULPHQLW\3URM
ect. Urban Design Master Plan Report.
ANU Aboriginal and Torres Strait Islander Heritage Trail, n.d. Aborigi-
nal Heritage Trail
\$(&20 &R[8QLYHUVLW\ RI &DQEHUUD &DPSXWHULPHQLW\3URM
ect. Urban Design Master Plan Report.
ANU Aboriginal and Torres Strait Islander Heritage Trail, n.d. Aborigi-
nal Heritage Trail

ACT Heritage Council, 2017, Background Information: Corroboree-
*URXQG DQG \$ERULJLQDO &XOWXUDO \$UHD 48HBDQGHDDQSHLYHD \$VH VWXGLHV FRQQHFWLQJ Z
pdf?la=e.
\$(&20 8QLYHUVLW\ RI &DQEHUUD 0DVWHU SODQ +LVWRULF +HULWDJH
3DUNV \$&7 %UXFH 5LGJH 1DWXUH 5HVHUYH
JRY DX 4QG D QDWXUH SDUN FDQEHUUD-QDWXUH
\$(&20 6WRUPZDWHU 0DQDJHPHQW 30DQ 8QLYHUVLW\ RI &DQEHUUD
Campus Community.
\$(&20 &R[8QLYHUVLW\ RI &DQEHUUD &DPSXWHULPHQLW\3URM
ect. Urban Design Master Plan Report.
ANU Aboriginal and Torres Strait Islander Heritage Trail, n.d. Aborigi-
nal Heritage Trail

\$(&20 8QLYHUVLW\ RI &DQEHUUD 0DVWHU SODQ +LVWRULF +HULWDJH
3DUNV \$&7 %UXFH 5LGJH 1DWXUH 5HVHUYH
JRY DX 4QG D QDWXUH SDUN FDQEHUUD-QDWXUH
\$(&20 6WRUPZDWHU 0DQDJHPHQW 30DQ 8QLYHUVLW\ RI &DQEHUUD
Campus Community.
\$(&20 &R[8QLYHUVLW\ RI &DQEHUUD &DPSXWHULPHQLW\3URM
ect. Urban Design Master Plan Report.
ANU Aboriginal and Torres Strait Islander Heritage Trail, n.d. Aborigi-
nal Heritage Trail

\$(&20 &R[8QLYHUVLW\ RI &DQEHUUD &DPSXWHULPHQLW\3URM
ect. Urban Design Master Plan Report.
ANU Aboriginal and Torres Strait Islander Heritage Trail, n.d. Aborigi-
nal Heritage Trail

ANU Aboriginal and Torres Strait Islander Heritage Trail, n.d. Aborigi-
nal Heritage Trail

ANU Aboriginal and Torres Strait Islander Heritage Trail, n.d. Aborigi-
nal Heritage Trail

Figure.62 - Yerrabingin. 2026. Mapping opportunities across the site.

net/main.html?utm_source=Pinterest&utm_medium=organic.



YERRABINGIN

WE ARE YERRABINGIN. WE WALK TOGETHER.

DISCLAIMER & COPYRIGHT

This document was prepared for the exclusive use of DITRDCSA. Hatch acts in all professional matters as a faithful advisor to its clients and exercises all reasonable skill and care in the provision of its professional services. The information presented herein has been compiled from a number of sources using a variety of methods. Hatch does not attempt to verify the accuracy, validity or comprehensiveness of any information supplied to Hatch by third parties. The development parameters (dwelling yields, stages etc) referred to in this report may vary over time. The figures contained herein are estimates; they represent a good approximation of likely development outcomes to a sufficient level of accuracy for the purposes of this report. Hatch makes no warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, validity or comprehensiveness of this document, or the misapplication or misinterpretation by third parties of its contents. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favouring by Hatch.

This document cannot be copied or reproduced in whole or part for any purpose without the prior written consent of Hatch.

© Hatch Pty Ltd, 2025

Hatch
Level 3, 50 Carrington Street, Sydney NSW 2000
T: +612 8202 8000